International Standards and Recommended Practices



Annex 4 to the Convention on International Civil Aviation

Aeronautical Charts

This edition incorporates all amendments adopted by the Council prior to 8 March 2001 and supersedes, on 1 November 2001, all previous editions of Annex 4.

For information regarding the applicability of Standards and Recommended Practices, see Chapter 1 and the Foreword.

Tenth Edition July 2001

AMENDMENTS

The issue of amendments is announced regularly in the *ICAO Journal* and in the monthly *Supplement to the Catalogue of ICAO Publications and Audio-visual Training Aids*, which holders of this publication should consult. The space below is provided to keep a record of such amendments.

RECORD OF AMENDMENTS AND CORRIGENDA

AMENDMENTS						
No.	Date applicable	Date entered	Entered by			
1-52	Ir	corporated in thi	s edition			

CORRIGENDA					
No.	Date of issue	Date entered	Entered by		

TABLE OF CONTENTS

		Page			Page
FOREW	ORD	(vii)	4.3	Units of measurement	4-1
			4.4	Coverage and scale	4-1
CHAPTI	ER 1. Definitions, applicability and		4.5	Format	4-1
availabili	ity	1-1	4.6	Identification	4-1
			4.7	Culture and topography	4-1
1.1	Definitions	1-1	4.8	Magnetic variation	4-2
1.2	Applicability	1-5	4.9	Aeronautical data	4-2
1.3	Availability	1-5	4.10	Accuracy	4-2
СНАРТІ	ER 2. General specifications	2-1			
				ER 5. Aerodrome Obstacle Chart —	
2.1	Operational requirements for charts	2-1	ICAO Ty	ype C	5-1
2.2	Titles	2-1			
2.3	Miscellaneous information	2-1	5.1	Function	5-1
2.4	Symbols	2-1	5.2	Availability	5-1
2.5	Units of measurement	2-2	5.3	Coverage and scale	5-1
2.6	Scale and projection	2-2	5.4	Format	5-1
2.7	Date of validity of aeronautical		5.5	Identification	5-1
2.7	information	2-2	5.6	Magnetic variation	5-1
2.8	Spelling of geographical names	2-2	5.7	Units of measurement	5-2
2.9	Abbreviations	2-2	5.8	Aeronautical data	5-2
			5.9	Accuracy	5-2
2.10	Political boundaries	2-2	3.7	Tiocaracy	0 2
2.11	Colours	2-2			
2.12	Relief	2-3	СНАРТЕ	ER 6. Precision Approach Terrain Chart —	
2.13	Prohibited, restricted and danger areas	2-3		EK 0. Frecision Approach Terrain Chart —	6-1
2.14	Air traffic services airspaces	2-3	ICAU		0-1
2.15	Magnetic variation	2-3	6.1	Function	6-1
2.16	Typography	2-3	6.2	Availability	6-1
2.17	Aeronautical data	2-3	6.3	Scale	6-1
2.18	World Geodetic System — 1984		6.4	Identification	6-1
	(WGS-84)	2-4	6.5	Plan and profile information	6-1
	ER 3. Aerodrome Obstacle Chart —				
ICAO T	ype A (Operating Limitations)	3-1	CHAPTI	ER 7. Enroute Chart — ICAO	7-1
3.1	Function	3-1	7.1	Function	7-1
3.2	Availability	3-1	7.2	Availability	7-1
3.3	Units of measurement	3-1	7.3	Coverage and scale	7-1
3.4	Coverage and scale	3-1	7.4	Projection	7-1
3.5	Format	3-1	7.5	Identification	7-1
3.6	Identification	3-1	7.6	Culture and topography	7-1
3.7	Magnetic variation	3-2	7.0 7.7		7-1 7-1
3.8	Aeronautical data	3-2		Magnetic variation	
3.9		3-2	7.8	Bearings, tracks and radials	7-1
	Accuracy	5-5	7.9	Aeronautical data	7-2
	ER 4. Aerodrome Obstacle Chart —	4 1	~~-·-·		_
ICAU I	ype B	4-1	CHAPTE	ER 8. Area Chart — ICAO	8-1
4.1	Function	4-1	8.1	Function	8-1
4.2	Availability	4-1	8.2	Availability	8-1

		Page			Page
8.3	Coverage and scale	8-1	12.5	Projection	12-1
8.4	Projection	8-1	12.6	Identification	12-1
8.5	Identification	8-1	12.7	Culture and topography	12-1
8.6	Culture and topography	8-1	12.8	Magnetic variation	12-1
8.7	Magnetic variation	8-1	12.9	Bearings, tracks and radials	12-2
8.8	Bearings, tracks and radials	8-2	12.10	Aeronautical data	12-2
8.9	Aeronautical data	8-2			
			CHAPTE	R 13. Aerodrome/Heliport Chart — ICAO	13-1
	ER 9. Standard Departure Chart —	0.1	13.1	Function	13-1
Instrume	nt (SID) — ICAO	9-1	13.2	Availability	13-1
9.1	Function	9-1	13.3	Coverage and scale	13-1
9.2	Availability	9-1	13.4	Identification	13-1
9.3	Coverage and scale	9-1	13.5	Magnetic variation	13-1
9.4	Projection	9-1	13.6	Aerodrome/heliport data	13-1
9.5	Identification	9-1		•	
9.6	Culture and topography	9-1			
9.7	Magnetic variation	9-2	CHAPTE	R 14. Aerodrome Ground Movement	
9.8	Bearings, tracks and radials	9-2	Chart —	ICAO	14-1
9.9	Aeronautical data	9-2		.	
			14.1	Function	14-1
			14.2	Availability	14-1
CHAPTE	ER 10. Standard Arrival Chart —		14.3	Coverage and scale	14-1
	nt (STAR) — ICAO	10-1	14.4	Identification	14-1
	(2)		14.5	Magnetic variation	14-1
10.1	Function	10-1	14.6	Aerodrome data	14-1
10.2	Availability	10-1			
10.3	Coverage and scale	10-1	СПУВТЕ	D 15 Aircraft Parking/Dooking Chart	
10.4	Projection	10-1		R 15. Aircraft Parking/Docking Chart —	15-1
10.5	Identification	10-1	icao	• • • • • • • • • • • • • • • • • • • •	13-1
10.6	Culture and topography	10-1	15.1	Function	15-1
10.7	Magnetic variation	10-2	15.2	Availability	15-1
10.8	Bearings, tracks and radials	10-2	15.3	Coverage and scale	15-1
10.9	Aeronautical data	10-2	15.4	Identification	15-1
			15.5	Magnetic variation	15-1
			15.6	Aerodrome data	15-1
	ER 11. Instrument Approach Chart —	11-1			
10110 11			СНАРТЕ	R 16. World Aeronautical Chart —	
11.1	Function	11-1		000 000	16-1
11.2	Availability	11-1	10/10/1.1		10-1
11.3	Coverage and scale	11-1	16.1	Function	16-1
11.4	Format	11-1	16.2	Availability	16-1
11.5	Projection	11-1	16.3	Scales	16-1
11.6	Identification	11-1	16.4	Format	16-1
11.7	Culture and topography	11-2	16.5	Projection	16-2
11.8	Magnetic variation	11-2	16.6	Identification	16-2
11.9	Bearings, tracks and radials	11-2	16.7	Culture and topography	16-2
11.10	Aeronautical data	11-3	16.8	Magnetic variation	16-4
			16.9	Aeronautical data	16-4
СНАРТІ	ER 12. Visual Approach Chart — ICAO	12-1			
10.1	Eron et au	10 1		R 17. Aeronautical Chart —	
12.1	Function	12-1	ICAO 1:5	500 000	17-1
12.2	Availability	12-1	17 1	Eurotion	17 1
12.3	Scale	12-1	17.1	Function.	17-1
12.4	Format	12-1	17.2	Availability	17-1

 $1/11/01 \qquad \qquad (iv)$

		Page	i	Page
17.3	Scales	17-1	19.8 Magnetic variation	19-1
17.4	Format	17-1	19.9 Aeronautical data	19-2
17.5	Projection	17-1		
17.6	Identification	17-2		
17.7	Culture and topography	17-2	CHAPTER 20. Electronic Aeronautical	
17.8	Magnetic variation	17-3	Chart Display — ICAO	20-1
17.9	Aeronautical data	17-3	• •	
			20.1 Function	20-1
			20.2 Information available for display	20-1
CHAPTI	ER 18. Aeronautical Navigation Chart —			20-1
ICAO Sı	mall Scale	18-1	20.4 Provision and updating of data	20-2
			20.5 Performance tests, malfunction alarms	
18.1	Function	18-1	and indications	20-2
18.2	Availability	18-1	20.6 Back-up arrangements	20-2
18.3	Coverage and scale	18-1	• •	
18.4	Format	18-1		
18.5	Projection	18-1	APPENDICES	
18.6	Culture and topography	18-2		
18.7	Magnetic variation	18-3	APPENDIX 1. Marginal note layout APF	' 1-1
18.8	Aeronautical data	18-3		
			APPENDIX 2. ICAO chart symbols APF	2-1
СНАРТІ	ER 19. Plotting Chart — ICAO	19-1	APPENDIX 3. Colour guide	3-1
19.1	Function	19-1	APPENDIX 4. Hypsometric tint guide APF	' 4-1
19.2	Availability	19-1		
19.3	Coverage and scale	19-1	APPENDIX 5. Sheet layout index for the World	
19.4	Format	19-1	Aeronautical Chart — ICAO 1:1 000 00 APF	5 -1
19.5	Projection	19-1		
19.6	Identification	19-1	APPENDIX 6. Aeronautical data quality	
10.7	Culture and topography	10 1	- · · ·	6 1

(v) 1/11/01

FOREWORD

Historical background

Standards and Recommended Practices for Aeronautical Charts were first adopted by the Council on 16 April 1948, pursuant to the provisions of Article 37 of the Convention on International Civil Aviation (Chicago, 1944), and were designated as Annex 4 to the Convention. They became applicable on 1 March 1949.

Table A shows the origin of subsequent amendments together with a list of the principal subjects involved and the dates on which the Annex and the amendments were adopted by the Council, when they became effective and when they became applicable.

Action by Contracting States

Notification of differences. The attention of Contracting States is drawn to the obligation imposed by Article 38 of the Convention by which Contracting States are required to notify the Organization of any differences between their national regulations and practices and the International Standards contained in this Annex and any amendments thereto. Contracting States are invited to extend such notification to any differences from the Recommended Practices contained in this Annex, and any amendments thereto when the notification of such differences is important for the safety of air navigation. Further, Contracting States are invited to keep the Organization currently informed of any differences which may subsequently occur, or of the withdrawal of any differences previously notified. A specific request for notification of differences will be sent to Contracting States immediately after the adoption of each Amendment to this Annex.

The attention of States is also drawn to the provisions of Annex 15 related to the publication of differences between their national regulations and practices and the related ICAO Standards and Recommended Practices through the Aeronautical Information Service, in addition to the obligation of States under Article 38 of the Convention.

Promulgation of information. Information relating to the availability and amendment of aeronautical charts affecting aircraft operations, provided according to the Standards, Recommended Practices and Procedures specified in this Annex, should be notified and take effect in accordance with Annex 15.

Status of Annex components

An Annex is made up of the following component parts, not all of which, however, are necessarily found in every Annex; they have the status indicated:

- 1.— Material comprising the Annex proper:
 - a) Standards and Recommended Practices adopted by the Council under the provisions of the Convention. They are defined as follows:

Standard. Any specification for physical characteristics, configuration, matériel, performance, personnel or procedure, the uniform application of which is recognized as necessary for the safety or regularity of international air navigation and to which Contracting States will conform in accordance with the Convention; in the event of impossibility of compliance, notification to the Council is compulsory under Article 38.

Recommended Practice. Any specification for physical characteristics, configuration, matériel, performance, personnel or procedure, the uniform application of which is recognized as desirable in the interests of safety, regularity or efficiency of international air navigation, and to which Contracting States will endeavour to conform in accordance with the Convention.

- b) Appendices comprising material grouped separately for convenience but forming part of the Standards and Recommended Practices adopted by the Council.
- c) Definitions of terms used in the Standards and Recommended Practices which are not selfexplanatory in that they do not have accepted dictionary meanings. A definition does not have an independent status but is an essential part of each Standard and Recommended Practice in which the term is used, since a change in the meaning of the term would affect the specification.
- d) Tables and Figures which add to or illustrate a Standard or Recommended Practice and which are referred to therein, form part of the associated Standard or Recommended Practice and have the same status.

Annex 4 — Aeronautical Charts Foreword

2.— Material approved by the Council for publication in association with the Standards and Recommended Practices:

- a) Forewords comprising historical and explanatory material based on the action of the Council and including an explanation of the obligations of States with regard to the application of the Standards and Recommended Practices ensuing from the Convention and the Resolution of Adoption.
- b) Introductions comprising explanatory material introduced at the beginning of parts, chapters or sections of the Annex to assist in the understanding of the application of the text.
- c) Notes included in the text, where appropriate, to give factual information or references bearing on the Standards or Recommended Practices in question, but not constituting part of the Standards or Recommended Practices.
- d) Attachments comprising material supplementary to the Standards and Recommended Practices, or included as a guide to their application.

Selection of language

This Annex has been adopted in five languages — English, Arabic, French, Russian and Spanish. Each Contracting State

is requested to select one of those texts for the purpose of national implementation and for other effects provided for in the Convention, either through direct use or through translation into its own national language, and to notify the Organization accordingly.

Editorial practices

The following practice has been adhered to in order to indicate at a glance the status of each statement: *Standards* have been printed in light face roman; *Recommended Practices* have been printed in light face italics, the status being indicated by the prefix **Recommendation**; *Notes* have been printed in light face italics, the status being indicated by the prefix *Note*.

It is to be noted that in the English text the following practice has been adhered to when writing the specifications: Standards employ the operative verb "shall" while Recommended Practices employ the operative verb "should".

Throughout this document measurements are given in the metric system followed in parentheses by corresponding measurements in the foot-pound system.

Any reference to a portion of this document, which is identified by a number and/or title, includes all subdivisions of that portion.

Table A. Amendments to Annex 4

Amendment	Source(s)	Subject(s)	Adopted Effective Applicable
1st Edition	Aeronautical Charts Division, First Session (November 1945), Second Session (April 1946), Third Session (January 1947)	World Aeronautical Chart (WAC) — ICAO 1:1 000 000; Instrument Approach and Landing Charts; Aeronautical Charts 1:500 000; Aeronautical Charts 1:250 000; Aeronautical Plotting Charts; Aeronautical Route Charts; Aeronautical Planning Charts.	16 April 1948 1 November 1948 1 March 1949
Amendment No. 1 included in 1st Edition	Aeronautical Charts Division, Fourth Session (March 1948)	Projection of WAC — ICAO 1:1 000 000.	6 December 1948 15 March 1949 15 March 1949
2nd Edition including Amendments 2-22	Aeronautical Charts Division, Fourth Session (March 1948)	Definitions; WAC — ICAO 1:1 000 000; Aeronautical Charts — ICAO 1:500 000; Aeronautical Charts — ICAO 1:250 000; Instrument Approach Charts — ICAO; Instrument Landing Charts — ICAO; Radio Facility Charts.	15 November 1949 1 June 1950 1 September 1950
23-28	Other activities of the Council	Abbreviations; Chart Symbols; Definitions.	25 June 1951 1 November 1951 1 January 1952

1/11/01 (viii)

Amendment	Source(s)	Subject(s)	Adopted Effective Applicable
29	Aeronautical Charts Division, Fifth Session (October 1951)	Definitions; WAC — ICAO 1:1 000 000; Aeronautical Charts — ICAO 1:500 000; Aeronautical Charts — ICAO 1:250 000; Approach Charts — ICAO; Landing Charts — ICAO; Aeronautical Plotting Charts — ICAO; Radio Facility Charts; ICAO Chart Symbols; Aerodrome Obstruction Plans and Profiles — ICAO.	19 June 1952 1 December 1952 1 April 1953
30	Action by Air Navigation Commission in consultation with States	Removal of inconsistencies between Annexes 4 and 15.	22 February 1956 1 July 1956 1 December 1956
31, 32	Third Air Navigation Conference (October 1956); Recommendation of the Air Navigation Commission	Aerodrome Obstruction Charts; editorial amendments; ICAO Chart Symbols.	13 June 1957 1 October 1957 1 December 1957
33	Action by Air Navigation Commission in consultation with States	Application of Definitions of Danger Area, Prohibited Area and Restricted Area (Guidance material).	14 November 1958 — —
34	Aeronautical Information Services Division and Aeronautical Charts Division (AIS/MAP Division) Meeting (April-May 1959)	Definitions; General Specifications; Aerodrome Obstruction Chart — ICAO Types A and B; Plotting Chart — ICAO; Radio Navigation Chart — ICAO; Terminal Area Chart — ICAO; Instrument Approach Chart — ICAO; WAC — ICAO 1:1 000 000; Aeronautical Chart — ICAO 1:500 000; Visual Approach Chart; Landing Chart — ICAO; Aerodrome Chart — ICAO; Aeronautical Navigation Chart 1:2 000 000; Sheet Layout for the WAC — ICAO 1:1 000 000; ICAO Chart Symbols; Colour Guide; Hypsometric Tint Guide; Format for WAC — ICAO 1:1 000 000; Criteria for determination of Minimum Sector Altitudes; Attachments.	20 June 1960 1 October 1960 1 July 1961
35	AIS/MAP Division Meeting (April-May 1959)	Aerodrome Obstruction Chart — ICAO Type A.	8 December 1961 1 April 1962 1 July 1962
36	AIS/MAP Division Meeting (April-May 1959); Informal EUM/MAP Meeting (May 1961)	Minimum Sector Altitudes; Sheet lines WAC — ICAO 1:1 000 000.	14 December 19621 April 19631 November 1963
37	Canada; Switzerland; United Nations Technical Conference on the International Map of the World	Chart Symbols.	11 December 1963 1 June 1964 1 November 1964
38	AGA Division — 7th Session; PANS-ICAO Abbreviations and Codes (Doc 8400)	Definitions; General Specifications; Sample Aerodrome Obstruction Chart — ICAO Types A and B.	25 March 1964 1 August 1964 1 November 1964
39	RAC/OPS Meeting (1963)	Definitions; Explanatory notes on the Application of the Definitions of Danger Area, Prohibited Area and Restricted Area.	10 December 1965 10 April 1966 25 August 1966

(ix) 1/11/01

Amendment	Source(s)	Subject(s)	Adopted Effective Applicable
40	AIS/MAP Divisional Meeting	Contours and portrayal of relief, hypsometric tints, chart symbols, WAC — ICAO 1:1 000 000, Aeronautical Chart — ICAO Small Scale; reference datum for heights of obstructions, definitions, Attachments.	13 June 1967 8 October 1967 8 February 1968
41	Fifth Air Navigation Conference; Obstacle Clearance Panel (First Meeting); All Weather Operations Panel (Third Meeting)	Definitions; Aerodrome Obstruction Chart — ICAO Type A; Landing Chart — ICAO; Aerodrome Chart — ICAO; ICAO Chart Symbols.	23 January 196923 May 196918 September 1969
42	Sixth Air Navigation Conference (1969)	Radio Navigation Chart — ICAO; Terminal Area Chart — ICAO.	15 May 1970 15 September 1970 4 February 1971
43	Fifth North Atlantic Regional Air Navigation Meeting (1970) Rec- ommendation 17/5 a)	Aerodrome Chart — ICAO.	29 November 1971 29 March 1972 7 December 1972
44	Third Meeting of the All Weather Operations Panel, Recommen- dation 8/1	Precision Approach Terrain Chart — ICAO.	27 November 1972 27 March 1973 16 August 1973
45	Air Navigation Commission decisions on RAN Meeting recommendations of worldwide applica- bility; Sixth EUM RAN Meeting (Rec 16/24); Ninth Air Navigation Conference	Definitions; Aerodrome Obstruction Chart — ICAO Types A and B; Radio Navigation Chart — ICAO; Terminal Area Chart — ICAO; Instrument Approach Chart — ICAO; World Aeronautical Chart — ICAO 1:1 000 000; Aeronautical Chart — ICAO 1:500 000; Visual Approach Chart; Landing Chart — ICAO; Aerodrome Chart — ICAO; Aeronautical Navigation Chart — ICAO Small Scale; Precision Approach Terrain Chart — ICAO; ICAO Chart Symbols.	9 December 1977 9 April 1978 10 August 1978
46	Study on charts to be used in the cockpit; Recommendation 4/2 of the seventh meeting of the Obstacle Clearance Panel and Recommendation 10/1 of the AGA Divisional Meeting (1981)	Definitions; General specifications; Instrument Approach Chart — ICAO.	27 February 1984 30 July 1984 22 November 1984
47	Study on charts to be used in the cockpit; Recommendation 3/1 of the seventh meeting of the Obstacle Clearance Panel and Recommendation 8/2 of the AGA Divisional Meeting (1981)	Definitions; General specifications; Aerodrome Obstacle Chart — ICAO Types A and B; Plotting Chart — ICAO; Enroute Chart — ICAO; Area Chart — ICAO; Instrument Approach Chart — ICAO; World Aeronautical Chart — ICAO 1:1 000 000; Aeronautical Chart — ICAO 1:500 000; Visual Approach Chart — ICAO; Aerodrome Chart — ICAO; Aeronautical Navigation Chart — ICAO Small Scale; Precision Approach Terrain Chart — ICAO; ICAO Chart Symbols; Colour Guide. Introduces Aerodrome Ground Movement Chart — ICAO; Aircraft Parking/Docking Chart — ICAO; Standard Departure Chart — Instrument (SID) — ICAO; Standard Arrival Chart — Instrument (STAR) — ICAO; Aerodrome Obstacle Chart — ICAO Type C.	18 March 1985 29 July 1985 21 November 1985

 $1/11/01 \tag{x}$

Amendment	Source(s)	Subject(s)	Adopted Effective Applicable
48	Amendment 18 to Annex 6; Amendment 33 to Annex 14; Visual Aids Panel (Eleventh Meeting); Recommen- dation 2/2 and Secretariat	Aerodrome Obstacle Chart — ICAO Types A, B and C; Precision Approach Terrain Chart — ICAO; Standard Departure Chart — Instrument (SID) — ICAO; Standard Arrival Chart — Instrument (STAR) — ICAO; Instrument Approach Chart — ICAO; Visual Approach Chart — ICAO; Aerodrome Chart — ICAO; Aerodrome Ground Movement Chart — ICAO; Aircraft Parking/Docking Chart — ICAO; World Aeronautical Chart — ICAO 1:1 000 000; Aeronautical Chart — ICAO 1:500 000; Aeronautical Navigation Chart — ICAO Small Scale; Plotting Chart — ICAO; ICAO Chart Symbols.	24 February 1989 31 July 1989 16 November 1989
49	Amendment 33 to Annex 11; Amendment 39 to Annex 14; Adoption of Annex 14, Vol. II; Amendments 5 and 6 to Doc 8168, PANS-OPS, Vols. I and II, respectively	Definitions; General specifications; Enroute Chart — ICAO; Area Chart — ICAO; Instrument Approach Chart — ICAO; Visual Approach Chart — ICAO; Aerodrome Chart — ICAO; World Aeronautical Chart — ICAO 1:1 000 000; Aeronautical Chart — ICAO 1:500 000; ICAO Chart Symbols.	28 February 1992 27 July 1992 12 November 1992
50	Adoption by Council of WGS-84 as the standard geodetic reference system for international aviation; WAFS planning and implementation; PANS-OPS implementation problems; revision of the Manual of All-Weather Operations; integration of helicopter traffic with conventional aeroplane traffic; proposal by RGCSP/8; and the Secretariat	Definitions; introduction of new provisions concerning the promulgation, as of 1 January 1998, of WGS-84 related geographical coordinates; deletion of the requirement for presentation of level acceleration altitude/height; introduction of RNP type; inclusion of the note on close-in obstacles on SID charts; and introduction of new chart symbol for active volcano.	1 March 1995 24 July 1995 9 November 1995; 1 January 1998
51	Tenth and Eleventh Meetings of the Obstacle Clearance Panel and Air Navigation Commission	Definitions; aeronautical data bases; vertical component of the World Geodetic System — 1984 (WGS-84); Human Factors; identification of RNAV procedures; provision of final approach gradient; steep glide path angle approaches; and chart symbols for flyover and fly-by waypoints.	20 March 1998 20 July 1998 5 November 1998
52	Recommendations of the Visual Aids Panel (VAP), the Obstacle Clearance Panel (OCP), the joint ICAO and Industry Controlled Flight Into Terrain (CFIT) Task Force, the Aeronautical Information Services/ Aeronautical Charts (AIS/MAP) Divisional Meeting (1998), and the Secretariat	Definitions; runway-holding position; air defence identification zone (ADIZ); portrayal of terrain and minimum flight altitudes; runway visual range (RVR) observation sites; airspace classifications, flight procedures and obstacle clearance criteria based on area navigation (RNAV) systems, and chart symbols for runway-holding position, ADIZ, electronic aeronautical charts, airspace classifications; nuclear power station and waypoint and, introduction of new provisions, as of 28 November 2002, concerning the Electronic Aeronautical Chart Display — ICAO.	7 March 2001 16 July 2001 1 November 2001; 28 November 2002

(xi) 1/11/01

INTERNATIONAL STANDARDS AND RECOMMENDED PRACTICES

CHAPTER 1. DEFINITIONS, APPLICABILITY AND AVAILABILITY

1.1 Definitions

When the following terms are used in the Standards and Recommended Practices for Aeronautical Charts, they have the following meanings:

- **Aerodrome.** A defined area on land or water (including any buildings, installations and equipment) intended to be used either wholly or in part for the arrival, departure and surface movement of aircraft.
- **Aerodrome elevation.** The elevation of the highest point of the landing area.
- **Aerodrome operating minima.** The limits of usability of an aerodrome for:
 - a) take-off, expressed in terms of runway visual range and/or visibility and, if necessary, cloud conditions;
 - b) landing in precision approach and landing operations, expressed in terms of visibility and/or runway visual range and decision altitude/height (DA/H) as appropriate to the category of the operation; and
 - c) landing in approach and landing operations with vertical guidance, expressed in terms of visibility and/or runway visual range and decision altitude/height (DA/H); and
 - d) landing in non-precision approach and landing operations, expressed in terms of visibility and/or runway visual range, minimum descent altitude/height (MDA/H) and, if necessary, cloud conditions.
- Aerodrome reference point. The designated geographical location of an aerodrome.
- **Aeronautical chart.** A representation of a portion of the earth, its culture and relief, specifically designated to meet the requirements of air navigation.
- Aircraft stand. A designated area on an apron intended to be used for parking an aircraft.
- Air defence identification zone. Special designated airspace of defined dimensions within which aircraft are required to

- comply with special identification and/or reporting procedures additional to those related to the provision of air traffic services (ATS).
- *Air taxiway.* A defined path on the surface established for the air taxiing of helicopters.
- Air traffic service. A generic term meaning variously, flight information service, alerting service, air traffic advisory service, air traffic control service (area control service, approach control service or aerodrome control service).
- **Air transit route.** A defined path on the surface established for the air transitting of helicopters.
- Airway. A control area or portion thereof established in the form of a corridor.
- Altitude. The vertical distance of a level, a point or an object considered as a point, measured from mean sea level (MSL).
- **Apron.** A defined area, on a land aerodrome, intended to accommodate aircraft for purposes of loading or unloading passengers, mail or cargo, fuelling, parking or maintenance.
- Area minimum altitude (AMA). The lowest altitude to be used under instrument meteorological conditions (IMC) which will provide a minimum vertical clearance of 300 m (1 000 ft) or in designated mountainous terrain 600 m (2 000 ft) above all obstacles located in the area specified, rounded up to the nearest (next higher) 30 m (100 ft).
- **Arrival routes.** Routes identified in an instrument approach procedure by which aircraft may proceed from the en-route phase of flight to an initial approach fix.
- ATS route. A specified route designed for channelling the flow of traffic as necessary for the provision of air traffic services.
- Note 1.— The term ATS route is used to mean variously, airway, advisory route, controlled or uncontrolled route, arrival or departure route, etc.
- Note 2.— An ATS route is defined by route specifications which include an ATS route designator, the track to or from

significant points (waypoints), distance between significant points, reporting requirements and, as determined by the appropriate ATS authority, the lowest safe altitude.

- Change-over point. The point at which an aircraft navigating on an ATS route segment defined by reference to very high frequency omnidirectional radio ranges is expected to transfer its primary navigational reference from the facility behind the aircraft to the next facility ahead of the aircraft.
- Note.— Change-over points are established to provide the optimum balance in respect of signal strength and quality between facilities at all levels to be used and to ensure a common source of azimuth guidance for all aircraft operating along the same portion of a route segment.
- Clearway. A defined rectangular area on the ground or water under the control of the appropriate authority, selected or prepared as a suitable area over which an aeroplane may make a portion of its initial climb to a specified height.
- Contour line. A line on a map or chart connecting points of equal elevation.
- *Culture.* All features constructed on the surface of the earth by man, such as cities, railways, canals, etc.
- Cyclic Redundancy Check (CRC). A mathematical algorithm applied to the digital expression of data that provides a level of assurance against loss or alteration of data.
- Danger area. An airspace of defined dimensions within which activities dangerous to the flight of aircraft may exist at specified times.
- **Data quality.** A degree or level of confidence that the data provided meet the requirements of the data user in terms of accuracy, resolution and integrity.
- **Displaced threshold.** A threshold not located at the extremity of a runway.
- *Electronic aeronautical chart display*. An electronic device by which flight crews are enabled to execute, in a convenient and timely manner, route planning, route monitoring and navigation by displaying required information.
- *Elevation.* The vertical distance of a point or a level, on or affixed to the surface of the earth, measured from mean sea level.
- *Ellipsoid height (Geodetic height)*. The height related to the reference ellipsoid, measured along the ellipsoidal outer normal through the point in question.
- *Final approach.* That part of an instrument approach procedure which commences at the specified final approach fix or point, or where such a fix or point is not specified,

- a) at the end of the last procedure turn, base turn or inbound turn of a racetrack procedure, if specified; or
- b) at the point of interception of the last track specified in the approach procedure; and
- ends at a point in the vicinity of an aerodrome from which:
- 1) a landing can be made; or
- 2) a missed approach procedure is initiated.
- Final approach and take-off area (FATO). A defined area over which the final phase of the approach manoeuvre to hover or landing is completed and from which the take-off manoeuvre is commenced. Where the FATO is to be used by performance Class 1 helicopters, the defined area includes the rejected take-off area available.
- Final approach fix or point. That fix or point of an instrument approach procedure where the final approach segment commences.
- Final approach segment. That segment of an instrument approach procedure in which alignment and descent for landing are accomplished.
- Flight information region. An airspace of defined dimensions within which flight information service and alerting service are provided.
- Flight level. A surface of constant atmospheric pressure which is related to a specific pressure datum, 1 013.2 hectopascals (hPa), and is separated from other such surfaces by specific pressure intervals.
- Note 1.— A pressure type altimeter calibrated in accordance with the Standard Atmosphere:
 - a) when set to a QNH altimeter setting, will indicate altitude:
 - b) when set to a QFE altimeter setting, will indicate height above the QFE reference datum;
 - c) when set to a pressure of 1 013.2 hPa, may be used to indicate flight levels.
- Note 2.— The terms "height" and "altitude", used in Note 1 above, indicate altimetric rather than geometric heights and altitudes.
- *Geodesic distance*. The shortest distance between any two points on a mathematically defined ellipsoidal surface.
- **Geodetic datum.** A minimum set of parameters required to define location and orientation of the local reference system with respect to the global reference system/frame.

1/11/01 1-2

Annex 4 — Aeronautical Charts

- *Geoid.* The equipotential surface in the gravity field of the Earth which coincides with the undisturbed mean sea level (MSL) extended continuously through the continents.
- Note.— The geoid is irregular in shape because of local gravitational disturbances (wind tides, salinity, current, etc.) and the direction of gravity is perpendicular to the geoid at every point.
- *Geoid undulation.* The distance of the geoid above (positive) or below (negative) the mathematical reference ellipsoid.
- Note.— In respect to the World Geodetic System 1984 (WGS-84) defined ellipsoid, the difference between the WGS-84 ellipsoidal height and orthometric height represents WGS-84 geoid undulation.
- *Glide path.* A descent profile determined for vertical guidance during a final approach.
- Height. The vertical distance of a level, a point or an object considered as a point, measured from a specified datum.
- **Helicopter stand.** An aircraft stand which provides for parking a helicopter and, where air taxiing operations are contemplated, the helicopter touchdown and lift-off.
- **Heliport.** An aerodrome or a defined area on a structure intended to be used wholly or in part for the arrival, departure and surface movement of helicopters.
- Holding procedure. A predetermined manoeuvre which keeps an aircraft within a specified airspace while awaiting further clearance.
- **Human Factors principles.** Principles which apply to aeronautical design, certification, training, operations and maintenance and which seek safe interface between the human and other system components by proper consideration to human performance.
- *Hypsometric tints.* A succession of shades or colour gradations used to depict ranges of elevation.
- *Initial approach segment.* That segment of an instrument approach procedure between the initial approach fix and the intermediate approach fix or, where applicable, the final approach fix or point.
- Instrument approach procedure. A series of predetermined manoeuvres by reference to flight instruments with specified protection from obstacles from the initial approach fix, or where applicable, from the beginning of a defined arrival route to a point from which a landing can be completed and thereafter, if a landing is not completed, to a position at which holding or en-route obstacle clearance criteria apply.

- Intermediate approach segment. That segment of an instrument approach procedure between either the intermediate approach fix and the final approach fix or point, or between the end of a reversal, racetrack or dead reckoning track procedure and the final approach fix or point, as appropriate.
- **Isogonal.** A line on a map or chart on which all points have the same magnetic variation for a specified epoch.
- Isogriv. A line on a map or chart which joins points of equal angular difference between the North of the navigation grid and Magnetic North.
- **Landing area.** That part of a movement area intended for the landing or take-off of aircraft.
- Landing direction indicator. A device to indicate visually the direction currently designated for landing and for take-off.
- Level. A generic term relating to the vertical position of an aircraft in flight and meaning variously, height, altitude or flight level.
- **Magnetic variation.** The angular difference between True North and Magnetic North.
- Note.— The value given indicates whether the angular difference is East or West of True North.
- **Manoeuvring area.** That part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, excluding aprons.
- Marking. A symbol or group of symbols displayed on the surface of the movement area in order to convey aeronautical information.
- Minimum sector altitude. The lowest altitude which may be used which will provide a minimum clearance of 300 m (1 000 ft) above all objects located in an area contained within a sector of a circle of 46 km (25 NM) radius centred on a radio aid to navigation.
- Missed approach point (MAPt). That point in an instrument approach procedure at or before which the prescribed missed approach procedure must be initiated in order to ensure that the minimum obstacle clearance is not infringed.
- *Missed approach procedure.* The procedure to be followed if the approach cannot be continued.
- **Movement area.** That part of an aerodrome to be used for the take-off, landing and taxiing of aircraft, consisting of the manoeuvring area and the apron(s).
- Obstacle clearance altitude (OCA) or obstacle clearance height (OCH). The lowest altitude or the lowest height above the elevation of the relevant runway threshold or the

1-3 1/11/01

aerodrome elevation as applicable, used in establishing compliance with appropriate obstacle clearance criteria.

- Note 1.— Obstacle clearance altitude is referenced to mean sea level and obstacle clearance height is referenced to the threshold elevation or in the case of non-precision approaches to the aerodrome elevation or the threshold elevation if that is more than 2 m (7 ft) below the aerodrome elevation. An obstacle clearance height for a circling approach is referenced to the aerodrome elevation.
- Note 2.— For convenience when both expressions are used they may be written in the form "obstacle clearance altitude/height" and abbreviated "OCA/H".
- Note 3.— See Procedures for Air Navigation Services Aircraft Operations (Doc 8168), Vol. I, Part III, 1.5 and Vol. II, Part III, 6.4 for specific applications of this definition.
- Obstacle free zone (OFZ). The airspace above the inner approach surface, inner transitional surfaces, and balked landing surface and that portion of the strip bounded by these surfaces, which is not penetrated by any fixed obstacle other than a low-mass and frangibly mounted one required for air navigation purposes.
- *Orthometric height.* Height of a point related to the geoid, generally presented as an MSL elevation.
- **Point light.** A luminous signal appearing without perceptible length.
- **Position** (geographical). Set of coordinates (latitude and longitude) referenced to the mathematical reference ellipsoid which define the position of a point on the surface of the Earth.
- **Precision approach procedure.** An instrument approach procedure utilizing azimuth and glide path information provided by ILS or PAR.
- **Procedure turn.** A manoeuvre in which a turn is made away from a designated track followed by a turn in the opposite direction to permit the aircraft to intercept and proceed along the reciprocal of the designated track.
- Note 1.— Procedure turns are designated "left" or "right" according to the direction of the initial turn.
- Note 2.— Procedure turns may be designated as being made either in level flight or while descending, according to the circumstances of each individual procedure.
- **Prohibited area.** An airspace of defined dimensions, above the land areas or territorial waters of a State, within which the flight of aircraft is prohibited.
- **Radar vectoring.** Provision of navigational guidance to aircraft in the form of specific headings, based on the use of radar.

- **Relief.** The inequalities in elevation of the surface of the earth represented on the aeronautical charts by contours, hypsometric tints, shading or spot elevations.
- **Reporting point.** A specified geographical location in relation to which the position of an aircraft can be reported.
- **Required navigation performance (RNP).** A statement of the navigation performance necessary for operation within a defined airspace.
- Note.— Navigation performance and requirements are defined for a particular RNP type and/or application.
- **Resolution.** A number of units or digits to which a measured or calculated value is expressed and used.
- **Restricted area.** An airspace of defined dimensions, above the land areas or territorial waters of a State, within which the flight of aircraft is restricted in accordance with certain specified conditions.
- **Reversal procedure.** A procedure designed to enable aircraft to reverse direction during the initial approach segment of an instrument approach procedure. The sequence may include procedure turns or base turns.
- **RNP** type. A containment value expressed as a distance in nautical miles from the intended position within which flights would be for at least 95 per cent of the total flying time.
 - Example.— RNP 4 represents a navigation accuracy of plus or minus 7.4 km (4 NM) on a 95 per cent containment basis.
- **Runway.** A defined rectangular area on a land aerodrome prepared for the landing and take-off of aircraft.
- **Runway-holding position.** A designated position intended to protect a runway, an obstacle limitation surface, or an ILS/MLS critical/sensitive area at which taxiing aircraft and vehicles shall stop and hold, unless otherwise authorized by the aerodrome control tower.
- **Runway** strip. A defined area including the runway and stopway, if provided, intended:
 - a) to reduce the risk of damage to aircraft running off a runway; and
 - b) to protect aircraft flying over it during take-off or landing operations.
- **Runway visual range (RVR).** The range over which the pilot of an aircraft on the centre line of a runway can see the runway surface markings or the lights delineating the runway or identifying its centre line.
- **Shoulder.** An area adjacent to the edge of a pavement so prepared as to provide a transition between the pavement and the adjacent surface.

1/11/01 1-4

- Significant obstacle. Any natural terrain feature or man-made fixed object, permanent or temporary, which has vertical significance in relation to adjacent and surrounding features and which is considered a potential hazard to the safe passage of aircraft in the type of operation for which the individual chart series is designed.
- Note.— The term "significant obstacle" is used in this Annex solely for the purpose of specifying the objects to be included on charts. Obstacles are specified in other terms in Annex 14, Volumes I and II, for the purpose of clearing and marking.
- *Significant point.* A specified geographical location used in defining an ATS route or the flight path of an aircraft and for other navigation and ATS purposes.
- **Stopway.** A defined rectangular area on the ground at the end of take-off run available prepared as a suitable area in which an aircraft can be stopped in the case of an abandoned take-off.
- **Taxiing.** Movement of an aircraft on the surface of an aerodrome under its own power, excluding take-off and landing.
- **Taxiway.** A defined path on a land aerodrome established for the taxiing of aircraft and intended to provide a link between one part of the aerodrome and another, including:
 - a) Aircraft stand taxilane. A portion of an apron designated as a taxiway and intended to provide access to aircraft stands only.
 - b) Apron taxiway. A portion of a taxiway system located on an apron and intended to provide a through taxi route across the apron.
 - c) Rapid exit taxiway. A taxiway connected to a runway at an acute angle and designed to allow landing aeroplanes to turn off at higher speeds than are achieved on other exit taxiways thereby minimizing runway occupancy times.
- **Threshold.** The beginning of that portion of the runway usable for landing.
- **Touchdown and lift-off area** (**TLOF**). A load bearing area on which a helicopter may touch down or lift off.
- **Touchdown zone.** The portion of a runway, beyond the threshold, where it is intended landing aeroplanes first contact the runway.
- *Track.* The projection on the earth's surface of the path of an aircraft, the direction of which path at any point is usually expressed in degrees from North (true, magnetic or grid).
- *Transition altitude.* The altitude at or below which the vertical position of an aircraft is controlled by reference to altitudes.

- Waypoint. A specified geographical location used to define an area navigation route or the flight path of an aircraft employing area navigation. Waypoints are identified as either:
 - Fly-by waypoint. A waypoint which requires turn anticipation to allow tangential interception of the next segment of a route or procedure, or
 - Flyover waypoint. A waypoint at which a turn is initiated in order to join the next segment of a route or procedure.

1.2 Applicability

- 1.2.1 The specifications in this Annex are applicable on and after 1 November 2001.
- Note.— Chapter 20 Electronic Aeronautical Chart Display ICAO is applicable on and after 28 November 2002.
- 1.2.2 All charts coming within the scope of this Annex and bearing the aeronautical information date of 1 November 2001 or later shall conform to the Standards relevant to the particular chart.
- 1.2.2.1 **Recommendation.** All such charts should in addition conform to the Recommended Practices relevant to the particular chart.

1.3 Availability

- 1.3.1 *Information*. A Contracting State shall on request by another Contracting State provide all information relating to its own territory that is necessary to enable the Standards of this Annex to be met.
- 1.3.2 *Charts*. Contracting States shall, when so specified, ensure the availability of charts in whichever of the following ways is appropriate for a particular chart or single sheet of a chart series.
- 1.3.2.1 For any chart or single sheet of a chart series entirely contained within the territory of a Contracting State, the State having jurisdiction over the territory shall either:
 - 1) produce the chart or sheet itself; or
 - 2) arrange for its production by another Contracting State or by an agency; or
 - provide another Contracting State prepared to accept an obligation to produce the chart or sheet with the data necessary for its production.

1-5 1/11/01

- 1.3.2.2 For any chart or single sheet of a chart series which includes the territory of two or more Contracting States, the States having jurisdiction over the territory so included shall determine the manner in which the chart or sheet will be made available. This determination shall be made with due regard being given to regional air navigation agreements and to any programme of allocation established by the Council of ICAO.
- Note.— The phrase "regional air navigation agreements" refers to the agreements approved by the Council of ICAO normally on the advice of regional air navigation meetings.
- 1.3.3 A Contracting State shall take all reasonable measures to ensure that the information it provides and the

aeronautical charts made available are adequate and accurate and that they are maintained up to date by an adequate revision service

1.3.4 **Recommendation.**— To improve worldwide dissemination of information on new charting techniques and production methods, appropriate charts produced by Contracting States should be made available without charge to other Contracting States on request on a reciprocal basis.

Note.— Guidance material on the preparation of aeronautical charts, including sample formats, is contained in the Aeronautical Chart Manual (Doc 8697).

1/11/01 1-6

CHAPTER 2. GENERAL SPECIFICATIONS

Note.— The Standards and Recommended Practices contained in this chapter are applicable to all ICAO aeronautical charts unless otherwise stated in the specifications of the chart concerned.

2.1 Operational requirements for charts

Note.— For the purposes of this Annex, the total flight is divided into the following phases:

Phase 1 — Taxi from aircraft stand to take-off point

Phase 2 — Take-off and climb to en-route ATS route structure

Phase 3 — En-route ATS route structure

Phase 4 — Descent to approach

Phase 5 — Approach to land and missed approach

Phase 6 — Landing and taxi to aircraft stand.

2.1.1 Each type of chart shall provide information relevant to the function of the chart and its design shall observe Human Factors principles which facilitate its optimum use.

Note.— Guidance material on the application of Human Factors principles can be found in the Human Factors Training Manual (Doc 9683).

- 2.1.2 Each type of chart shall provide information appropriate to the phase of flight, to ensure the safe and expeditious operation of the aircraft.
- 2.1.3 The presentation of information shall be accurate, free from distortion and clutter, unambiguous, and be readable under all normal operating conditions.
- 2.1.4 Colours or tints and type size used shall be such that the chart can be easily read and interpreted by the pilot in varying conditions of natural and artificial light.
- 2.1.5 The information shall be in a form which enables the pilot to acquire it in a reasonable time consistent with workload and operating conditions.
- 2.1.6 The presentation of information provided on each type of chart shall permit smooth transition from chart to chart as appropriate to the phase of flight.

- 2.1.7 **Recommendation.** The charts should be True North orientated.
- 2.1.8 **Recommendation.** The basic sheet size of the charts should be $210 \times 148 \text{ mm}$ (8.27 $\times 5.82 \text{ in}$) (A5).

2.2 Titles

The title of a chart or chart series prepared in accordance with the specifications contained in this Annex and intended to satisfy the function of the chart, shall be that of the relevant chapter heading as modified by application of any Standard contained therein, except that such title shall not include "ICAO" unless the chart conforms with all Standards specified in this Chapter 2 and any specified for the particular chart.

2.3 Miscellaneous information

- 2.3.1 The marginal note layout shall be as given in Appendix 1, except as otherwise specified for a particular chart.
- 2.3.2 The following information shall be shown on the face of each chart unless otherwise stated in the specification of the chart concerned:
 - 1) designation or title of the chart series;

Note.— The title may be abbreviated.

- 2) name and reference of the sheet;
- 3) on each margin an indication of the adjoining sheet (when applicable).
- 2.3.3 A legend to the symbols and abbreviations used shall be provided. The legend shall be on the face or reverse of each chart except that, where it is impracticable for reasons of space, a legend may be published separately.
- 2.3.4 The name and adequate address of the producing agency shall be shown in the margin of the chart except that, where the chart is published as part of an aeronautical document, this information may be placed in the front of that document.

2.4 Symbols

Symbols used shall conform to those shown in Appendix 2 — ICAO Chart Symbols, except that where it is desired to show

on an aeronautical chart special features or items of importance to civil aviation for which no ICAO symbol is at present provided, any appropriate symbol may be chosen for this purpose, provided that it does not cause confusion with any existing ICAO chart symbol or impair the legibility of the chart.

Note.— The size and prominence of symbols and the thickness and spacing of lines may be varied according to the scale and functions of the chart, with due regard to the importance of the information they convey.

2.5 Units of measurement

- 2.5.1 Distances shall be derived as geodesic distances.
- 2.5.2 Distances shall be expressed in either kilometres or nautical miles or both, provided the units are clearly differentiated.
- 2.5.3 Altitudes, elevations and heights shall be expressed in either metres or feet or both, provided the units are clearly differentiated.
- 2.5.4 Linear dimensions on aerodromes and short distances shall be expressed in metres.
- 2.5.5 The order of resolution of distances, dimensions, elevations and heights shall be that as specified for a particular chart
- 2.5.6 The units of measurement used to express distances, altitudes, elevations and heights shall be conspicuously stated on the face of each chart.
- 2.5.7 Conversion scales (kilometres/nautical miles, metres/feet) shall be provided on each chart on which distances, elevations or altitudes are shown. The conversion scales shall be placed on the face of each chart.

2.6 Scale and projection

- 2.6.1 For charts of large areas, the name and basic parameters and scale of the projection shall be indicated.
- 2.6.2 For charts of small areas, a linear scale only shall be indicated.

2.7 Date of validity of aeronautical information

The date of validity of aeronautical information shall be clearly indicated on the face of each chart.

2.8 Spelling of geographical names

- 2.8.1 The symbols of the Roman alphabet shall be used for all writing.
- 2.8.2 The names of places and of geographical features in countries which officially use varieties of the Roman alphabet shall be accepted in their official spelling, including the accents and diacritical marks used in the respective alphabets.
- 2.8.3 Where a geographical term such as "cape", "point", "gulf", "river", is abbreviated on any particular chart, that word shall be spelt out in full in the language used by the publishing agency, in respect of the most important example of each type. Punctuation marks shall not be used in abbreviations within the body of a chart.
- 2.8.4 **Recommendation.** In areas where romanized names have not been officially produced or adopted, and outside the territory of Contracting States, names should be transliterated from the non-Roman alphabet form by the system generally used by the producing agency.

2.9 Abbreviations

- 2.9.1 Abbreviations shall be used on aeronautical charts whenever they are appropriate.
- 2.9.2 **Recommendation.** Where applicable, abbreviations should be selected from the Procedures for Air Navigation Services ICAO Abbreviations and Codes (Doc 8400).

2.10 Political boundaries

- 2.10.1 International boundaries shall be shown, but may be interrupted if data more important to the use of the chart would be obscured.
- 2.10.2 Where the territory of more than one State appears on a chart, the names identifying the countries shall be indicated.

Note.— In the case of a dependent territory, the name of the sovereign State may be added in brackets.

2.11 Colours

Recommendation.— Colours used on charts should conform to Appendix 3 — Colour Guide.

1/11/01 2-2

2.12 Relief

- 2.12.1 Relief, where shown, shall be portrayed in a manner that will satisfy the chart users' need for:
 - a) orientation and identification;
 - b) safe terrain clearance;
 - c) clarity of aeronautical information when shown;
 - d) planning.
- Note.— Relief is usually portrayed by combinations of contours, hypsometric tints, spot elevations and hill shading, the choice of method being affected by the nature and scale of the chart and its intended use.
- 2.12.2 **Recommendation.** Where relief is shown by hypsometric tints, the tints used should be based on those shown in the Hypsometric Tint Guide in Appendix 4.
- 2.12.3 Where spot elevations are used they shall be shown for selected critical points.
- 2.12.3.1 The value of spot elevations of doubtful accuracy shall be followed by the sign \pm .

2.13 Prohibited, restricted and danger areas

When prohibited, restricted or danger areas are shown, the reference or other identification shall be included, except that the nationality letters may be omitted.

Note.— Nationality letters are those contained in Doc 7910 — Location Indicators.

2.14 Air traffic services airspaces

- 2.14.1 When ATS airspace is shown on a chart, the class of airspace, the type, name or call sign, the vertical limits and the radio frequency(ies) to be used shall be indicated and the horizontal limits depicted in accordance with Appendix 2 ICAO Chart Symbols.
- 2.14.2 **Recommendation.** On charts used for visual flight, those parts of the ATS Airspace Classifications table in Annex 11 applicable to the airspace depicted on the chart should be on the face or reverse of each chart.

2.15 Magnetic variation

2.15.1 True North and magnetic variation shall be indicated. The order of resolution of magnetic variation shall be that as specified for a particular chart.

2.15.2 **Recommendation.**— When magnetic variation is shown on a chart, the values shown should be those for the year nearest to the date of publication that is divisible by 5, i.e. 1980, 1985, etc. In exceptional cases where the current value would be more than one degree different, after applying the calculation for annual change, an interim date and value should be quoted.

Note.— The date and the annual change may be shown.

2.16 Typography

Note.— Samples of type suitable for use on aeronautical charts are included in the Aeronautical Chart Manual (Doc 8697).

2.17 Aeronautical data

2.17.1 Each Contracting State shall take all necessary measures to introduce a properly organized quality system containing procedures, processes and resources necessary to implement quality management at each function stage as outlined in Annex 15, 3.1.7. The execution of such quality management shall be made demonstrable for each function stage, when required. In addition, States shall ensure that established procedures exist in order that aeronautical data at any moment is traceable to its origin so to allow any data anomalies or errors, detected during the production/maintenance phases or in the operational use, to be corrected.

Note.— Specifications governing the quality system are given in Annex 15, Chapter 3.

- 2.17.2 States shall ensure that the order of chart resolution of aeronautical data shall be that as specified for a particular chart and as presented in a tabular form in Appendix 6.
- 2.17.3 Contracting States shall ensure that integrity of aeronautical data is maintained throughout the data process from survey/origin to the next intended user. Aeronautical data integrity requirements shall be based upon the potential risk resulting from the corruption of data and upon the use to which the data item is put. Consequently, the following classification and data integrity level shall apply:
 - a) critical data, integrity level 1×10^{-8} : there is a high probability when using corrupted critical data that the continued safe flight and landing of an aircraft would be severely at risk with the potential for catastrophe;
 - b) essential data, integrity level 1×10^{-5} : there is a low probability when using corrupted essential data that the continued safe flight and landing of an aircraft would be severely at risk with the potential for catastrophe; and

2-3 1/11/01

- c) routine data, integrity level 1×10^{-3} : there is a very low probability when using corrupted routine data that the continued safe flight and landing of an aircraft would be severely at risk with the potential for catastrophe.
- 2.17.4 Aeronautical data quality requirements related to the integrity and data classification shall be as provided in Tables 1 to 5 in Appendix 6.
- 2.17.5 Protection of electronic aeronautical data while stored or in transit shall be totally monitored by the Cyclic Redundancy Check (CRC). To achieve protection of the integrity level of critical and essential aeronautical data as classified in 2.17.3 above, a 32- or 24-bit CRC algorithm shall apply respectively.
- 2.17.6 **Recommendation.** To achieve protection of the integrity level of routine aeronautical data as classified in 2.17.3 above, a 16-bit CRC algorithm should apply.

Note.— Guidance material on the aeronautical data quality requirements (accuracy, resolution, integrity, protection and traceability) is contained in the World Geodetic System — 1984 (WGS-84) Manual (Doc 9674). Supporting material in respect of the provisions of Appendix 6 related to chart resolution and integrity of aeronautical data is contained in RTCA Document DO-201A and European Organization for Civil Aviation Equipment (EUROCAE) Document ED-77 — Industry Requirements for Aeronautical Information.

2.18 World Geodetic System — 1984 (WGS-84)

- 2.18.1 Published geographical coordinates indicating latitude and longitude shall be expressed in terms of the World Geodetic System 1984 (WGS-84) geodetic reference datum.
- 2.18.2 In addition to the elevation (referenced to mean sea level) for the specific surveyed ground positions, geoid undulation (referenced to the WGS-84 ellipsoid) for those positions shall also be published as specified for a particular chart
- 2.18.3 Geographical coordinates which have been transformed into WGS-84 coordinates but whose accuracy of original field work does not meet the requirements in Annex 11, Chapter 2 and Annex 14, Volumes I and II, Chapter 2, shall be identified by an asterisk.
- 2.18.4 The order of resolution of geographical coordinates and geoid undulations shall be that as specified for a particular chart.

Note.— Specifications governing the determination and reporting of WGS-84 coordinates are given in Annex 11, Chapter 2, and Annex 14, Volumes I and II, Chapter 2.

1/11/01 2-4

CHAPTER 3. AERODROME OBSTACLE CHART — ICAO TYPE A (OPERATING LIMITATIONS)

3.1 Function

This chart, in combination with the Aerodrome Obstacle Chart — ICAO Type C or with the relevant information published in the AIP, shall provide the data necessary to enable an operator to comply with the operating limitations of Annex 6, Parts I and II, Chapter 5, and Part III, Chapter 3.

3.2 Availability

- 3.2.1 Aerodrome Obstacle Charts ICAO Type A (Operating Limitations) shall be made available in the manner prescribed in 1.3.2 for all aerodromes regularly used by international civil aviation, except for those aerodromes where there are no significant obstacles in the take-off flight path areas.
- 3.2.2 Where a chart is not required because no significant obstacles exist in the take-off flight path area, a notification to this effect shall be published.

3.3 Units of measurement

- 3.3.1 Elevations shall be shown to the nearest half-metre or to the nearest foot.
- 3.3.2 Linear dimensions shall be shown to the nearest half-metre.

3.4 Coverage and scale

- 3.4.1 The extent of each plan shall be sufficient to cover all significant obstacles.
- Note.— Isolated distant significant obstacles that would unnecessarily increase the sheet size may be indicated by the appropriate symbol and an arrow, provided that the distance and bearing from the end of the runway farthest removed and the elevation are given.
- 3.4.2 The horizontal scale shall be within the range of 1:10 000 to 1:15 000.
- 3.4.3 **Recommendation.** The horizontal scale should be 1:10 000.

- Note.— When the production of the charts would be expedited thereby, a scale of 1:20 000 may be used.
- 3.4.4 The vertical scale shall be ten times the horizontal scale.
- 3.4.5 *Linear scales*. Horizontal and vertical linear scales showing both metres and feet shall be included in the charts.

3.5 Format

- 3.5.1 The charts shall depict a plan and profile of each runway, any associated stopway or clearway, the take-off flight path area, and significant obstacles.
- 3.5.2 The profile for each runway, stopway, clearway and the obstacles in the take-off flight path area shall be shown above its corresponding plan. The profile of an alternative take-off flight path area shall comprise a linear projection of the full take-off flight path and shall be disposed above its corresponding plan in the manner most suited to the ready interpretation of the information.
- 3.5.3 A profile grid shall be ruled over the entire profile area exclusive of the runway. The zero for vertical coordinates shall be mean sea level. The zero for horizontal coordinates shall be the end of the runway furthest from the take-off flight path area concerned. Graduation marks indicating the subdivisions of intervals shall be shown along the base of the grid and along the vertical margins.
- 3.5.3.1 **Recommendation.** The vertical grid should have intervals of 30 m (100 ft) and the horizontal grid should have intervals of 300 m (1 000 ft).
 - 3.5.4 The chart shall include:
 - a) a box for recording the operational data specified in 3.8.3;
 - b) a box for recording amendments and dates thereof.

3.6 Identification

The chart shall be identified by the name of the country in which the aerodrome is located, the name of the city or town, or area, which the aerodrome serves, the name of the aerodrome and the designator(s) of the runway(s).

3.7 Magnetic variation

The magnetic variation to the nearest degree and date of information shall be indicated.

3.8 Aeronautical data

3.8.1 Obstacles

- 3.8.1.1 Obstacles in the take-off flight path area which project above a plane surface having a 1.2 per cent slope and having a common origin with the take-off flight path area, shall be regarded as significant obstacles, except that significant obstacles lying wholly below the shadow of other significant obstacles as defined in 3.8.1.2 need not be shown. Mobile obstacles such as boats, trains, trucks, etc., which may project above the 1.2 per cent plane shall be considered significant obstacles but shall not be considered as being capable of creating a shadow.
- 3.8.1.2 The shadow of an obstacle is considered to be a plane surface originating at a horizontal line passing through the top of the obstacle at right angles to the centre line of the take-off flight path area. The plane covers the complete width of the take-off flight path area and extends to the plane defined at 3.8.1.1 or to the next higher significant obstacle if it occurs first. For the first 300 m (1 000 ft) of the take-off flight path area, the shadow planes are horizontal and beyond this point such planes have an upward slope of 1.2 per cent.
- 3.8.1.3 If the significant obstacle creating a shadow is likely to be removed, objects that would become significant obstacles by its removal shall be shown.

3.8.2 Take-off flight path area

- 3.8.2.1 The take-off flight path area consists of a quadrilateral area on the surface of the earth lying directly below, and symmetrically disposed about, the take-off flight path. This area has the following characteristics:
 - a) it commences at the end of the area declared suitable for take-off (i.e. at the end of the runway or clearway as appropriate);
 - b) its width at the point of origin is 180 m (600 ft) and this width increases at the rate of 0.25D to a maximum of 1 800 m (6 000 ft), where D is the distance from the point of origin;
 - c) it extends to the point beyond which no significant obstacles exist or to a distance of 10.0 km (5.4 NM), whichever is the lesser.
- 3.8.2.2 For runways serving aircraft having operating limitations which do not preclude the use of a take-off flight

path gradient of less than 1.2 per cent, the extent of the take-off flight path area specified in 3.8.2.1 c) shall be increased to not less than 12.0 km (6.5 NM) and the slope of the plane surface specified in 3.8.1.1 and 3.8.1.2 shall be reduced to 1.0 per cent or less.

Note.— When a 1.0 per cent survey plane touches no obstacles, this plane may be lowered until it touches the first obstacle

3.8.3 Declared distances

- 3.8.3.1 The following information for each direction of each runway shall be entered in the space provided:
 - a) take-off run available;
 - b) accelerate-stop distance available;
 - c) take-off distance available;
 - d) landing distance available.

Note.— In Annex 14, Volume I, Attachment A, Section 3, guidance is given on declared distances.

3.8.3.2 **Recommendation.**— Where a declared distance is not provided because a runway is usable in one direction only, that runway should be identified as "not usable for takeoff, landing, or both".

3.8.4 Plan and profile views

3.8.4.1 The plan view shall show:

- a) the outline of the runways by a solid line, including the length and width, the magnetic bearing to the nearest degree, and the runway number;
- b) the outline of the clearways by a broken line, including the length and identification as such;
- take-off flight path areas by a dashed line and the centre line by a fine line consisting of short and long dashes;
- d) alternative take-off flight path areas. When alternative take-off flight path areas not centred on the extension of the runway centre line are shown, notes shall be provided explaining the significance of such areas;
- e) obstacles, including:
 - the exact location of each significant obstacle together with a symbol indicative of its type;
 - the elevation and identification of each significant obstacle;

1/11/01 3-2

 the limits of penetration of significant obstacles of large extent in a distinctive manner identified in the legend.

Note.— This does not exclude the necessity for indicating critical spot elevations within the take-off flight path area.

- 3.8.4.1.1 **Recommendation.** The nature of the runway and stopway surfaces should be indicated.
- 3.8.4.1.2 **Recommendation.** Stopways should be identified as such and should be shown by a broken line.
- 3.8.4.1.3 When stopways are shown, the length of each stopway shall be indicated.
 - 3.8.4.2 The profile view shall show:
 - a) the profile of the centre line of the runway by a solid line and the profile of the centre line of any associated stopways and clearways by a broken line;
 - b) the elevation of the runway centre line at each end of the runway, at the stopway and at the origin of each takeoff flight path area, and at each significant change in slope of runway and stopway;
 - c) obstacles, including:
 - each significant obstacle by a solid vertical line extending from a convenient grid line over at least one other grid line to the elevation of the top of the obstacle;
 - 2) identification of each significant obstacle;

 the limits of penetration of significant obstacles of large extent in a distinctive manner identified in the legend.

Note.— An obstacle profile consisting of a line joining the tops of each significant obstacle and representing the shadow created by successive significant obstacles may be shown.

3.9 Accuracy

- 3.9.1 The order of accuracy attained shall be shown on the chart.
- 3.9.2 **Recommendation.** The horizontal dimensions and the elevations of the runway, stopway and clearway to be printed on the chart should be determined to the nearest 0.5 m (1 ft).
- 3.9.3 **Recommendation.** The order of accuracy of the field work and the precision of chart production should be such that measurements in the take-off flight path areas can be taken from the chart within the following maximum deviations:
 - 1) horizontal distances: 5 m (15 ft) at a point of origin increasing at a rate of 1 per 500;
 - 2) vertical distances: 0.5 m (1.5 ft) in the first 300 m (1 000 ft) and increasing at a rate of 1 per 1 000.
- 3.9.4 *Datum.* Where no accurate datum for vertical reference is available, the elevation of the datum used shall be stated and shall be identified as assumed.

3-3 1/11/01

CHAPTER 4. AERODROME OBSTACLE CHART — ICAO TYPE B

4.1 Function

This chart shall provide information to satisfy the following functions:

- a) the determination of minimum safe altitudes/heights including those for circling procedures;
- b) the determination of procedures for use in the event of an emergency during take-off or landing;
- c) the application of obstacle clearing and marking criteria;
- d) the provision of source material for aeronautical charts.

4.2 Availability

- 4.2.1 **Recommendation.** Aerodrome Obstacle Charts ICAO Type B should be made available, in the manner prescribed in 1.3.2, for all aerodromes regularly used by international civil aviation.
- 4.2.2 When a chart combining the specifications of Chapters 3 and 4 is made available, it shall be called the Aerodrome Obstacle Chart ICAO (Comprehensive).

4.3 Units of measurement

- 4.3.1 Elevations shall be shown to the nearest half-metre or to the nearest foot.
- 4.3.2 Linear dimensions shall be shown to the nearest half-metre.

4.4 Coverage and scale

4.4.1 The extent of each plan shall be sufficient to cover all significant obstacles.

Note.— Isolated distant obstacles that would unnecessarily increase the sheet size may be indicated by the appropriate symbol and an arrow, provided that the distance and bearing from the aerodrome reference point and elevation are given.

- 4.4.2 The horizontal scale shall be within the range of 1:10 000 to 1:20 000.
- 4.4.3 A horizontal linear scale showing both metres and feet shall be included in the chart. When necessary, a linear scale for kilometres and a linear scale for nautical miles shall also be shown.

4.5 Format

The charts shall include:

- a) any necessary explanation of the projection used;
- b) any necessary identification of the grid used;
- c) a notation indicating that obstacles are those which penetrate the surfaces specified in Annex 14, Volume I, Chapter 4;
- d) a box for recording amendments and dates thereof;
- e) outside the neat line, every minute of latitude and longitude marked in degrees and minutes.

Note.— Lines of latitude and longitude may be shown across the face of the chart.

4.6 Identification

The chart shall be identified by the name of the country in which the aerodrome is located, the name of the city or town, or area, which the aerodrome serves and the name of the aerodrome.

4.7 Culture and topography

- 4.7.1 Drainage and hydrographic details shall be kept to a minimum.
- 4.7.2 Buildings and other salient features associated with the aerodrome shall be shown. Wherever possible, they shall be shown to scale.

- 4.7.3 All objects, either cultural or natural, that project above the take-off and approach surfaces specified in 4.9 or the clearing and marking surfaces specified in Annex 14, Volume I, Chapter 4 shall be shown.
- 4.7.4 Roads and railroads within the take-off and approach area, and less than 600 m (2 000 ft) from the end of the runway or runway extensions, shall be shown.

Note.— Geographical names of features may be shown if of significance.

4.8 Magnetic variation

The chart shall show a compass rose orientated to the True North, or a North point, showing the magnetic variation to the nearest degree with the date of magnetic information and annual change.

4.9 Aeronautical data

- 4.9.1 The charts shall show:
- the aerodrome reference point and its geographical coordinates in degrees, minutes and seconds;
- b) the outline of the runways by a solid line;
- c) the length and width of the runway;
- d) the magnetic bearing to the nearest degree of the runway and the runway number;
- e) the elevation of the runway centre line at each end of the runway, at the stopway, at the origin of each takeoff and approach area, and at each significant change of slope of runway and stopway;
- f) taxiways, aprons and parking areas identified as such, and the outlines by a solid line;
- g) stopways identified as such and depicted by a broken line:
- h) the length of each stopway;
- i) clearways identified as such and depicted by a broken line;
- j) the length of each clearway;

- k) take-off and approach surfaces identified as such and depicted by a broken line;
- l) take-off and approach areas;

Note.— The take-off area is described in 3.8.2.1. The approach area consists of an area on the surface of the earth lying directly below the approach surface as specified in Annex 14, Volume I, Chapter 4.

- m) significant obstacles at their exact location, including:
 - 1) a symbol indicative of their type;
 - 2) elevation;
 - 3) identification;
 - 4) limits of penetration of large extent in a distinctive manner identified in the legend;

Note.— This does not exclude the necessity for indicating critical spot elevations within the take-off and approach areas.

 any additional obstacles, as determined by 3.8.1.1 including the obstacles in the shadow of a significant obstacle, which would otherwise be exempted.

Note.— The specifications in Annex 14, Volume I, Chapter 4, are minimum requirements. Where the competent authority has established lower surfaces, they may be used in the determination of significant obstacles.

- 4.9.1.1 **Recommendation.** The nature of the runway and stopway surfaces should be given.
- 4.9.1.2 **Recommendation.** Wherever practicable the highest object or obstacle between adjacent approach areas within a radius of 5 000 m (15 000 ft) from the aerodrome reference point should be indicated in a prominent manner.
- 4.9.1.3 **Recommendation.** The extent of tree areas and relief features, part of which constitute significant obstacles, should be shown.

4.10 Accuracy

- 4.10.1 The order of accuracy attained shall be shown on the chart.
- 4.10.2 **Recommendation.** The horizontal dimensions and the elevations of the movement area, stopways and clearways to be printed on the chart should be determined to the nearest 0.5 m (1 ft).

1/11/01 4-2

Chapter 4 Aeronautical Charts

4.10.3 **Recommendation.**— The order or accuracy of the field work and the precision of chart production should be such that the resulting data will be within the maximum deviations indicated herein:

- a) Take-off and approach areas:
 - 1) horizontal distances: 5 m (15 ft) at point of origin increasing at a rate of 1 per 500;
 - 2) vertical distances: 0.5 m (1.5 ft) in the first 300 m (1000 ft) and increasing at a rate of 1 per 1000.

- b) Other areas:
 - 1) horizontal distances: 5 m (15 ft) within 5 000 m (15 000 ft) of the aerodrome reference point and 12 m (40 ft) beyond that area;
 - 2) vertical distances: 1 m (3 ft) within 1 500 m (5 000 ft) of the aerodrome reference point increasing at a rate of 1 per 1 000.
- 4.10.4 *Datum.* Where no accurate datum for vertical reference is available, the elevation of the datum used shall be stated and identified as assumed.

4-3 1/11/01

CHAPTER 5. AERODROME OBSTACLE CHART — ICAO TYPE C

5.1 Function

When produced, this chart shall provide the obstacle data necessary to enable an operator to develop procedures to comply with the operating limitations of Annex 6, Parts I and II, Chapter 5, and Part III, Chapter 3, with particular reference to information on obstacles that limit the maximum permissible take-off mass, and also to:

- a) determine minimum safe heights including those for circling procedures;
- b) determine procedures for use in the event of an emergency during take-off or landing;
- c) provide source material for aeronautical charts and aeronautical data bases.

Note.— An explanation of the intended purpose and use of this chart is given in the Aeronautical Chart Manual (Doc 8697).

5.2 Availability

This chart is not required where:

- a) the obstacle data specified in 5.1 are published in the AIP; or
- b) no significant obstacles exist and notification of this is published in the AIP.

5.3 Coverage and scale

- 5.3.1 The extent of each chart shall be sufficient:
- a) to cover all significant obstacles, including obstacles in the shadow of a significant obstacle, in the take-off flight path area which project above a plane surface having a 1.2 per cent slope and having a common origin with the take-off flight path area. Account shall be taken of mobile obstacles such as boats, trains, trucks, etc., which may project above the 1.2 per cent plane;
- b) to cover all obstacles exceeding 120 m (400 ft) above the lowest elevation on the runway(s) which may influence the maximum permissible take-off mass or the choice of the aircraft's flight profile both straight ahead and in all areas where turning departures may occur;

- c) to provide topographical information covering a distance of approximately 45 km (24 NM) from the aerodrome reference point.
- 5.3.2 The horizontal scale shall be within the range of 1:20 000 to 1:100 000.

Note.— A scale of 1:50 000 is preferred.

5.4 Format

The chart shall include:

- a) any necessary explanation of the projection used;
- b) any necessary identification of the grid used;
- c) a box for recording amendments and dates thereof;
- d) a box for recording the declared distances specified in 5.8.2:
- e) graduation marks at consistent intervals outside the neat line, at least every 10 minutes of latitude and longitude and marked in degrees and minutes.
- Note 1.— Lines of latitude and longitude may be shown across the face of the chart.

Note 2.— Aerodrome Obstacle Chart — ICAO Type C may consist of any suitable topographical chart or series of charts available, overprinted with the necessary aeronautical data in a distinctive colour.

5.5 Identification

The chart shall be identified by the name of the country in which the aerodrome is located, the name of the city or town which the aerodrome serves, and the name of the aerodrome.

5.6 Magnetic variation

Recommendation.— The chart should show the magnetic variation to the nearest degree with the date and annual change.

5.7 Units of measurement

- 5.7.1 Elevations shall be shown to the nearest metre or foot.
- 5.7.2 Linear dimensions shall be shown to the nearest metre.

5.8 Aeronautical data

- 5.8.1 The chart shall show:
- a) the aerodrome reference point and its geographical coordinates in degrees, minutes and seconds;
- b) the runways and the extended runway centre lines;
- c) significant obstacles as specified in 5.3.1 a) and b); the extent of each plan shall be sufficient to cover all significant obstacles except that isolated distant obstacles that would unnecessarily increase the sheet size may be indicated by an arrow, provided that the distance and bearing from a reference point and their elevation and geographical coordinates in degrees, minutes, seconds and tenths of seconds are given;
- d) the exact position of each significant obstacle by a symbol and its geographical coordinates in degrees, minutes, seconds and tenths of seconds;
- e) the elevation of each significant obstacle;
- f) an indication of the type of each significant obstacle;

Note.— The obstacle type may be given in textual form or in areas where excessive clutter would ensue, the obstacle may be identified by a number on the chart

- and the number and type tabulated in the margin or on a separate sheet.
- g) the limits of penetration of significant obstacles of large extent in a distinctive manner identified in the legend;

Note.— This does not exclude the necessity for indicating the positions of critical spot elevations and their geographical coordinates in degrees, minutes, seconds and tenths of seconds within such an area.

h) the positions of all radio navigation aids.

5.8.2 Declared distances

- 5.8.2.1 The following information for each direction of each runway shall be entered in the space provided:
 - a) take-off run available;
 - b) accelerate-stop distance available;
 - c) take-off distance available;
 - d) landing distance available.

Note.— In Annex 14, Volume I, Attachment A, guidance is given on declared distances.

5.8.2.2 **Recommendation.**— Where a declared distance is not provided because a runway direction cannot be used for take-off or landing or both, then this should be indicated and the words "not usable" or the abbreviation "NU" entered.

5.9 Accuracy

The order of accuracy attained shall be shown on the chart.

1/11/01 5-2

CHAPTER 6. PRECISION APPROACH TERRAIN CHART — ICAO

6.1 Function

The chart shall provide detailed terrain profile information within a defined portion of the final approach so as to enable aircraft operating agencies to assess the effect of the terrain on decision height determination by the use of radio altimeters.

6.2 Availability

- 6.2.1 The Precision Approach Terrain Chart ICAO shall be made available for all precision approach runways Categories II and III at aerodromes used by international civil aviation.
- 6.2.2 The Precision Approach Terrain Chart ICAO shall be revised whenever any significant change occurs.

6.3 Scale

- 6.3.1 **Recommendation.** The horizontal scale should be 1:2 500, and the vertical scale 1:500.
- 6.3.2 **Recommendation.** When the chart includes a profile of the terrain to a distance greater than 900 m (3 000 ft) from the runway threshold, the horizontal scale should be 1:5 000.

6.4 Identification

The chart shall be identified by the name of the country in which the aerodrome is located, the name of the city or town,

or area, which the aerodrome serves, the name of the aerodrome and the designator of the runway.

6.5 Plan and profile information

- 6.5.1 The chart shall include:
- a plan showing contours at 1 m (3 ft) intervals in the area 60 m (200 ft) on either side of the extended centre line of the runway, to the same distance as the profile, the contours to be related to the runway threshold;
- an indication where the terrain or any object thereon, within the plan defined in 1) above, differs by ±3 m (10 ft) in height from the centre line profile and is likely to affect a radio altimeter;
- a profile of the terrain to a distance of 900 m (3 000 ft) from the threshold along the extended centre line of the runway.
- 6.5.2 **Recommendation.** Where the terrain at a distance greater than 900 m (3 000 ft) from the runway threshold is mountainous or otherwise significant to users of the chart, the profile of the terrain should be shown to a distance not exceeding 2 000 m (6 500 ft) from the runway threshold.
- 6.5.3 **Recommendation.** The ILS reference datum height should be shown to the nearest half metre or foot.

CHAPTER 7. ENROUTE CHART — ICAO

7.1 Function

This chart shall provide flight crews with information to facilitate navigation along ATS routes in compliance with air traffic services procedures.

Note.— Simplified versions of these charts are appropriate for inclusion in Aeronautical Information Publications to complement the tabulation of radio communication and navigation facilities.

7.2 Availability

- 7.2.1 The Enroute Chart ICAO shall be made available in the manner prescribed in 1.3.2 for all areas where flight information regions have been established.
- Note.— Under certain conditions, an Area Chart ICAO may have to be provided. (See Chapter 8.)
- 7.2.2 Where different air traffic services routes, position reporting requirements or lateral limits of flight information regions or control areas exist in different layers of airspace and cannot be shown with sufficient clarity on one chart, separate charts shall be provided.

7.3 Coverage and scale

- Note 1.— A uniform scale for charts of this type cannot be specified due to the varying degree of congestion of information in certain areas.
- Note 2.— A linear scale based on the mean scale of the chart may be shown.
- 7.3.1 **Recommendation.** Layout of sheet lines should be determined by the density and pattern of the ATS route structure.
- 7.3.2 Large variations of scale between adjacent charts showing a continuous route structure shall be avoided.
- 7.3.3 An adequate overlap of charts shall be provided to ensure continuity of navigation.

7.4 Projection

7.4.1 **Recommendation.**— A conformal projection on which a straight line approximates a great circle should be used.

- 7.4.2 Parallels and meridians shall be shown at suitable intervals.
- 7.4.3 Graduation marks shall be placed at consistent intervals along selected parallels and meridians.

7.5 Identification

Each sheet shall be identified by chart series and number.

7.6 Culture and topography

- 7.6.1 Generalized shore lines of all open water areas, large lakes and rivers shall be shown except where they conflict with data more applicable to the function of the chart.
- 7.6.2 Within each quadrilateral formed by the parallels and meridians the area minimum altitude shall be shown, except as provided for in 7.6.3.
- 7.6.3 **Recommendation.** In areas of high latitude where it is determined by the appropriate authority that True North orientation of the chart is impractical, the area minimum altitude should be shown within each quadrilateral formed by reference lines of the graticule (grid) used.
- 7.6.4 Where charts are not True North orientated, this fact and the selected orientation used shall be clearly indicated.

7.7 Magnetic variation

Recommendation.— Isogonals should be indicated and the date of the isogonic information given.

7.8 Bearings, tracks and radials

- 7.8.1 Bearings, tracks and radials shall be magnetic, except as provided for in 7.8.2.
- 7.8.2 **Recommendation.** In areas of high latitude where it is determined by the appropriate authority that reference to Magnetic North is impractical, another suitable reference, i.e. True North or Grid North, should be used.

7.8.3 Where bearings, tracks or radials are given with reference to True North or Grid North, this shall be clearly indicated. When Grid North is used its reference grid meridian shall be identified.

7.9 Aeronautical data

7.9.1 Aerodromes

All aerodromes used by international civil aviation to which an instrument approach can be made shall be shown.

Note.— Other aerodromes may be shown.

7.9.2 Prohibited, restricted and danger areas

Prohibited, restricted and danger areas relevant to the layer of airspace, shall be depicted with their identification and vertical limits.

7.9.3 Air traffic services system

7.9.3.1 Where appropriate, the components of the established air traffic services system shall be shown.

7.9.3.1.1 The components shall include the following:

- the radio navigation aids associated with the air traffic services system together with their names, identifications, frequencies and geographical coordinates in degrees, minutes and seconds;
- in respect of DME, additionally the elevation of the transmitting antenna of the DME to the nearest 30 m (100 ft);
- an indication of all designated airspace, including lateral and vertical limits and the appropriate class of airspace;
- 4) all ATS routes for en-route flight including route designators, required navigation performance (RNP) types, the track to the nearest degree in both directions along each segment of the routes and, where applicable, the direction of traffic flow;
- all significant points which define the ATS routes and are not marked by the position of a radio navigation aid, together with their name-codes and geographical coordinates in degrees, minutes and seconds;
- 6) in respect of waypoints defining VOR/DME area navigation routes, additionally,
 - a) the station identification and radio frequency of the reference VOR/DME;

- b) the bearing to the nearest tenth of a degree and the distance to the nearest two-tenths of a kilometre (tenth of a nautical mile) from the reference VOR/ DME, if the waypoint is not collocated with it;
- an indication of all compulsory and "on-request" reporting points and ATS/MET reporting points;
- the distances to the nearest kilometre or nautical mile between significant points constituting turning points or reporting points;
 - Note.— Overall distances between radio navigation aids may also be shown.
- change-over points on route segments defined by reference to very high frequency omnidirectional radio ranges, indicating the distances to the nearest kilometre or nautical mile to the navigation aids;
 - Note.— Change-over points established at the midpoint between two aids, or at the intersection of two radials in the case of a route which changes direction between the aids, need not be shown for each route segment if a general statement regarding their existence is made.
- 10) minimum flight altitudes on ATS routes to the nearest higher 50 metres or 100 feet (see Annex 11, 2.21);
- radio communication facilities listed with their frequencies;
- 12) air defence identification zone (ADIZ) properly identified.

Note.— ADIZ procedures may be described in the chart legend.

7.9.4 Supplementary information

- 7.9.4.1 Details of departure and arrival routes and associated holding patterns in terminal areas shall be shown unless they are shown on an Area Chart, a Standard Departure Chart Instrument (SID) ICAO or a Standard Arrival Chart Instrument (STAR) ICAO.
- Note 1.— For specifications of these charts see Chapters 8, 9 and 10.
- Note 2.— Departure routes normally originate at the end of a runway; arrival routes normally terminate at the point where an instrument approach is initiated.
- 7.9.4.2 Where established, altimeter setting regions shall be shown and identified.

1/11/01 7-2

CHAPTER 8. AREA CHART — ICAO

8.1 Function

This chart shall provide the flight crew with information to facilitate the following phases of instrument flight:

- a) the transition between the en-route phase and approach to an aerodrome;
- b) the transition between take-off/missed approach and enroute phase of flight; and
- c) flights through areas of complex ATS routes or airspace structure.

Note.— The function described in 8.1 c) may be satisfied by a separate chart or an inset on an Enroute Chart — ICAO.

8.2 Availability

- 8.2.1 The Area Chart ICAO shall be made available in the manner prescribed in 1.3.2 where the air traffic services routes or position reporting requirements are complex and cannot be adequately shown on an Enroute Chart ICAO.
- 8.2.2 Where air traffic services routes or position reporting requirements are different for arrivals and for departures, and these cannot be shown with sufficient clarity on one chart, separate charts shall be provided.

Note.— Under certain conditions a Standard Departure Chart — Instrument (SID) — ICAO and a Standard Arrival Chart — Instrument (STAR) — ICAO may have to be provided (see Chapters 9 and 10).

8.3 Coverage and scale

- 8.3.1 The coverage of each chart shall extend to points that effectively show departure and arrival routes.
- 8.3.2 The chart shall be drawn to scale and a scale-bar shown.

8.4 Projection

- 8.4.1 **Recommendation.** A conformal projection on which a straight line approximates a great circle should be used.
- 8.4.2 Parallels and meridians shall be shown at suitable intervals.

8.4.3 Graduation marks shall be placed at consistent intervals along the neat lines.

8.5 Identification

Each sheet shall be identified by a name associated with the airspace portrayed.

Note.— The name may be that of the air traffic services centre, the name of the largest city or town situated in the area covered by the chart or the name of the city which the aerodrome serves. Where more than one aerodrome serves the city or town, the name of the aerodrome on which the procedures are based should be added.

8.6 Culture and topography

- 8.6.1 Generalized shore lines of all open water areas, large lakes and rivers shall be shown except where they conflict with data more applicable to the function of the chart.
- 8.6.2 **Recommendation.** To improve situational awareness in areas where significant relief exists, all relief exceeding 300 m (1 000 ft) above the elevation of the primary aerodrome should be shown by smoothed contour lines, contour values and layer tints printed in brown. Appropriate spot elevations, including the highest elevation within each top contour line should be shown printed in black. Significant obstacles should also be shown.
- Note 1.— The next higher suitable contour line appearing on base topographic maps exceeding 300 m (1 000 ft) above the elevation of the primary aerodrome may be selected to start layer tinting.
- Note 2.— An appropriate brown colour, on which half-tone layer tinting is to be based, is specified in Appendix 3 Colour Guide for contours and topographic features.
- Note 3.— Appropriate spot elevations and significant obstacles are those provided by the procedures specialists.

8.7 Magnetic variation

The average magnetic variation of the area covered by the chart shall be shown to the nearest degree.

8.8 Bearings, tracks and radials

- 8.8.1 Bearings, tracks and radials shall be magnetic, except as provided for in 8.8.2.
- 8.8.2 **Recommendation.** In areas of high latitude, where it is determined by the appropriate authority that reference to Magnetic North is impractical, another suitable reference, i.e. True North or Grid North, should be used.
- 8.8.3 Where bearings, tracks and radials are given with reference to True North or Grid North, this shall be clearly indicated. When Grid North is used its reference grid meridian shall be identified.

8.9 Aeronautical data

8.9.1 Aerodromes

All aerodromes which affect the terminal routings shall be shown. Where appropriate a runway pattern symbol shall be used.

8.9.2 Prohibited, restricted and danger areas

Prohibited, restricted and danger areas shall be depicted with their identification and vertical limits.

8.9.3 Area minimum altitudes

Area minimum altitudes shall be shown within quadrilaterals formed by the parallels and meridians.

Note.— Depending on the selected chart scale, quadrilaterals formed by the parallels and meridians normally correspond to the whole degree of latitude and longitude.

8.9.4 Air traffic services system

8.9.4.1 The components of the established relevant air traffic services system shall be shown.

8.9.4.1.1 The components shall include the following:

- the radio navigation aids associated with the air traffic services system together with their names, identifications, frequencies and geographical coordinates in degrees, minutes and seconds;
- in respect of DME, additionally the elevation of the transmitting antenna of the DME to the nearest 30 m (100 ft);

- terminal radio aids which are required for outbound and inbound traffic and for holding patterns;
- the lateral and vertical limits of all designated airspace and the appropriate class of airspace;
- holding patterns and terminal routings, together with the route designators, and the track to the nearest degree along each segment of the prescribed airways and terminal routings;
- 6) all significant points which define the terminal routings and are not marked by the position of a radio navigation aid, together with their name-codes and geographical coordinates in degrees, minutes and seconds;
- in respect of waypoints defining VOR/DME area navigation routes, additionally,
 - a) the station identification and radio frequency of the reference VOR/DME;
 - b) the bearing to the nearest tenth of a degree and the distance to the nearest two-tenths of a kilometre (tenth of a nautical mile) from the reference VOR/DME, if the waypoint is not collocated with it;
- an indication of all compulsory and "on-request" reporting points;
- 9) the distances to the nearest kilometre or nautical mile between significant points constituting turning points or reporting points;
 - Note.— Overall distances between radio navigation aids may also be shown.
- 10) change-over points on route segments defined by reference to very high frequency omnidirectional radio ranges, indicating the distances to the nearest kilometre or nautical mile to the radio navigation aids:
 - Note.— Change-over points established at midpoint between two aids, or at the intersection of two radials in the case of a route which changes direction between the aids, need not be shown for each route segment if a general statement regarding their existence is made.
- 11) minimum flight altitudes on ATS routes to the nearest higher 50 metres or 100 feet (see Annex 11, 2.21);
- 12) established minimum altitudes to the nearest higher 50 metres or 100 feet where radar vectoring on departure or arrival is provided, clearly identified;

1/11/01 8-2

Note.— Where radar procedures are used to vector aircraft to or from a significant point on a published standard departure or arrival route, these may be depicted on the Area Chart — ICAO unless excessive chart clutter will result.

- 13) area speed and level/altitude restrictions where established;
- 14) radio communication facilities listed with their frequencies.

8-3 1/11/01

CHAPTER 9. STANDARD DEPARTURE CHART — INSTRUMENT (SID) — ICAO

9.1 Function

This chart shall provide the flight crew with information to enable it to comply with the designated standard departure route — instrument from take-off phase to the enroute phase.

- Note 1.— Provisions governing the identification of standard departure routes are in Annex 11, Appendix 3; guidance material relating to the establishment of such routes is contained in the Air Traffic Services Planning Manual (Doc 9426).
- Note 2.— Provisions governing obstacle clearance criteria and details of the minimum information to be published are contained in PANS-OPS, Volume II, Part II (Doc 8168).

9.2 Availability

The Standard Departure Chart — Instrument (SID) — ICAO shall be made available wherever a standard departure route — instrument has been established and cannot be shown with sufficient clarity on the Area Chart — ICAO.

9.3 Coverage and scale

- 9.3.1 The coverage of the chart shall be sufficient to indicate the point where the departure route begins and the specified significant point at which the en-route phase of flight along a designated air traffic services route can be commenced.
- Note.— The departure route normally originates at the end of a runway.
- 9.3.2 **Recommendation.** The chart should be drawn to scale.
- 9.3.3 If the chart is drawn to scale, a scale-bar shall be shown.
- 9.3.4 When the chart is not drawn to scale the annotation "NOT TO SCALE" shall be shown and the symbol for scale-break shall be used on tracks and other aspects of the chart which are too large to be drawn to scale.

9.4 Projection

9.4.1 **Recommendation.**— A conformal projection on which a straight line approximates a great circle should be used.

- 9.4.2 **Recommendation.** When the chart is drawn to scale, parallels and meridians should be shown at suitable intervals.
- 9.4.3 Graduation marks shall be placed at consistent intervals along the neat lines, as appropriate.

9.5 Identification

- 9.5.1 Each sheet shall be identified by the name of the city or town, or area, which the aerodrome serves, the name of the aerodrome, and where appropriate, the runway designator(s) and the designator(s) of the standard departure route(s) instrument.
- 9.5.2 When departure routes are designed for RNAV, the additional abbreviation "RNAV" shall be given. If routes are restricted to specific sensors, these shall be indicated in subscript and parenthesis, e.g. "RNAV_(DME/DME)".
- Note.— The sensor does not form part of the ATC clearance.
- 9.5.3 For a VOR/DME RNAV procedure, the abbreviation "RNAV" or "RNAV $_{(VOR/DME)}$ " shall be followed by the identification of the reference VOR/DME.
- Note.— The identification does not form part of the ATC clearance.
- 9.5.4 When the departure route is designed for RNP, the abbreviation "RNP" shall be applied, and the RNP value shall be published in subscript and parenthesis, e.g. "RNP $_{(0.3)}$ ".
- 9.5.5 When operationally required, separate charts shall be published for each sensor or for a combination of navigation sensors. Separate charts shall only be published if the routes differ laterally or vertically.

9.6 Culture and topography

- 9.6.1 Where the chart is drawn to scale, generalized shore lines of all open water areas, large lakes and rivers shall be shown except where they conflict with data more applicable to the function of the chart.
- 9.6.2 **Recommendation.** To improve situational awareness in areas where significant relief exists, the chart

should be drawn to scale and all relief exceeding 300 m (1 000 ft) above the aerodrome elevation should be shown by smoothed contour lines, contour values and layer tints printed in brown. Appropriate spot elevations, including the highest elevation within each top contour line, should be shown printed in black. Significant obstacles should also be shown.

- Note 1.— The next higher suitable contour line appearing on base topographic maps exceeding 300 m (1 000 ft) above the aerodrome elevation may be selected to start layer tinting.
- Note 2.— An appropriate brown colour, on which half-tone layer tinting is to be based, is specified in Appendix 3—Colour Guide for contours and topographic features.
- Note 3.— Appropriate spot elevations and significant obstacles are those provided by the procedures specialists.

9.7 Magnetic variation

Magnetic variation used in determining the magnetic bearings, tracks and radials shall be shown to the nearest degree.

9.8 Bearings, tracks and radials

- 9.8.1 Bearings, tracks and radials shall be magnetic, except as provided for in 9.8.2.
 - Note.— A note to this effect may be included on the chart.
- 9.8.2 **Recommendation.** In areas of high latitude, where it is determined by the appropriate authority that reference to Magnetic North is impractical, another suitable reference, i.e. True North or Grid North, should be used.
- 9.8.3 Where bearings, tracks and radials are given with reference to True North or Grid North, this shall be clearly indicated. When Grid North is used its reference grid meridian shall be identified.

9.9 Aeronautical data

9.9.1 Aerodromes

- 9.9.1.1 The aerodrome of departure shall be shown by the runway pattern.
- 9.9.1.2 All aerodromes which affect the designated standard departure route instrument shall be shown and identified. Where appropriate the aerodrome runway patterns shall be shown.

9.9.2 Prohibited, restricted and danger areas

Prohibited, restricted and danger areas which may affect the execution of the procedures shall be shown with their identification and vertical limits.

9.9.3 Minimum sector altitude

- 9.9.3.1 The established minimum sector altitude, based on a navigation aid associated with the procedure, shall be shown with a clear indication of the sector to which it applies.
- 9.9.3.2 Where the minimum sector altitude has not been established, the chart shall be drawn to scale and area minimum altitudes shall be shown within quadrilaterals formed by the parallels and meridians. Area minimum altitudes shall also be shown in those parts of the chart not covered by the minimum sector altitude.
- Note.— Depending on the selected chart scale, quadrilaterals formed by the parallels and meridians normally correspond to the half-degree of latitude and longitude.

9.9.4 Air traffic services system

- 9.9.4.1 The components of the relevant air traffic services system shall be shown.
 - 9.9.4.1.1 The components shall comprise the following:
 - a graphic portrayal of each standard departure route instrument, including:
 - a) route designator;
 - b) significant points defining the route;
 - c) track or radial to the nearest degree along each segment of the route(s);
 - d) distances to the nearest kilometre or nautical mile between significant points;
 - e) minimum flight altitudes to the nearest higher 50 m or 100 ft along the route or route segments;
 - f) altitude to the nearest higher 50 m or 100 ft/flight level restrictions, where established;
 - Note.— Where radar procedures are used to vector aircraft to or from a significant point on a standard departure route, they may be shown.
 - 2) the radio navigation aid(s) associated with the route(s) including:
 - a) plain language name;

1/11/01 9-2

- b) identification;
- c) frequency;
- d) geographical coordinates in degrees, minutes and seconds;
- e) for DME, the channel and the elevation of the transmitting antenna of the DME to the nearest 30 m (100 ft);
- 3) the name-codes of the significant points not marked by the position of a radio navigation aid, their geographical coordinates in degrees, minutes and seconds and the bearing to the nearest tenth of a degree and distance to the nearest two-tenths of a kilometre (tenth of a nautical mile) from the reference radio navigation aid;
- 4) applicable holding patterns;
- 5) transition altitude/height to the nearest higher 300 m or 1 000 ft;
- the position and height of close-in obstacles which penetrate the obstacle identification surface (OIS). A

note shall be included whenever close-in obstacles penetrating the OIS exist but which were not considered for the published procedure design gradient.

Note.— In accordance with PANS-OPS, Volume II, information on close-in obstacles is provided by the procedures specialists.

- 7) area speed restrictions, where established;
- 8) all compulsory and "on-request" reporting points;
- 9) radio communication procedures, including:
 - a) call sign(s) of ATS unit(s);
 - b) frequency;
 - c) transponder setting, where appropriate.
- 9.9.4.2 **Recommendation.** A textual description of standard departure route(s) instrument (SID) and communication failure procedures in relation to radar control should be provided and should, whenever feasible, be shown on the chart or on the same page which contains the chart.

9-3 1/11/01

CHAPTER 10. STANDARD ARRIVAL CHART — INSTRUMENT (STAR) — ICAO

10.1 Function

This chart shall provide the flight crew with information to enable it to comply with the designated standard arrival route — instrument from the en-route phase to the approach phase.

- Note 1.— Standard arrival routes instrument are to be interpreted as including "standard descent profiles", "continuous descent approach", and other non-standard descriptions. In the case of a standard descent profile, the depiction of a cross-section is not required.
- Note 2.— Provisions governing the identification of standard arrival routes are in Annex 11, Appendix 3; guidance material relating to the establishment of such routes is contained in the Air Traffic Services Planning Manual (Doc 9426).

10.2 Availability

The Standard Arrival Chart — Instrument (STAR) — ICAO shall be made available wherever a standard arrival route — instrument has been established and cannot be shown with sufficient clarity on the Area Chart.

10.3 Coverage and scale

- 10.3.1 The coverage of the chart shall be sufficient to indicate the points where the en-route phase ends and the approach phase begins.
- 10.3.2 **Recommendation.** The chart should be drawn to scale.
- 10.3.3 If the chart is drawn to scale, a scale-bar shall be shown.
- 10.3.4 When the chart is not drawn to scale the annotation "NOT TO SCALE" shall be shown and the symbol for scale break shall be used on tracks and other aspects of the chart which are too large to be drawn to scale.

10.4 Projection

10.4.1 **Recommendation.**— A conformal projection on which a straight line approximates a great circle should be used.

- 10.4.2 **Recommendation.** When the chart is drawn to scale, parallels and meridians should be shown at suitable intervals.
- 10.4.3 Graduation marks shall be placed at consistent intervals along the neat lines, as appropriate.

10.5 Identification

- 10.5.1 Each sheet shall be identified by the name of the city or town, or area, which the aerodrome serves, the name of the aerodrome, and where appropriate, the runway designator(s) and the designator(s) of the standard arrival route(s) instrument.
- 10.5.2 When arrival routes are designed for RNAV, the additional abbreviation "RNAV" shall be given. If routes are restricted to specific sensors, these shall be indicated in subscript and parenthesis, e.g. "RNAV_(DME/DME)".
- Note.— The sensor does not form part of the ATC clearance.
- 10.5.3 For a VOR/DME RNAV arrival route, the abbreviation "RNAV" or "RNAV $_{\rm (VOR/DME)}$ " shall be followed by the identification of the reference VOR/DME.
- Note.— The identification does not form part of the ATC clearance.
- 10.5.4 When the arrival route is designed for RNP, the abbreviation "RNP" shall be applied, and the RNP value shall be published in subscript and parenthesis, e.g. "RNP $_{(0.3)}$ ".
- 10.5.5 When operationally required, separate charts shall be published for each sensor or for a combination of navigation sensors. Separate charts shall only be published if the routes differ laterally or vertically.

10.6 Culture and topography

- 10.6.1 Where the chart is drawn to scale, generalized shore lines of all open water areas, large lakes and rivers shall be shown except where they conflict with data more applicable to the function of the chart.
- 10.6.2 **Recommendation.** To improve situational awareness in areas where significant relief exists, the chart

should be drawn to scale and all relief exceeding 300 m (1 000 ft) above the aerodrome elevation should be shown by smoothed contour lines, contour values and layer tints printed in brown. Appropriate spot elevations, including the highest elevation within each top contour line, should be shown printed in black. Significant obstacles should also be shown.

- Note 1.— The next higher suitable contour line appearing on base topographic maps exceeding 300 m (1 000 ft) above the aerodrome elevation may be selected to start layer tinting.
- Note 2.— An appropriate brown colour, on which half-tone layer tinting is to be based, is specified in Appendix 3 Colour Guide for contours and topographic features.
- Note 3.— Appropriate spot elevations and significant obstacles are those provided by the procedures specialists.

10.7 Magnetic variation

Magnetic variation used in determining the magnetic bearings, tracks and radials shall be shown to the nearest degree.

10.8 Bearings, tracks and radials

- 10.8.1 Bearings, tracks and radials shall be magnetic, except as provided for in 10.8.2.
 - Note.— A note to this effect may be included on the chart.
- 10.8.2 **Recommendation.** In areas of high latitude, where it is determined by the appropriate authority that reference to Magnetic North is impractical, another suitable reference, i.e. True North or Grid North, should be used.
- 10.8.3 Where bearings, tracks and radials are given with reference to True North or Grid North, this shall be clearly indicated. When Grid North is used its reference grid meridian shall be identified.

10.9 Aeronautical data

10.9.1 Aerodromes

- 10.9.1.1 The aerodrome of landing shall be shown by the runway pattern.
- 10.9.1.2 All aerodromes which affect the designated standard arrival route instrument shall be shown and identified. Where appropriate the aerodrome runway patterns shall be shown.

10.9.2 Prohibited, restricted and danger areas

Prohibited, restricted and danger areas which may affect the execution of the procedures shall be shown with their identification and vertical limits.

10.9.3 Minimum sector altitude

- 10.9.3.1 The established minimum sector altitude shall be shown with a clear indication of the sector to which it applies.
- 10.9.3.2 Where the minimum sector altitude has not been established, the chart shall be drawn to scale and area minimum altitudes shall be shown within quadrilaterals formed by the parallels and meridians. Area minimum altitudes shall also be shown in those parts of the chart not covered by the minimum sector altitude.
- Note.— Depending on the selected chart scale, quadrilaterals formed by the parallels and meridians normally correspond to the half-degree of latitude and longitude.

10.9.4 Air traffic services system

- 10.9.4.1 The components of the relevant air traffic services system shall be shown.
 - 10.9.4.1.1 The components shall comprise the following:
 - 1) a graphic portrayal of each standard arrival route instrument, including:
 - a) route designator;
 - b) significant points defining the route;
 - c) track or radial to the nearest degree along each segment of the route;
 - d) distances to the nearest kilometre or nautical mile between significant points;
 - e) minimum flight altitudes to the nearest higher 50 m or 100 ft along the route or route segments;
 - f) altitude to the nearest higher 50 m or 100 ft/flight level restrictions, where established;
 - Note.— Where radar procedures are used to vector aircraft to or from a significant point on a standard arrival route, they may be shown.
 - 2) the radio navigation aid(s) associated with the route(s) including:
 - a) plain language name;

1/11/01 10-2

- b) identification;
- c) frequency;
- d) geographical coordinates in degrees, minutes and seconds;
- e) for DME, the channel and the elevation of the transmitting antenna of the DME to the nearest 30 m (100 ft);
- 3) the name-codes of the significant points not marked by the position of a radio navigation aid, their geographical coordinates in degrees, minutes and seconds and the bearing to the nearest tenth of a degree and distance to the nearest two-tenths of a kilometre (tenth of a nautical mile) from the reference radio navigation aid;
- 4) applicable holding patterns;

- 5) transition altitude/height to the nearest higher 300 m or 1 000 ft;
- 6) area speed restrictions, where established;
- 7) all compulsory and "on-request" reporting points;
- 8) radio communication procedures, including:
 - a) call sign(s) of ATS unit(s);
 - b) frequency;
 - c) transponder setting, where appropriate.
- 10.9.4.2 **Recommendation.** A textual description of standard arrival route(s) instrument (STAR) and communication failure procedures in relation to radar control, should be provided and should whenever feasible, be shown on the chart or on the same page which contains the chart.

10-3 1/11/01

CHAPTER 11. INSTRUMENT APPROACH CHART — ICAO

11.1 Function

This chart shall provide flight crews with information which will enable them to perform an approved instrument approach procedure to the runway of intended landing including the missed approach procedure and where applicable, associated holding patterns.

Note.— Detailed criteria for the establishment of instrument approach procedures and the resolutions of associated altitudes/heights are contained in the Procedures for Air Navigation Services — Aircraft Operations (Doc 8168).

11.2 Availability

- 11.2.1 Instrument Approach Charts ICAO shall be made available for all aerodromes used by international civil aviation where instrument approach procedures have been established by the State concerned.
- 11.2.2 A separate Instrument Approach Chart ICAO shall normally be provided for each precision approach procedure established by the State.
- 11.2.3 A separate Instrument Approach Chart ICAO shall normally be provided for each non-precision approach procedure established by the State.
- Note.— A single precision or non-precision approach procedure chart may be provided to portray more than one approach procedure when the procedures for the intermediate approach, final approach and missed approach segments are identical.
- 11.2.4 When the values for track, time or altitude differ between categories of aircraft on other than the final approach segment of the instrument approach procedures and the listing of these differences on a single chart could cause clutter or confusion, more than one chart shall be provided.
- Note.— For categories of aircraft, see Procedures for Air Navigation Services Aircraft Operations (Doc 8168), Vol. II, Part III, Chapter 1.
- 11.2.5 Instrument Approach Charts ICAO shall be revised whenever information essential to safe operation becomes out of date.

11.3 Coverage and scale

- 11.3.1 The coverage of the chart shall be sufficient to include all segments of the instrument approach procedure and such additional areas as may be necessary for the type of approach intended.
- 11.3.2 The scale selected shall ensure optimum legibility consistent with:
 - 1) the procedure shown on the chart;
 - 2) sheet size.
 - 11.3.3 A scale indication shall be given.
- 11.3.3.1 Except where this is not practicable, a distance circle with a radius of 20 km (10 NM) centred on a DME located on or close to the aerodrome, or on the aerodrome reference point where no suitable DME is available, shall be shown; its radius shall be indicated on the circumference.
- 11.3.3.2 **Recommendation.** A distance scale should be shown directly below the profile.

11.4 Format

Recommendation.— The sheet size should be $210 \times 148 \text{ mm } (8.27 \times 5.82 \text{ in}).$

11.5 Projection

- 11.5.1 A conformal projection on which a straight line approximates a great circle shall be used.
- 11.5.2 **Recommendation.** Graduation marks should be placed at consistent intervals along the neat lines.

11.6 Identification

11.6.1 The chart shall be identified by the name of the city or town, or area, which the aerodrome serves, the name of the aerodrome, the abbreviation of the type of radio navigation aid(s) on which the instrument approach procedure or the visual manoeuvring (circling) procedure is established and the designator of the runway where applicable.

- 11.6.2 Where the instrument approach procedure is limited to certain categories of aircraft this shall be shown in parentheses at the end of the identification.
- 11.6.3 When the instrument approach procedure is designed for RNAV, the additional abbreviation "RNAV" shall be given. If the procedure is restricted to specific sensors, these shall be indicated in subscript and parenthesis "RNAV_(DME/DME)".
- Note.— The sensor does not form part of the ATC clearance.
- 11.6.4 For a VOR/DME RNAV procedure, the additional abbreviation "RNAV" or "RNAV_(VOR/DME)" shall be followed by the identification of the reference VOR/DME.
- Note.— The identification does not form part of the ATC clearance.
- 11.6.5 When the instrument approach procedure is designed for RNP, the abbreviation "RNP" shall be applied, and the RNP value shall be published in subscript and parenthesis, e.g. "RNP $_{(0.3)}$ ".
- 11.6.6 When operationally required, separate charts shall be published for each sensor or for a combination of navigation sensors. Separate charts shall only be published if the routes differ laterally or vertically.

11.7 Culture and topography

- 11.7.1 Culture and topographic information pertinent to the safe execution of the instrument approach procedure, including the missed approach procedure, associated holding procedures and visual manoeuvring (circling) procedure when established, shall be shown. Topographic information shall be named, only when necessary, to facilitate the understanding of such information, and the minimum shall be a delineation of land masses and significant lakes and rivers.
- 11.7.2 Relief shall be shown in a manner best suited to the particular elevation characteristics of the area. In areas where relief exceeds 1 200 m (4 000 ft) above the aerodrome elevation within the coverage of the chart or 600 m (2 000 ft) within 11 km (6 NM) of the aerodrome reference point or when final approach or missed approach procedure gradient is steeper than optimal due to terrain, all relief exceeding 150 m (500 ft) above the aerodrome elevation shall be shown by smoothed contour lines, contour values and layer tints printed in brown. Appropriate spot elevations, including the highest elevation within each top contour line, shall also be shown printed in black.
- Note 1.— The next higher suitable contour line appearing on base topographic maps exceeding 150 m (500 ft) above the aerodrome elevation may be selected to start layer tinting.

Note 2.— An appropriate brown colour, on which half-tone layer tinting is to be based, is specified in Appendix 3—Colour Guide for contours and topographic features.

- Note 3.— Appropriate spot elevations are those provided by the procedures specialists.
- 11.7.3 **Recommendation.** In areas where relief is lower than specified in 11.7.2, all relief exceeding 150 m (500 ft) above the aerodrome elevation should be shown by smoothed contour lines, contour values and layer tints printed in brown. Appropriate spot elevations, including the highest elevation within each top contour line, should also be shown printed in black.
- Note 1.— The next higher suitable contour line appearing on base topographic maps exceeding 150 m (500 ft) above the aerodrome elevation may be selected to start layer tinting.
- Note 2.— An appropriate brown colour, on which half-tone layer tinting is to be based, is specified in Appendix 3—Colour Guide for contours and topographic features.
- Note 3.— Appropriate spot elevations are those provided by the procedures specialists.

11.8 Magnetic variation

- 11.8.1 **Recommendation.** The magnetic variation should be shown.
- 11.8.2 When shown, the value of the variation, indicated to the nearest degree, shall agree with that used in determining magnetic bearings, tracks and radials.

11.9 Bearings, tracks and radials

- 11.9.1 Bearings, tracks and radials shall be magnetic except as provided for in 11.9.2.
 - Note.— A note to this effect may be included on the chart.
- 11.9.2 **Recommendation.** In areas of high latitude where it is determined by the appropriate authority that reference to Magnetic North is impractical, another suitable reference, i.e. True North or Grid North, should be used.
- 11.9.3 Where bearings, tracks and radials are given with reference to True North or Grid North, this shall be clearly indicated. When Grid North is used its reference grid meridian shall be identified.

1/11/01 11-2

11.10 Aeronautical data

11.10.1 Aerodromes

- 11.10.1.1 All aerodromes which show a distinctive pattern from the air shall be shown by the appropriate symbol. Abandoned aerodromes shall be identified as abandoned.
- 11.10.1.2 The runway pattern, at a scale sufficiently large to show it clearly, shall be shown for:
 - 1) the aerodrome on which the procedure is based;
 - aerodromes affecting the traffic pattern or so situated as to be likely, under adverse weather conditions, to be mistaken for the aerodrome of intended landing.
- 11.10.1.3 The aerodrome elevation shall be shown to the nearest metre or foot in a prominent position on the chart.
- 11.10.1.4 The threshold elevation or, where applicable, the highest elevation of the touchdown zone shall be shown to the nearest metre or foot.

11.10.2 Obstacles

- 11.10.2.1 Significant obstacles shall be shown on the plan view of the chart.
- Note.— Appropriate significant obstacles are those provided by the procedures specialists.
- 11.10.2.2 **Recommendation.** If one or more obstacles are the determining factor of an obstacle clearance altitude/height, those obstacles should be identified.
- 11.10.2.3 The elevation of the top of obstacles shall be shown to the nearest (next higher) metre or foot.
- 11.10.2.4 **Recommendation.** The heights of obstacles above a datum other than mean sea level (see 11.10.2.3) should be shown. When shown, they should be given in parentheses on the chart.
- 11.10.2.5 When the heights of obstacles above a datum other than mean sea level are shown, the datum shall be the aerodrome elevation except that, at aerodromes having an instrument runway (or runways) with a threshold elevation more than 2 m (7 ft) below the aerodrome elevation, the chart datum shall be the threshold elevation of the runway to which the instrument approach is related.
- 11.10.2.6 Where a datum other than mean sea level is used, it shall be stated in a prominent position on the chart.
- 11.10.2.7 Where an obstacle free zone has been established for a precision approach runway category I, this shall be indicated or described.

11.10.3 Prohibited, restricted and danger areas

Prohibited areas, restricted areas, and danger areas which may affect the execution of the procedures shall be shown with their identification and vertical limits.

11.10.4 Radio communication facilities and navigation aids

- 11.10.4.1 Radio navigation aids required for the procedures together with their frequencies, identifications and track-defining characteristics, if any, shall be shown. In the case of a procedure in which more than one station is located on the final approach track, the facility to be used for track guidance for final approach shall be clearly identified. In addition, consideration shall be given to the elimination from the approach chart of those facilities that are not used by the procedure.
- 11.10.4.2 The final approach fix (or final approach point for an ILS approach procedure) and other essential fixes or points comprising the procedure shall be shown and identified.
- 11.10.4.3 **Recommendation.** The final approach fix (or final approach point for an ILS approach procedure) should be identified with its geographical coordinates in degrees, minutes and seconds.
- 11.10.4.4 Radio navigation aids that might be used in diversionary procedures together with their track-defining characteristics, if any, shall be shown or indicated on the chart.
- 11.10.4.5 Radio communication frequencies, including call signs, that are required for the execution of the procedures shall be shown.
- 11.10.4.6 When required by the procedures, the distance to the aerodrome from each radio navigation aid concerned with the final approach shall be shown to the nearest kilometre or nautical mile. When no track-defining aid indicates the bearing of the aerodrome, the bearing shall also be shown to the nearest degree.

11.10.5 Minimum sector altitude

The minimum sector altitude established by the competent authority shall be shown, with a clear indication of the sector to which it applies.

11.10.6 Portrayal of procedure tracks

11.10.6.1 The plan view shall show the following information in the manner indicated:

11-3 1/11/01

- a) the approach procedure track by an arrowed continuous line indicating the direction of flight;
- b) the missed approach procedure track by an arrowed broken line;
- c) any additional procedure track, other than those specified in a) and b), by an arrowed dotted line;
- d) bearings, tracks, radials to the nearest degree and distances to the nearest two-tenths of a kilometre or tenth of a nautical mile or times required for the procedure;
- e) where no track-defining aid is available, the magnetic bearing to the nearest degree to the aerodrome from the radio navigation aids concerned with the final approach;
- f) the boundaries of any sector in which visual manoeuvring (circling) is prohibited;
- g) where specified the holding pattern and minimum holding altitude/height associated with the approach and missed approach;
- h) caution notes where required, prominently displayed on the face of the chart.
- 11.10.6.2 **Recommendation.** The plan view should show the distance to the aerodrome from each radio navigation aid concerned with the final approach.
- 11.10.6.3 A profile shall be provided normally below the plan view showing the following data:
 - a) the aerodrome by a solid block at aerodrome elevation;
 - b) the profile of the approach procedure segments by an arrowed continuous line indicating the direction of flight;
 - c) the profile of the missed approach procedure segment by an arrowed broken line and a description of the procedure;
 - d) the profile of any additional procedure segment, other than those specified in b) and c), by an arrowed dotted line;
 - e) bearings, tracks, radials to the nearest degree and distances to the nearest two-tenths of a kilometre or tenth of a nautical mile or times required for the procedure;
 - f) altitude/heights required by the procedures, including transition altitude, where established:
 - g) limiting distance to the nearest kilometre or nautical mile on procedure turn, when specified;

- h) the intermediate approach fix or point, on procedures where no course reversal is authorized.
- a line representing the aerodrome elevation or threshold elevation, as appropriate, extended across the width of the chart including a distance scale with its origin at the runway threshold.
- 11.10.6.4 **Recommendation.** Heights required by procedures should be shown in parentheses, using the height datum selected in accordance with 11.10.2.5.
- 11.10.6.5 **Recommendation.** A ground profile should be shown by a solid line depicting the highest elevations of the relief occurring within the primary area of the final approach segment. The highest elevations of the relief occurring in the secondary areas of the final approach segment should be shown on the profile by a dashed line.
- Note.— Actual templates of the primary and secondary areas of the final approach segment are provided to the cartographer by the procedures specialist.

11.10.7 Aerodrome operating minima

- 11.10.7.1 Aerodrome operating minima when established by the State shall be shown.
- 11.10.7.2 The obstacle clearance altitudes/heights as appropriate shall be shown.

11.10.8 Supplementary information

- 11.10.8.1 When the missed approach point is defined by:
- a distance from the final approach fix, or
- a facility or a fix and the corresponding distance from the final approach fix,

the distance to the nearest two-tenths of a kilometre or tenth of a nautical mile and a table showing ground speeds and times from the final approach fix to the missed approach point shall be shown.

- 11.10.8.2 When DME is required for use in the final approach segment, a table showing altitudes/heights for each 2 km or 1 NM, as appropriate, shall be shown. The table shall not include distances which would correspond to altitudes/heights below the OCA/H.
- 11.10.8.3 **Recommendation.** For procedures in which DME is not required for use in the final approach segment but where a suitably located DME is available to provide advisory

1/11/01 11-4

descent profile information, a table showing the altitudes/heights should be included.

- 11.10.8.4 **Recommendation.** A rate of descent table should be shown.
- 11.10.8.5 Final approach descent gradient and, in parenthesis, descent angle to the nearest one tenth of a degree shall be shown for non-precision procedures with a final approach fix.
- 11.10.8.6 On charts depicting ILS/MLS and LNAV/VNAV approach procedures, the height of the ILS/MLS and LNAV/VNAV reference datum to the nearest half metre or foot and the glide path/elevation/vertical path angle shall be shown. If the ILS/MLS glide path/elevation angle exceeds 3.5°, a note shall be included referring to appropriate aircraft and flight crew qualification requirements for such a procedure.
- *Note.* See Procedures for Air Navigation Services Aircraft Operations, Volume II (Doc 8168) about additional requirements when glide path angles/elevations exceed 3.5°.

11.10.8.7 Final approach descent angle shall be shown to the nearest one tenth of a degree for instrument procedures with vertical guidance.

11.10.9 Aeronautical data base requirements

The following data shall be published in tabular form on the verso of the chart or as a separate, properly referenced sheet:

- a) final approach fixes/points and other essential fixes/ points comprising the instrument approach procedure identified with their geographical coordinates in degrees, minutes, seconds and tenths of seconds;
- b) instrument approach procedure fix formation bearings to the nearest hundredth of a degree; and
- c) instrument approach procedure fix formations distance to the nearest one hundredth of a nautical mile; and
- d) for non-precision approaches, the final approach descent angle to the nearest one hundredth of a degree.

11-5 1/11/01

CHAPTER 12. VISUAL APPROACH CHART — ICAO

12.1 Function

This chart shall provide flight crews with information which will enable them to transit from the en-route/descent to approach phases of flight to the runway of intended landing by means of visual reference.

12.2 Availability

The Visual Approach Chart — ICAO shall be made available in the manner prescribed in 1.3.2 for all aerodromes used by international civil aviation where:

- 1) only limited navigation facilities are available; or
- 2) radio communication facilities are not available; or
- no adequate aeronautical charts of the aerodrome and its surroundings at 1:500 000 or greater scale are available; or
- 4) visual approach procedures have been established.

12.3 Scale

- 12.3.1 The scale shall be sufficiently large to permit depiction of significant features and indication of the aero-drome layout.
- 12.3.2 **Recommendation.** The scale should not be smaller than 1:500 000.
 - Note.— A scale of 1:250 000 or 1:200 000 is preferred.
- 12.3.3 **Recommendation.** When an Instrument Approach Chart is available for a given aerodrome, the Visual Approach Chart should be drawn to the same scale.

12.4 Format

Recommendation.— The sheet size should be $210 \times 148 \text{ mm } (8.27 \times 5.82 \text{ in}).$

Note.— It would be advantageous to print the charts in several colours, selected to provide maximum legibility in varying degrees and kinds of light.

12.5 Projection

- 12.5.1 A conformal projection on which a straight line approximates a great circle shall be used.
- 12.5.2 **Recommendation.** Graduation marks should be placed at consistent intervals along the neat lines.

12.6 Identification

The chart shall be identified by the name of the city or town which the aerodrome serves and the name of the aerodrome.

12.7 Culture and topography

- 12.7.1 Natural and cultural landmarks shall be shown (e.g. bluffs, cliffs, sand dunes, cities, towns, roads, railroads, isolated lighthouses, etc.).
- 12.7.1.1 **Recommendation.** Geographical place names should be included only when they are required to avoid confusion or ambiguity.
- 12.7.2 Shore lines, lakes, rivers and streams shall be shown.
- 12.7.3 Relief shall be shown in a manner best suited to the particular elevation and obstacle characteristics of the area covered by the chart.
- 12.7.4 **Recommendation.** When shown, spot elevations should be carefully selected.
- Note.— The value of certain spot elevations/heights in relation to both mean sea level and aerodrome elevation may be given.
- 12.7.5 The figures relating to different reference levels shall be clearly differentiated in their presentation.

12.8 Magnetic variation

The magnetic variation shall be shown.

12.9 Bearings, tracks and radials

- 12.9.1 Bearings, tracks and radials shall be magnetic except as provided for in 12.9.2.
- 12.9.2 **Recommendation.** In areas of high latitude where it is determined by the appropriate authority that reference to Magnetic North is impractical another suitable reference, i.e. True North or Grid North, should be used.
- 12.9.3 Where bearings, tracks or radials are given with reference to True North or Grid North, this shall be clearly indicated. When Grid North is used its reference grid meridian shall be identified.

12.10 Aeronautical data

12.10.1 Aerodromes

- 12.10.1.1 All aerodromes shall be shown by the runway pattern. Restrictions on the use of any landing direction shall be indicated. Where there is any risk of confusion between two neighbouring aerodromes this shall be indicated. Abandoned aerodromes shall be identified as abandoned.
- 12.10.1.2 The aerodrome elevation shall be shown in a prominent position on the chart.

12.10.2 Obstacles

- 12.10.2.1 Significant obstacles shall be shown and identified.
- 12.10.2.2 The elevation of the top of obstacles shall be shown to the nearest (next higher) metre or foot.
- 12.10.2.3 **Recommendation.** The heights of obstacles above the aerodrome elevation should be shown.

12.10.2.3.1 When the heights of obstacles are shown, the height datum shall be stated in a prominent position on the chart and the heights shall be given in parentheses on the chart.

12.10.3 Prohibited, restricted and danger areas

Prohibited areas, restricted areas, and danger areas shall be depicted with their identification and vertical limits.

12.10.4 Designated airspace

Where applicable, control zones and aerodrome traffic zones shall be depicted with their vertical limits and the appropriate class of airspace.

12.10.5 Visual approach information

- 12.10.5.1 Visual approach procedures shall be shown where applicable.
- 12.10.5.2 Visual aids for navigation shall be shown as appropriate.
- 12.10.5.3 Location and type of the visual approach slope indicator systems with their nominal approach slope angle(s), minimum eye height(s) over the threshold of the on-slope signal(s), and where the axis of the system is not parallel to the runway centre line, the angle and direction of displacement, i.e. left or right, shall be shown.

12.10.6 Supplementary information

- 12.10.6.1 Radio navigation aids together with their frequencies and identifications shall be shown as appropriate.
- 12.10.6.2 Radio communication facilities with their frequencies shall be shown as appropriate.

1/11/01 12-2

CHAPTER 13. AERODROME/HELIPORT CHART — ICAO

13.1 Function

This chart shall provide flight crews with information which will facilitate the ground movement of aircraft:

- a) from the aircraft stand to the runway; and
- b) from the runway to the aircraft stand;

and helicopter movement:

- a) from the helicopter stand to the touchdown and lift-off area and to the final approach and take-off area;
- b) from the final approach and take-off area to the touchdown and lift-off area and to the helicopter stand;
- c) along helicopter ground and air taxiways; and
- d) along air transit routes;

it shall also provide essential operational information at the aerodrome/heliport.

13.2 Availability

- 13.2.1 The Aerodrome/Heliport Chart ICAO shall be made available in the manner prescribed in 1.3.2 for all aerodromes/heliports regularly used by international civil aviation.
- 13.2.2 **Recommendation.** The Aerodrome/Heliport Chart ICAO should be made available also, in the manner prescribed in 1.3.2, for all other aerodromes/heliports available for use by international civil aviation.

Note.— Under certain conditions an Aerodrome Ground Movement Chart — ICAO and an Aircraft Parking/Docking Chart — ICAO may have to be provided (see Chapters 14 and 15); in which case, the elements portrayed on these supplementary charts need not be duplicated on the Aerodrome/Heliport Chart — ICAO.

13.3 Coverage and scale

- 13.3.1 The coverage and scale shall be sufficiently large to show clearly all the elements listed in 13.6.1.
 - 13.3.2 A linear scale shall be shown.

13.4 Identification

The chart shall be identified by the name of the city or town, or area, which the aerodrome/heliport serves and the name of the aerodrome/heliport.

13.5 Magnetic variation

True and Magnetic North arrows and magnetic variation to the nearest degree and annual change of the magnetic variation shall be shown.

13.6 Aerodrome/heliport data

13.6.1 This chart shall show:

- a) geographical coordinates in degrees, minutes and seconds for the aerodrome/heliport reference point;
- b) elevations to the nearest metre or foot of the aerodrome/heliport, of non-precision approach runway thresholds and apron (altimeter checkpoint locations) where applicable;
- elevations and geoid undulations to the nearest half metre or foot of runway thresholds, geometric centre of touchdown and lift-off area and the highest elevation of the touchdown zone of a precision approach runway;
- all runways including those under construction with designation number, length and width to the nearest metre, bearing strength, displaced thresholds, stopways, clearways, runway directions to the nearest degree magnetic, type of surface, and runway markings;

Note.— Bearing strengths may be shown in tabular form on the face or verso of the chart.

 e) all aprons, with aircraft/helicopter stands, lighting, markings and other visual guidance and control aids, where applicable, including location and type of visual docking guidance systems, type of surface for heliports, and bearing strengths or aircraft type restrictions where the bearing strength is less than that of the associated runways;

Note.— Bearing strengths or aircraft type restrictions may be shown in tabular form on the face or verso of the chart.

- geographical coordinates in degrees, minutes and seconds for thresholds, geometric centre of touchdown and lift-off area and/or thresholds of the final approach and take-off area (where appropriate);
- g) all taxiways, helicopter air and ground taxiways with type of surface, helicopter air transit routes, with designations, width, lighting, markings, including runway-holding positions and stop bars, other visual guidance and control aids, and bearing strength or aircraft type restrictions where the bearing strength is less than that of the associated runways;
 - Note.— Bearing strengths or aircraft type restrictions may be shown in tabular form on the face or verso of the chart.
- geographical coordinates in degrees, minutes, seconds and hundredths of seconds for appropriate taxiway centre line points and aircraft stands;
- where established, standard routes for taxiing aircraft with their designators;
- j) the boundaries of the air traffic control service;
- k) position of runway visual range (RVR) observation sites:
- 1) approach and runway lighting;
- m) location and type of the visual approach slope indicator systems with their nominal approach slope angle(s), minimum eye height(s) over the threshold of the on-slope signal(s), and where the axis of the system is not parallel to the runway centre line, the angle and direction of the displacement, i.e. left or right;
- n) radio communication facilities;
- o) significant obstacles to taxiing;

- aircraft servicing areas and buildings of operational significance;
- q) VOR checkpoint and radio frequency of the aid concerned;
- r) any part of the depicted movement area permanently unsuitable for aircraft, clearly identified as such.
- 13.6.2 In addition to the items in 13.6.1 relating to heliports, the chart shall show:
 - a) heliport type;
 - Note.— Heliport types are identified in Annex 14, Volume II as surface-level, elevated or helideck.
 - b) touchdown and lift-off area including dimensions to the nearest metre, slope, type of surface and bearing strength in tonnes;
 - c) final approach and take-off area including type, true bearing to the nearest degree, designation number (where appropriate), length and width to the nearest metre, slope and type of surface;
 - d) safety area including length, width and type of surface;
 - e) helicopter clearway including length and ground profile;
 - f) significant obstacles including type and elevation of the top of the obstacles to the nearest (next higher) metre or foot;
 - g) visual aids for approach procedures, marking and lighting of final approach and take-off area, and of touchdown and lift-off area;
 - h) declared distances to the nearest metre for heliports, where relevant, including:
 - 1) take-off distance available;
 - 2) rejected take-off distance available;
 - 3) landing distance available.

1/11/01 13-2

CHAPTER 14. AERODROME GROUND MOVEMENT CHART — ICAO

14.1 Function

This supplementary chart shall provide flight crews with detailed information to facilitate the ground movement of aircraft to and from the aircraft stands and the parking/docking of aircraft.

14.2 Availability

Recommendation.— The Aerodrome Ground Movement Chart — ICAO should be made available in the manner prescribed in 1.3.2 where, due to congestion of information, details necessary for the ground movement of aircraft along the taxiways to and from the aircraft stands cannot be shown with sufficient clarity on the Aerodrome/Heliport Chart — ICAO.

14.3 Coverage and scale

- 14.3.1 The coverage and scale shall be sufficiently large to show clearly all the elements listed in 14.6.
- 14.3.2 **Recommendation.** A linear scale should be shown.

14.4 Identification

The chart shall be identified by the name of the city or town which the aerodrome serves and the name of the aerodrome.

14.5 Magnetic variation

- 14.5.1 A True North arrow shall be shown.
- 14.5.2 **Recommendation.** *Magnetic variation to the nearest degree and its annual change should be shown.*

Note.— This chart need not be True North orientated.

14.6 Aerodrome data

This chart shall show in a similar manner all the information on the Aerodrome/Heliport Chart — ICAO relevant to the area depicted, including:

- a) apron elevation to the nearest metre or foot;
- aprons, with aircraft stands, bearing strengths or aircraft type restrictions, lighting, marking and other visual guidance and control aids, where applicable, including location and type of visual docking guidance systems;
- c) geographical coordinates in degrees, minutes, seconds and hundredths of seconds for aircraft stands;
- d) taxiways with designations, width to the nearest metre, bearing strength or aircraft type restrictions where applicable, lighting, markings, including runwayholding positions and stop bars and other visual guidance and control aids;
- e) where established, standard routes for taxiing aircraft, with their designators;
- f) geographical coordinates in degrees, minutes, seconds and hundredths of seconds for appropriate taxiway centre line points;
- g) the boundaries of the air traffic control service;
- h) relevant radio communication facilities listed with their frequencies;
- i) significant obstacles to taxiing;
- j) aircraft servicing areas and buildings of operational significance;
- k) VOR checkpoint and radio frequency of the aid concerned;
- any part of the depicted movement area permanently unsuitable for aircraft, clearly identified as such.

CHAPTER 15. AIRCRAFT PARKING/DOCKING CHART — ICAO

15.1 Function

This supplementary chart shall provide flight crews with detailed information to facilitate the ground movement of aircraft between the taxiways and the aircraft stands and the parking/docking of aircraft.

15.2 Availability

Recommendation.— The Aircraft Parking/ Docking Chart — ICAO should be made available in the manner prescribed in 1.3.2 where, due to the complexity of the terminal facilities, the information cannot be shown with sufficient clarity on the Aerodrome/Heliport Chart — ICAO or on the Aerodrome Ground Movement Chart — ICAO.

15.3 Coverage and scale

- 15.3.1 The coverage and scale shall be sufficiently large to show clearly all the elements listed in 15.6.
- 15.3.2 **Recommendation.** A linear scale should be shown.

15.4 Identification

The chart shall be identified by the name of the city or town which the aerodrome serves and the name of the aerodrome.

15.5 Magnetic variation

- 15.5.1 A True North arrow shall be shown.
- 15.5.2 **Recommendation.** Magnetic variation to the nearest degree and its annual change should be shown.

Note.— This chart need not be True North orientated.

15.6 Aerodrome data

This chart shall show in a similar manner all the information on the Aerodrome/Heliport Chart — ICAO and the Aerodrome Ground Movement Chart — ICAO relevant to the area depicted, including:

- a) apron elevation to the nearest metre or foot;
- b) aprons with aircraft stands, bearing strengths or aircraft type restrictions, lighting, marking and other visual guidance and control aids, where applicable, including location and type of visual docking guidance systems;
- c) geographical coordinates in degrees, minutes, seconds and hundredths of seconds for aircraft stands;
- d) taxiway entries with designations, including runwayholding positions and stop bars;
- e) geographical coordinates in degrees, minutes, seconds and hundredths of seconds for appropriate taxiway centre line points;
- f) the boundaries of the air traffic control service;
- g) relevant radio communication facilities listed with their frequencies;
- h) significant obstacles to taxiing;
- i) aircraft servicing areas and buildings of operational significance;
- j) VOR checkpoint and radio frequency of the aid concerned;
- k) any part of the depicted movement area permanently unsuitable for aircraft clearly identified as such.

CHAPTER 16. WORLD AERONAUTICAL CHART — ICAO 1:1 000 000

16.1 Function

This chart shall provide information to satisfy the requirements of visual air navigation.

Note.— This chart may also serve:

- 1) as a basic aeronautical chart:
 - a) when highly specialized charts lacking visual information do not provide essential data;
 - b) to provide complete world coverage at a constant scale with a uniform presentation of planimetric data;
 - c) in the production of other charts required by international civil aviation;
- 2) as a pre-flight planning chart.

16.2 Availability

- 16.2.1 The World Aeronautical Chart ICAO 1:1 000 000 shall be made available in the manner prescribed in 1.3.2 for all areas delineated in Appendix 5.
- Note.— When operational or chart production considerations indicate that operational requirements can be effectively satisfied by Aeronautical Charts ICAO 1:500 000 or Aeronautical Navigation Charts ICAO Small Scale, either of these charts may be made available instead of the basic 1:1 000 000 chart.
- 16.2.2 **Recommendation.** To ensure complete coverage of all land areas and adequate continuity in any one coordinated series, the selection of a scale of other than 1:1 000 000 should be determined by regional agreement.

16.3 Scales

- 16.3.1 Linear scales for kilometres and nautical miles arranged in the following order:
 - kilometres,
 - nautical miles,

with their zero points in the same vertical line shall be shown in the margin.

- 16.3.1.1 **Recommendation.** The length of the linear scales should represent at least 200 km (110 NM).
- 16.3.2 A conversion scale (metres/feet) shall be shown in the margin.

16.4 Format

- 16.4.1 **Recommendation.** The title and marginal notes should be in one of the ICAO working languages.
- Note.— The language of the publishing country may be used in addition to the ICAO working language.
- 16.4.2 The information regarding the number of the adjoining sheets and the unit of measurement to express elevations shall be so located as to be clearly visible when the sheet is folded.
- 16.4.3 **Recommendation.** The method of folding should be as follows:

Fold the chart on the long axis, near the mid-parallel of latitude, face out; with the bottom half of the chart face upward, fold inwards near the meridian, and fold both halves backward in accordion folds.

- 16.4.4 **Recommendation.** Whenever practicable, the sheet lines should conform with those shown in the index in Appendix 5.
- Note 1.— The area covered by a sheet may vary from the lines shown to satisfy particular requirements.
- Note 2.— The value of adopting identical sheet lines for ICAO 1:1 000 000 Charts and the corresponding sheet of the International Map of the World (IMW), provided aeronautical requirements are not compromised, is recognized.
- 16.4.5 The sheet lines used shall be notified to ICAO for publication in the ICAO *Aeronautical Chart Catalogue* (Doc 7101).
- 16.4.6 **Recommendation.** Overlaps should be provided by extending the chart area on the top and right side beyond the area given on the index. This overlap area should contain all aeronautical, topographical, hydrographical and cultural information. The overlap should extend up to 28 km (15 NM) if possible but in any case from the limiting parallels and meridians of each chart to the neat line.

16.5 Projection

- 16.5.1 The projections shall be as follows:
- between the Equator and 80° latitude: the Lambert conformal conic projection, in separate bands for each tier of charts. The standard parallels for each 4° band shall be 40′ south of the northern parallel and 40′ north of the southern parallel;
- 2) between 80° and 90° latitude: the Polar stereographic projection with scale matching that of the Lambert conformal conic projection at latitude 80°, except that in the northern hemisphere the Lambert conformal conic projection may be used between 80° and 84° latitude and the Polar stereographic projection between 84° and 90° with the scales matching at 84° North.
- 16.5.2 Graticules and graduations shall be shown as follows:

1) Parallels:

Latitude	Distance between parallels	Graduations on parallels
0° to 72°	30′	1′
72° to 84°	30′	5′
84° to 89°	30′	1°
89° to 90°	30′	5°
		(Only on
		degree parallel
		from 72° to 89°

2) Meridians:

Latitude	Interval between meridians	Graduations on meridians
0° to 52°	30′	1'
52° to 72°	30′	1'
		(Only on even
		numbered
		meridians)
72° to 84°	1°	1'
84° to 89°	5°	1'
89° to 90°	15°	1'
		(Only on
		every fourth
		meridian)

16.5.3 The graduation marks at 1' and 5' intervals shall extend away from the Greenwich Meridian and from the Equator. Each 10' interval shall be shown by a mark on both sides of the graticule line.

- 16.5.3.1 **Recommendation.** The length of the graduation marks should be approximately 1.3 mm (0.05 in) for the 1' intervals, and 2 mm (0.08 in) for the 5' intervals and 2 mm (0.08 in) extending on both sides of the graticule line for the 10' intervals.
- 16.5.4 All meridians and parallels shall be numbered in the borders of the charts. In addition, each parallel shall be numbered within the body of the chart in such a manner that the parallel can be readily identified when the chart is folded.
- Note.— Meridians may be numbered within the body of the chart.
- 16.5.5 The name and basic parameters of the projection shall be indicated in the margin.

16.6 Identification

Sheet numbering shall be in conformity with the index in Appendix 5.

Note.— The corresponding International Map of the World (IMW) sheet number may also be shown.

16.7 Culture and topography

16.7.1 Built-up areas

- 16.7.1.1 Cities, towns and villages shall be selected and shown according to their relative importance to visual air navigation.
- 16.7.1.2 **Recommendation.** Cities and towns of sufficient size should be indicated by the outline of their built-up areas and not of their established city limits.

16.7.2 Railroads

- 16.7.2.1 All railroads having landmark value shall be shown.
- Note 1.— In congested areas, some railroads may be omitted in the interest of legibility.
 - Note 2.— Railroads may be named where space permits.
- 16.7.2.2 **Recommendation.** *Important tunnels should be shown.*
 - Note.— A descriptive note may be added.

1/11/01 16-2

16.7.3 Highways and roads

- 16.7.3.1 Road systems shall be shown in sufficient detail to indicate significant patterns from the air.
- 16.7.3.2 **Recommendation.** Roads should not be shown in built-up areas unless they can be distinguished from the air as definite landmarks.

Note.— The numbers or names of important highways may be shown.

16.7.4 Landmarks

Recommendation.— Natural and cultural landmarks, such as bridges, prominent transmission lines, permanent cable car installations, mine structures, forts, ruins, levees, pipelines, and rocks, bluffs, cliffs, sand dunes, isolated lighthouses, lightships, etc., when considered to be of importance for visual air navigation, should be shown.

Note.— Descriptive notes may be added.

16.7.5 Political boundaries

International boundaries shall be shown. Undemarcated and undefined boundaries shall be distinguished by descriptive notes.

16.7.6 Hydrography

- 16.7.6.1 All water features compatible with the scale of the chart comprising shore lines, lakes, rivers and streams (including those non-perennial in nature), salt lakes, glaciers and ice caps shall be shown.
- 16.7.6.2 **Recommendation.** The tint covering large open water areas should be kept very light.
- Note.— A narrow band of darker tone may be used along the shore line to emphasize this feature.
- 16.7.6.3 **Recommendation.** Reefs and shoals including rocky ledges, tidal flats, isolated rocks, sand, gravel, stone and all similar areas should be shown by symbols when of significant landmark value.
- Note.— Groups of rocks may be shown by a few representative rock symbols within the area.

16.7.7 Contours

- 16.7.7.1 Contours shall be shown. The selection of intervals shall be governed by the requirement to depict clearly the relief features required in air navigation.
 - 16.7.7.2 The values of the contours used shall be shown.

16.7.8 Hypsometric tints

- 16.7.8.1 When hypsometric tints are used the range of elevations for the tints shall be shown.
- 16.7.8.2 The scale of the hypsometric tints used on the chart shall be shown in the margin.

16.7.9 Spot elevations

- 16.7.9.1 Spot elevations shall be shown at selected critical points. The elevations selected shall always be the highest in the immediate vicinity and shall generally indicate the top of a peak, ridge, etc. Elevations in valleys and at lake surface levels which are of special value to the aviator shall be shown. The position of each selected elevation shall be indicated by a dot.
- 16.7.9.2 The elevation (in metres or feet) of the highest point on the chart and its geographical position to the nearest five minutes shall be indicated in the margin.
- 16.7.9.3 **Recommendation.** The spot elevation of the highest point in any sheet should be cleared of hypsometric tinting.

16.7.10 Incomplete or unreliable relief

- 16.7.10.1 Areas that have not been surveyed for contour information shall be labelled "Relief data incomplete".
- 16.7.10.2 Charts on which spot elevations are generally unreliable shall bear a warning note prominently displayed on the face of the chart in the colour used for aeronautical information, as follows:

"Warning — The reliability of relief information on this chart is doubtful and elevations should be used with caution."

16.7.11 Escarpments

Recommendation.— Escarpments should be shown when they are prominent landmarks or when cultural detail is very sparse.

16.7.12 Wooded areas

16.7.12.1 **Recommendation.**— Wooded areas should be shown.

Note.— On high latitude charts, the approximate extreme northern or southern limits of tree growth may be shown.

16-3 1/11/01

16.7.12.2 Where shown, the approximate extreme northern or southern limits of tree growth shall be indicated by a dashed black line and shall be appropriately labelled.

16.7.13 Date of topographic information

The date of latest information shown on the topographic base shall be indicated in the margin.

16.8 Magnetic variation

- 16.8.1 Isogonic lines shall be shown.
- 16.8.2 The date of the isogonic information shall be indicated in the margin.

16.9 Aeronautical data

16.9.1 Aeronautical data shown shall be kept to a minimum consistent with the use of the chart for visual navigation and the revision cycle (see 16.9.6).

16.9.2 Aerodromes

- 16.9.2.1 Land and water aerodromes and heliports shall be shown with their names, to the extent that they do not produce undesirable congestion on the chart, priority being given to those of greatest aeronautical significance.
- 16.9.2.2 The aerodrome elevation, the lighting available, the type of runway surface and the length of the longest runway or channel, shown in abbreviated form for each aerodrome in conformity with the example given in Appendix 2, provided they do not cause undesirable clutter on the chart, shall be indicated.
- 16.9.2.3 Abandoned aerodromes which are still recognizable as aerodromes from the air shall be shown and identified as abandoned.

16.9.3 Obstacles

16.9.3.1 Significant obstacles shall be shown.

Note.— Obstacles of a height of 100 m (300 ft) or more above ground are normally regarded as significant obstacles.

16.9.3.2 When considered of importance to visual flight, prominent transmission lines and permanent cable car installations, which are significant obstacles, shall be shown.

16.9.4 Prohibited, restricted and danger areas

Prohibited, restricted and danger areas shall be shown.

16.9.5 Air traffic services system

- 16.9.5.1 Significant elements of the air traffic services system including, where practicable, control zones, aerodrome traffic zones, control areas, flight information regions and other airspaces in which VFR flights operate shall be shown together with the appropriate class of airspace.
- 16.9.5.2 Where appropriate, the air defence identification zone (ADIZ) shall be shown and properly identified.

Note.— ADIZ procedures may be described in the chart legend.

16.9.6 Radio navigation aids

Radio navigation aids shall be shown by the appropriate symbol and named, but excluding their frequencies, coded designators, times of operation and other characteristics unless any or all of this information which is shown is kept up to date by means of new editions of the chart.

16.9.7 Supplementary information

- 16.9.7.1 Aeronautical ground lights together with their characteristics or their identifications or both shall be shown.
- 16.9.7.2 Marine lights on outer prominent coastal or isolated features of not less than 28 km (15 NM) visibility range shall be shown:
 - 1) where they are not less distinguishable than more powerful marine lights in the vicinity;
 - where they are readily distinguishable from other marine or other types of lights in the vicinity of built-up coastal areas;
 - 3) where they are the only lights of significance available.

1/11/01 16-4

CHAPTER 17. AERONAUTICAL CHART — ICAO 1:500 000

17.1 Function

This chart shall provide information to satisfy the requirements of visual air navigation for low speed, short- or medium-range operations at low and intermediate altitudes.

Note 1.— This chart may be used:

- a) to serve as a basic aeronautical chart;
- b) to provide a suitable medium for basic pilot and navigation training;
- c) to supplement highly specialized charts which do not provide essential visual information;
- d) in pre-flight planning.
- Note 2.— It is intended that these charts be provided for land areas where charts of this scale are required for civil air operations employing visual air navigation independently or in support of other forms of air navigation.
- Note 3.— Where States produce charts of this series covering their national territories, the entire area being portrayed is usually treated on a regional basis.

17.2 Availability

Recommendation.— The Aeronautical Chart — ICAO 1:500 000 should be made available in the manner prescribed in 1.3.2 for all areas delineated in Appendix 5.

Note.— The selection of this scale as an alternative to the World Aeronautical Chart — ICAO 1:1 000 000 is covered by 16.2.1 and 16.2.2.

17.3 Scales

- 17.3.1 Linear scales for kilometres and nautical miles arranged in the following order:
 - kilometres,
 - nautical miles,

with their zero points in the same vertical line shall be shown in the margin.

- 17.3.1.1 **Recommendation.** The length of the linear scale should be not less than 200 mm (8 in).
- 17.3.2 A conversion scale (metres/feet) shall be shown in the margin.

17.4 Format

- 17.4.1 The title and marginal notes shall be in one of the working languages of ICAO.
- Note.— The language of the publishing country or any other language may be used in addition to the ICAO working language.
- 17.4.2 The information regarding the number of the adjoining sheets and the unit of measurement used to express elevation shall be so located as to be clearly visible when the sheet is folded.
- 17.4.3 **Recommendation.** The method of folding should be as follows:

Fold the chart on the long axis near the mid-parallel of latitude, face out, with the bottom part of the chart face upward. Fold inwards near the meridian and fold both halves backward in accordion folds.

- 17.4.4 **Recommendation.** Whenever practicable, sheets should be quarter sheets of the World Aeronautical Chart ICAO 1:1 000 000. An appropriate index to adjacent sheets, showing the relationship between the two chart series should be included on the face of the chart or on the reverse side.
- Note.— Sheet lines may be varied to satisfy particular requirements.
- 17.4.5 **Recommendation.** Overlaps should be provided by extending the chart area on the top and right side beyond the area given on the index. This overlap area should contain all aeronautical, topographical, hydrographical and cultural information. The overlap should extend up to 15 km (8 NM), if possible, but in any case from the limiting parallels and meridians of each chart to the neat line.

17.5 Projection

17.5.1 A conformal (orthomorphic) projection shall be used.

- 17.5.2 **Recommendation.** The projection of the World Aeronautical Chart ICAO 1:1 000 000 should be used.
 - 17.5.3 Parallels shall be shown at intervals of 30'.
- 17.5.3.1 Meridians shall normally be shown at intervals of 30'.
 - Note.— At high latitudes this interval may be increased.
- 17.5.4 Graduation marks shall be shown at 1' intervals along each whole degree meridian and parallel, extending away from the Greenwich Meridian and from the Equator. Each 10' interval shall be shown by a mark on both sides of the graticule line.
- 17.5.4.1 **Recommendation.** The length of the graduation marks should be approximately 1.3 mm (0.05 in) for the 1' intervals, and 2 mm (0.08 in) for the 5' intervals and 2 mm (0.08 in) extending on both sides of the graticule line for the 10' intervals.
- 17.5.5 All meridians and parallels shown shall be numbered in the borders of the chart.
- 17.5.5.1 **Recommendation.** Each meridian and parallel should be numbered within the body of the chart whenever this data is required operationally.
- 17.5.6 The name and basic parameters of the projection shall be indicated in the margin.

17.6 Identification

- 17.6.1 Each sheet shall be identified by a name which should be that of the principal town or of a main geographical feature appearing on the sheet.
- 17.6.1.1 **Recommendation.** Where applicable, sheets should also be identified by the reference number of the corresponding World Aeronautical Chart ICAO 1:1 000 000, with the addition of one or more of the following letter suffixes indicating the quadrant or quadrants:

Letter	Chart quadrant
A	North-West
B	North-East
C	South-East
D	South-West

17.7 Culture and topography

17.7.1 Built-up areas

17.7.1.1 Cities, towns and villages shall be selected and shown according to their relative importance to visual air navigation.

17.7.1.2 **Recommendation.**— Cities and towns of sufficient size should be shown by the outline of their built-up areas and not of their established city limits.

17.7.2 Railroads

- 17.7.2.1 All railroads having landmark value shall be shown.
- Note 1.— In congested areas, some railroads may be omitted in the interest of legibility.
 - Note 2.— Railroads may be named.
 - Note 3.— Rail stations may be shown.
- 17.7.2.2 Tunnels shall be shown when they serve as prominent landmarks.
- Note.— A descriptive note may be added, if necessary, to accentuate this feature.

17.7.3 Highways and roads

- 17.7.3.1 Road systems shall be shown in sufficient detail to indicate significant patterns from the air.
 - Note.— Roads under construction may be shown.
- 17.7.3.2 **Recommendation.** Roads should not be shown in built-up areas unless they can be distinguished from the air as definite landmarks.
- Note.— The numbers or names of important highways may be shown.

17.7.4 Landmarks

Recommendation.— Natural and cultural landmarks, such as bridges, mine structures, lookout towers, forts, ruins, levees, pipelines, prominent transmission lines, permanent cable car installations, and rocks, bluffs, cliffs, sand dunes, isolated lighthouses, lightships, etc., when considered to be of importance for visual air navigation, should be shown.

Note.— Descriptive notes may be added.

17.7.5 Political boundaries

International boundaries shall be shown. Undemarcated or undefined boundaries shall be distinguished by descriptive notes.

Note.— Other boundaries may be shown.

1/11/01 17-2

17.7.6 Hydrography

- 17.7.6.1 All water features compatible with the scale of the chart comprising shore lines, lakes, rivers and streams (including those non-perennial in nature), salt lakes, glaciers and ice caps shall be shown.
- 17.7.6.2 **Recommendation.** The tint covering large open water areas should be kept very light.
- Note.— A narrow band of darker tone may be used along the shore line to emphasize this feature.
- 17.7.6.3 **Recommendation.** Reefs and shoals, including rocky ledges, tidal flats, isolated rocks, sand, gravel, stone and all similar areas should be shown by symbols when of significant landmark value.
- Note.— Groups of rocks may be shown by a few representative rock symbols within the area.

17.7.7 Contours

- 17.7.7.1 Contours shall be shown. The selection of intervals shall be governed by the requirement to depict clearly the relief features required in air navigation.
 - 17.7.7.2 The values of the contours used shall be shown.

17.7.8 Hypsometric tints

- 17.7.8.1 When hypsometric tints are used, the range of elevations for the tints shall be shown.
- 17.7.8.2 The scale of the hypsometric tints used on the chart shall be shown in the margin.

17.7.9 Spot elevations

- 17.7.9.1 Spot elevations shall be shown at selected critical points. The elevation selected shall always be the highest in the immediate vicinity and shall generally indicate the top of a peak, ridge, etc. Elevations in valleys and at lake surface levels which are of navigational value shall be shown. The position of each selected elevation shall be indicated by a dot.
- 17.7.9.2 The elevation (in metres or feet) of the highest point on the chart and its geographical position to the nearest five minutes shall be indicated in the margin.
- 17.7.9.3 **Recommendation.** The spot elevation of the highest point on any sheet should be cleared of hypsometric tinting.

17.7.10 Incomplete or unreliable relief

- 17.7.10.1 Areas that have not been surveyed for contour information shall be labelled "Relief data incomplete".
- 17.7.10.2 Charts on which spot elevations are generally unreliable shall bear a warning note prominently displayed on the face of the chart in the colour used for aeronautical information, as follows:
 - "Warning The reliability of relief information on this chart is doubtful and elevations should be used with caution."

17.7.11 Escarpments

Recommendation.— Escarpments should be shown when they are prominent landmarks or when cultural detail is very sparse.

17.7.12 Wooded areas

- 17.7.12.1 **Recommendation.** Wooded areas should be shown.
- Note.— On high latitude charts the approximate extreme northern or southern limits of tree growth may be shown.
- 17.7.12.2 Where shown, the approximate northern or southern limits of tree growth shall be indicated by a dashed black line and shall be appropriately labelled.

17.7.13 Date of topographic information

The date of latest information shown on the topographic base shall be indicated in the margin.

17.8 Magnetic variation

- 17.8.1 Isogonic lines shall be shown.
- 17.8.2 The date of the isogonic information shall be indicated in the margin.

17.9 Aeronautical data

17.9.1 Aeronautical information shall be shown consistent with the use of the chart and the revision cycle.

17-3 1/11/01

17.9.2 Aerodromes

- 17.9.2.1 Land and water aerodromes and heliports shall be shown with their names, to the extent that they do not produce undesirable congestion on the chart, priority being given to those of greatest aeronautical significance.
- 17.9.2.2 The aerodrome elevation, the lighting available, the type of runway surface and the length of the longest runway or channel, shown in abbreviated form for each aerodrome in conformity with the example given in Appendix 2, provided they do not cause undesirable clutter on the chart, shall be indicated.
- 17.9.2.3 Abandoned aerodromes which are still recognizable as aerodromes from the air shall be shown and identified as abandoned.

17.9.3 Obstacles

- 17.9.3.1 Significant obstacles shall be shown.
- Note.— Obstacles of a height of 100 m (300 ft) or more above ground are normally regarded as significant obstacles.
- 17.9.3.2 When considered of importance to visual flight, prominent transmission lines and permanent cable car installations, which are significant obstacles, shall be shown.
 - 17.9.4 Prohibited, restricted and danger areas

Prohibited, restricted and danger areas shall be shown.

17.9.5 Air traffic services system

17.9.5.1 Significant elements of the air traffic services system including, where practicable, control zones, aerodrome

traffic zones, control areas, flight information regions and other airspaces in which VFR flights operate shall be shown together with the appropriate class of airspace.

17.9.5.2 Where appropriate, the air defence identification zone (ADIZ) shall be shown and properly identified.

Note.— ADIZ procedures may be described in the chart legend.

17.9.6 Radio navigation aids

Radio navigation aids shall be shown by the appropriate symbol and named, but excluding their frequencies, coded designators, times of operation and other characteristics unless any or all of this information which is shown is kept up to date by means of new editions of the chart.

17.9.7 Supplementary information

- 17.9.7.1 Aeronautical ground lights together with their characteristics or their identifications or both shall be shown.
- 17.9.7.2 Marine lights on outer prominent coastal or isolated features of not less than 28 km (15 NM) visibility range shall be shown:
 - 1) where they are not less distinguishable than more powerful marine lights in the vicinity;
 - 2) where they are readily distinguishable from other marine or other types of lights in the vicinity of built-up coastal areas:
 - 3) where they are the only lights of significance available.

1/11/01 17-4

CHAPTER 18. AERONAUTICAL NAVIGATION CHART — ICAO SMALL SCALE

18.1 Function

This chart shall:

- 1) serve as an air navigation aid for flight crews of long range aircraft at high altitudes;
- provide selective checkpoints over extensive ranges for identification at high altitudes and speeds, which are required for visual confirmation of position;
- provide for continuous visual reference to the ground during long range flights over areas lacking radio or other electronic navigation aids, or over areas where visual navigation is preferred or becomes necessary;
- 4) provide a general purpose chart series for long range flight planning and plotting.

18.2 Availability

Recommendation.— The Aeronautical Navigation Chart—ICAO Small Scale should be made available in the manner prescribed in 1.3.2 for all areas delineated in Appendix 5.

Note.— The selection of this scale as an alternative to the World Aeronautical Chart — ICAO 1:1 000 000 is covered by 16.2.1 and 16.2.2.

18.3 Coverage and scale

- 18.3.1 **Recommendation.** The Aeronautical Navigation Chart ICAO Small Scale should provide, as a minimum, complete coverage of the major land masses of the world.
- Note 1.— A sheet layout for this series is contained in the Aeronautical Chart Manual (Doc 8697).
- Note 2.— The sheet size may represent the maximum press size available to the producing agency.
- 18.3.2 The scale shall be in the range of 1:2 000 000 to 1:5 000 000.
- 18.3.3 The scale of the chart shall be substituted in the title for the words "Small Scale".

- 18.3.4 Linear scales for kilometres and nautical miles arranged in the following order:
 - kilometres,
 - nautical miles,

with their zero points in the same vertical line shall be shown in the margin.

- 18.3.5 **Recommendation.** The length of the linear scale should be not less than 200 mm (8 in).
- 18.3.6 A conversion scale (metres/feet) shall be shown in the margin.

18.4 Format

- 18.4.1 The title and marginal notes shall be in one of the working languages of ICAO.
- Note.— The language of the publishing country or any other language may be used in addition to the ICAO working language.
- 18.4.2 The information regarding the number of the adjoining sheets and the unit of measurement to express elevations shall be so located as to be clearly visible when the sheet is folded.
- Note.— There is no internationally agreed sheet numbering.

18.5 Projection

- 18.5.1 A conformal (orthomorphic) projection shall be used.
- 18.5.1.1 The name and basic parameters of the projection shall be shown in the margin.
 - 18.5.2 Parallels shall be shown at intervals of 1°.
- 18.5.2.1 Graduations on the parallels shall be shown at sufficiently close intervals compatible with the latitude and the scale of the chart.
- 18.5.3 Meridians shall be shown at intervals compatible with the latitude and the scale of the chart.

- 18.5.3.1 Graduations on the meridians shall be shown at intervals not exceeding 5'.
- 18.5.4 The graduation marks shall extend away from the Greenwich Meridian and from the Equator.
- 18.5.5 All meridians and parallels shown shall be numbered in the borders of the chart. In addition, when required, meridians and parallels shall be numbered within the body of the chart in such a manner that they can be readily identified when the chart is folded.

18.6 Culture and topography

18.6.1 Built-up areas

- 18.6.1.1 Cities, towns and villages shall be selected and shown according to their relative importance to visual air navigation.
- 18.6.1.2 **Recommendation.** Cities and towns of sufficient size should be indicated by the outline of their built-up areas and not of their established city limits.

18.6.2 Railroads

- 18.6.2.1 All railroads having landmark value shall be shown.
- Note.— In congested areas, some railroads may be omitted in the interest of legibility.
- 18.6.2.2 **Recommendation.** *Important tunnels should be shown.*
 - Note.— A descriptive note may be added.

18.6.3 Highways and roads

- 18.6.3.1 Road systems shall be shown in sufficient detail to indicate significant patterns from the air.
- 18.6.3.2 **Recommendation.** Roads should not be shown in built-up areas unless they can be distinguished from the air as definite landmarks.

18.6.4 Landmarks

Recommendation.— Natural and cultural landmarks, such as bridges, prominent transmission lines, permanent cable car installations, mine structures, forts, ruins, levees, pipelines and rocks, bluffs, cliffs, sand dunes, isolated

lighthouses, lightships, etc., when considered to be of importance for visual air navigation, should be shown.

Note.— Descriptive notes may be added.

18.6.5 Political boundaries

International boundaries shall be shown. Undemarcated and undefined boundaries shall be distinguished by descriptive notes.

18.6.6 Hydrography

- 18.6.6.1 All water features compatible with the scale of the chart comprising shore lines, lakes, rivers and streams (including those non-perennial in nature), salt lakes, glaciers and ice caps shall be shown.
- 18.6.6.2 **Recommendation.** The tint covering large open water areas should be kept very light.
- Note.— A narrow band of darker tone may be used along the shore line to emphasize this feature.
- 18.6.6.3 **Recommendation.** Reefs and shoals including rocky ledges, tidal flats, isolated rocks, sand, gravel, stone and all similar areas should be shown by a symbol when of significant landmark value.

18.6.7 Contours

- 18.6.7.1 Contours shall be shown. The selection of intervals shall be governed by the requirement to depict clearly the relief features required in air navigation.
 - 18.6.7.2 The values of the contours used shall be shown.

18.6.8 Hypsometric tints

- 18.6.8.1 When hypsometric tints are used the range of elevations for the tints shall be shown.
- 18.6.8.2 The scale of the hypsometric tints used on the chart shall be shown in the margin.

18.6.9 Spot elevations

18.6.9.1 Spot elevations shall be shown at selected critical points. The elevations selected shall always be the highest in the immediate vicinity, and shall generally indicate the top of a peak, ridge, etc. Elevations in valleys and at lake surface levels which are of value to visual air navigation shall be shown. The position of each selected elevation shall be indicated by a dot.

1/11/01 18-2

- 18.6.9.2 The elevation (in metres or feet) of the highest point on the chart and its geographical position to the nearest five minutes shall be indicated in the margin.
- 18.6.9.3 **Recommendation.** The spot elevation of the highest point in any sheet should be cleared of hypsometric tinting.

18.6.10 Incomplete or unreliable relief

- 18.6.10.1 Areas that have not been surveyed for contour information shall be labelled "Relief data incomplete".
- 18.6.10.2 Charts on which spot elevations are generally unreliable shall bear a warning note prominently displayed on the face of the chart in the colour used for aeronautical information, as follows:

"Warning — The reliability of relief information on this chart is doubtful and elevations should be used with caution."

18.6.11 Escarpments

Recommendation.— Escarpments should be shown when they are prominent landmarks or when cultural detail is very sparse.

18.6.12 Wooded areas

Recommendation.— Wooded areas of large extent should be shown.

18.6.13 Date of topographic information

The date of latest information shown on the topographic base shall be indicated in the margin.

18.6.14 Colours

- 18.6.14.1 **Recommendation.** Subdued colours should be used for the chart background to facilitate plotting.
- 18.6.14.2 **Recommendation.** Good colour contrast should be ensured to emphasize features important to visual air navigation.

18.7 Magnetic variation

- 18.7.1 Isogonic lines shall be shown.
- 18.7.2 The date of isogonic information shall be indicated in the margin.

18.8 Aeronautical data

18.8.1 Aerodromes

Land and water aerodromes and heliports shall be shown with their names, to the extent that they do not produce undesirable congestion on the chart, priority being given to those of greatest aeronautical significance.

18.8.2 Obstacles

Significant obstacles shall be shown.

18.8.3 Prohibited, restricted and danger areas

Recommendation.— Prohibited, restricted and danger areas should be shown when considered to be of importance to air navigation.

18.8.4 Air traffic services system

- 18.8.4.1 **Recommendation.** Significant elements of the air traffic services system should be shown when considered to be of importance to air navigation.
- 18.8.4.2 **Recommendation.** Where appropriate, the air defence identification zone (ADIZ) should be shown and properly identified.
- Note.— ADIZ procedures may be described in the chart legend.

18.8.5 Radio navigation aids

Note.— Radio aids to navigation may be shown by the appropriate symbol and named.

18-3 1/11/01

CHAPTER 19. PLOTTING CHART — ICAO

19.1 Function

This chart shall provide a means of maintaining a continuous flight record of the aircraft position by various fixing methods and dead reckoning in order to maintain an intended flight path.

19.2 Availability

Recommendation.— This chart should be made available, in the manner prescribed in 1.3.2, to cover major air routes over oceanic areas and sparsely settled areas used by international civil aviation.

Note.— In areas where the Enroute Chart — ICAO is provided there may be no requirement for a plotting chart.

19.3 Coverage and scale

- 19.3.1 **Recommendation.** Where practicable, the chart for a particular region should cover major air routes and their terminals on a single sheet.
- 19.3.2 **Recommendation.** The scale should be governed by the area to be covered.

Note.— Normally the scale will range from 1:3 000 000 to 1:7 500 000.

19.4 Format

Recommendation.— The sheet should be of a size that can be adapted for use on a navigator's plotting table.

19.5 Projection

- 19.5.1 **Recommendation.** A conformal projection on which a straight line approximates a great circle should be used.
 - 19.5.2 Parallels and meridians shall be shown.

- 19.5.2.1 **Recommendation.** The intervals should be arranged to permit accurate plotting to be carried out with a minimum of time and effort.
- 19.5.2.2 Graduation marks shall be shown at consistent intervals along an appropriate number of parallels and meridians. The interval selected shall, regardless of scale, minimize the amount of interpolation required for accurate plotting.
- 19.5.2.3 **Recommendation.** Parallels and meridians should be numbered so that a number appears at least once every 15 cm (6 in) on the face of the chart.
- 19.5.2.4 If a navigational grid is shown on charts covering the higher latitudes, it shall comprise lines parallel to the Meridian or anti-Meridian of Greenwich.

19.6 Identification

Each sheet shall be identified by chart series and number.

19.7 Culture and topography

- 19.7.1 Generalized shore lines of all open water areas, large lakes and rivers shall be shown.
- 19.7.2 Spot elevations for selected features constituting a hazard to air navigation shall be shown.
- 19.7.3 **Recommendation.** Particularly hazardous or prominent relief features should be emphasized.

Note.— Large cities and towns may be shown.

19.8 Magnetic variation

- 19.8.1 Isogonals or, in higher latitudes, isogrivs, or both, shall be shown at consistent intervals throughout the chart. The interval selected shall, regardless of scale, minimize the amount of interpolation required.
- 19.8.2 The date of the isogonic information shall be shown.

19.9 Aeronautical data

- 19.9.1 The following aeronautical data shall be shown:
- 1) aerodromes regularly used by international commercial air transport together with their names;
- selected radio aids to navigation that will contribute to position-finding together with their names and identifications;
- 3) lattices of long-range electronic aids to navigation, as required;

- 4) boundaries of flight information regions, control areas and control zones necessary to the function of the chart;
- 5) designated reporting points necessary to the function of the chart;
- 6) ocean station vessels.

Note.— Other aeronautical data may be shown provided that they do not detract from the legibility of essential information.

19.9.2 **Recommendation.**— Aeronautical ground lights and marine lights useful for air navigation should be shown where other means of navigation are non-existent.

1/11/01 19-2

CHAPTER 20. ELECTRONIC AERONAUTICAL CHART DISPLAY — ICAO

20.1 Function

The Electronic Aeronautical Chart Display — ICAO, with adequate back-up arrangements and in compliance with the requirements of Annex 6 for charts, shall enable flight crews to execute, in a convenient and timely manner, route planning, route monitoring and navigation by displaying required information.

20.2 Information available for display

- 20.2.1 The Electronic Aeronautical Chart Display ICAO shall be capable of displaying all aeronautical, cultural and topographic information required by Annex 4, Chapter 5 and Chapters 7 through 19.
- 20.2.2 **Recommendation.** The Electronic Aeronautical Chart Display ICAO should be capable of displaying all aeronautical, cultural and topographic information recommended by Annex 4, Chapter 5 and Chapters 7 through 19.
- Note.— The Electronic Aeronautical Chart Display ICAO may display supplementary information, in addition to that required for the equivalent paper chart, which may be considered useful for safe navigation.

20.3 Display requirements

20.3.1 Display categories

- 20.3.1.1 Information available for display shall be subdivided into the following categories:
 - a) basic display information, permanently retained on the display and consisting of the minimum information essential for the safe conduct of flight; and
 - b) other display information, which may be removed from the display or displayed individually on demand, and consisting of information not considered essential for the safe conduct of flight.
- 20.3.1.2 It shall be a simple function to add or remove other display information but shall not be possible to remove information contained in the basic display.

20.3.2 Display mode and generation of neighbouring area

20.3.2.1 The Electronic Aeronautical Chart Display — ICAO shall be capable of continuously plotting the aircraft's position in a true motion mode where reset and generation of the surrounding area shall take place automatically.

Note.— Other modes, such as static chart displays, may be available.

20.3.2.2 It shall be possible manually to change the chart area and the position of the aircraft relative to the edge of the display.

20.3.3 Scale

It shall be possible to vary the scale at which a chart is displayed.

20.3.4 Symbols

Symbols used shall conform to those specified for electronic charts in Appendix 2 — ICAO Chart Symbols except where it is desired to show items for which no ICAO chart symbol is provided. In these cases electronic chart symbols shall be chosen which:

- a) employ a minimum use of lines, arcs and area fills;
- b) do not cause confusion with any existing aeronautical chart symbol;
- c) do not impair the legibility of the display.

Note.— Additional details for each symbol may be added according to the resolution of the output media, but any enhancements may not change the basic recognizability of the symbol.

20.3.5 Display hardware

20.3.5.1 The effective size of the chart presentation shall be sufficient to display the information required by 20.2 without excessive scrolling.

- 20.3.5.2 The display shall have the capabilities required to accurately portray required elements of Appendix 2 ICAO Chart Symbols.
- 20.3.5.3 The method of presentation shall ensure that the displayed information is clearly visible to the observer in the conditions of natural and artificial light experienced in the cockpit.
- 20.3.5.4 The display luminance shall be adjustable by the flight crew.

20.4 Provision and updating of data

- 20.4.1 The provision and updating of data for use by the display shall be in conformance with the aeronautical data quality system requirements.
- Note.— For aeronautical data quality system requirements see Chapter 2, 2.17 and Annex 15, Chapter 3, 3.2.
- 20.4.2 The display shall be capable of automatically accepting authorized updates to existing data. A means of ensuring that authorized data and all relevant updates to that data have been correctly loaded into the display shall be provided.
- 20.4.3 The display shall be capable of accepting updates to authorized data entered manually with simple means for verification prior to final acceptance of the data. Updates entered manually shall be distinguishable on the display from authorized data and its authorized updates and shall not affect display legibility.
- 20.4.4 A record shall be kept of all updates, including date and time of application.

20.4.5 The display shall allow the flight crew to display updates so that the flight crew may review the contents of the updates and determine that they have been included in the system.

20.5 Performance tests, malfunction alarms and indications

- 20.5.1 A means shall be provided for carrying out onboard tests of major functions. In case of a failure, the test shall display information to indicate which part of the system is at fault.
- 20.5.2 A suitable alarm or indication of system malfunction shall be provided.

20.6 Back-up arrangements


To ensure safe navigation in case of a failure of the Electronic Aeronautical Chart Display — ICAO, the provision of adequate back-up arrangements shall include:

- a) facilities enabling a safe takeover of display functions in order to ensure that a failure does not result in a critical situation; and
- b) a back-up arrangement facilitating the means for safe navigation of the remaining part of the flight.

Note.— A suitable back-up system may include the carriage of paper charts.

1/11/01 20-2

APPENDIX 1. MARGINAL NOTE LAYOUT



APPENDIX 2. ICAO CHART SYMBOLS

Index	No.	Index	No.
Abandoned canal	30	Clearway — CWY (on Aerodrome	
Advisory airspace — ADA	115	Obstacle Charts)	165
Advisory route — ADR	118	Cliff	4
Aerodromes	84-98	Coast guard station	73
Abandoned or closed	91	Collocated VOR and DME radio navigation aids —	
Civil, land	84	VOR/DME	103,110
Civil, water	85	Collocated VOR and TACAN radio navigation	
Data in abbreviated form	96	aids — VORTAC	107,110
Emergency, or with no facilities	90	Compass rose	110
For Approach Charts	97,98	Contours	1
For use on charts on which aerodrome		Control area — CTA	113
classification is not required	93	Control zone — CTR	116
Joint civil and military, land	88	Controlled route	113
Joint civil and military, water	89	Coral reefs and ledges	22
Military, land	86	Culture	47-83
Military, water	87	Culture, miscellaneous	63-83
Runway pattern in lieu of aerodrome symbol	95	Dam	67
Runway (profile on electronic charts)	169	Danger area	127
Aerodrome/Heliport Charts	142-156	Danger line	43
Aerodrome Obstacle Charts	157-165	Distance measuring equipment — DME	102,110,173,174
Building	159	DME distance	104
Clearway — CWY	165	Dry lake bed	39
Escarpment	163	Dual highway	57
Pole, tower, spire, antenna	158	Electronic chart symbols 100,101,103,107,	108,140,166-174
Railroad	160	Escarpment	4
Stopway — SWY	164	Escarpment (on Aerodrome Obstacle Charts)	163
Terrain penetrating obstacle plane	162	Esker	9
Transmission line or overhead cable	161	Falls	28
Tree or shrub	157	Fence	65
Aerodrome reference point — ARP (on		Ferry	68
Aerodrome/Heliport Charts)	147	Flight information region — FIR	111
Aerodrome traffic zone — ATZ	112	Forest ranger station	76
Aeronautical ground light	140	Fort	79
Air defence identification zone — ADIZ	117	Gas field	70
Air Traffic Services — ATS	111-124	Glaciers	42
Airspace classifications	125-126	Gravel	8
Airspace restrictions	127-128	Hard surface runway (on Aerodrome/Heliport Charts	
Airway — AWY	113	Holding pattern (on electronic charts)	167
Antenna (on Aerodrome Obstacle Charts)	158	Helicopter alighting area on an aerodrome	
Approximate contours	2	(on Aerodrome/Heliport Charts)	146
Areas not surveyed for contour information	18	Heliport	94
ATS/MET reporting point — MRP		Highest elevation on chart	12
(compulsory, on request)	123	Highways	57-62
Basic radio navigation aid	99	Hydrography	19-46
Bluff	4	Ice cap	42
Boundaries (international)	63	Instrument landing system — ILS	108
Boundaries, other	64	International boundary closed to passage of aircraft	
Building (on Aerodrome Obstacle Charts)	159	except through air corridor	128
Buildings	50	Isogonic line or isogonal	137
Built-up areas	47-50	Lakes (non-perennial)	32
Canal	29	Lakes (perennial)	31
Change-over point — COP	122	Landing Direction Indicator (Lighted)	
Charted isolated rock	44	(on Aerodrome/Heliport Charts)	153
Church	80	Landing Direction Indicator (Unlighted)	
City or large town	47	(on Aerodrome/Heliport Charts)	154

Annex 4 — Aeronautical Charts

Appendix 2

Large struction (Aerodrome Obstacle Charts)	Index	No.	Index	No.
Large sturcure (on Aerodrome Obstacle Charts)	Large river (perennial)	23	Rice field	36
Lavya flow	•			
Lave				
Lyene	=			
Lightstip				
Lobout tower				
Marine light Marine 1.79 brithmum sector altitude MSA (on electronic charts) 1.69 brithmum sector altitude MSA (on electronic charts) 1.69 brithmum sector altitude MSA (on electronic charts) 1.66 brithmum sector altitude MSA (on electronic charts) 1.68 brithmum sector altitude MSA (on electronic charts) 1.67 brithmum sector altitude MSA (on electronic charts) 1.68 brithmum sector altitude MSA (on electronic charts) 1.68 brithmum sector altitude MSA (on electronic charts) 1.68 brithmum sector altitude MSA (on electronic charts) 1.33 brithmum sector altitude MSA (on electronic charts) 3.33 brithmum sector altitude MSA (on electronic charts) 3.33 bar (on altitude MSA (on electronic charts) 3.33 bar alta aca altitude (on Acrodrone Charts) 3.54 brithmum sector altitude (on Acrodrone Charts) 3.55 bar (on Acrodrone Charts) 5.55 bar (on Acrodrone Charts) 5.55 bar (on Acrodrone Charts) 1.55 bar (on Acrodrone Charts) 5.55 bar (on Acrodrone Charts)	č i			
Mine Moment Runway-bolding position 156 Miscellaneous symbols — aeronautical 136-138 Runway-bolding position 149 Miscellaneous symbols — culture 63-83 381 take 33 discalagemose ymbols — culture 34 Miscellaneous symbols — culture 168 Sand take 33 Miscellaneous symbols — culture 188 Sand take 34 Moscage 81 Sand dunes 6 Mondrictional radio beacon — NDB 100 Seacheak (on ATS route) 120 Non-directional radio beacon — NDB 120 Secondary road 59 Obstacle light (on Aerodrome/Heliport Charts) 129-135 Shore line (reliable) 141 Elevation of top 133 Shore line (unreliable) 20 Exceptionally high, lighted 133 Shore line (unreliable) 20 Lighted 130 Spire (evention of on Aerodrome Obstacle Charts) 154 Lighted 130 Spire (evention of doubtful accuracy) 134 Lighted group 132 Spot (evention of doubtful accuracy) 134				
Minimum scotor altitude MSA (on electronic charts) 169	Č .			
Miscellameous symbols — aeronautical 13e-138 (on Aerodrome/Heliport Charts) 149 Miscellameous symbols — culture 63-88 Sat I take 33 Miscela approach track (on electronic charts) 168 Salt pans (evaporator) 34 Moscage 81 Sand dunes 6 Mondrictional radio beacon — NDB 100 Secaberal Cereation of Cereation (or ATS route) 26 Obstacle light (no Aerodrome/Heliport Charts) 152 Shore line (reliable) 59 Obstacle light (no Aerodrome/Heliport Charts) 153 Shore line (reliable) 41 Elevation of top 153 Shore line (unreliable) 20 Exceptionally high, lighted 131 Shore line (unreliable) 20 Group 131 Spine (leveraliable) 20 Height 135 Spice elevation 13 Lighted group 132 Spot elevation 13 Ughter boundaries 64 Stop and Accordance (leptor Charts) 15 Oil field 70 Stop bar Stop bar 15 Offered able (on				156
Misselalaneous symbols — culture 63-83 Salt lake 33 Misselalaneous bratek (on electronic charts) 168 Salt pans (vaporator) 34 Mosque 81 Sand area 7 Mosque 81 Sand dunes 67 Non-directional radio beacon — NDB 100 Seale-break (on ATS route) 120 Nucleiar power station 72 Secondary road 59 Obstacles light (on Aerodrome/Heliport Charts) 152 Sholered anchorage 92 Obstacles of Distacles on Totop 135 Shore line (reliable) 19 Exceptionally high, lighted 133 Shore line (unerliable) 20 Exceptionally high, lighted 134 Shrub (on Aerodrome Obstacle Charts) 157 Group 131 Small (river (perennial) 22 Lighted 130 Spric (son Aerodrome Obstacle Charts) 158 Lighted group 132 Spric (wardome Obstacle Charts) 158 Ober active 161 70 Stop bar Oli field 70 Stop bar Stadiu	· · · · · · · · · · · · · · · · · · ·			
Missed approach track (on electronic charts) 168 Salt pans (evaporator) 34 Mosque 81 Sand draces 7 Montaire citorial radio beacon — NDB 100 Sca-bereak (on ATS route) 20 Nuclear power station 72 Scondary road 59 Obstacle Sight (on Aerodrome/Heliport Charts) 125 Scheen line (reliable) 92 Obstacles 129-135 Shoals 41 Esceptionally high 133 Shoals 41 Exceptionally high, lighted 134 Shore line (unreliable) 19 Exceptionally high, lighted 133 Small river (perennial) 24 Height 133 Spire (on Aerodrome Obstacle Charts) 157 Group 131 Small river (perennial) 24 Height 133 Spire (on Aerodrome Obstacle Charts) 16 Obstacle 129 Spire (on Aerodrome Obstacle Charts) 13 Other trees 16 Sport elevation (of doubtful accuracy) 14 Other trees 16 Sport elevation (of doubtful accuracy) </td <td></td> <td></td> <td></td> <td></td>				
Mountain pass		63-83		
Monufaire piase 11		168		34
Non-directional radio beacon — NDB 100 Nuclear power station 72 20 20 20 20 20 20 20	Mosque	81	Sand area	7
Nuclear power station	Mountain pass	11	Sand dunes	6
Obstacles light (on Aerodrome/Heliport Charts) 129-135 Shoelared anchorage 92 Obstacles (Sexpotionally high lighted 133 Shore line (reliable) 19 Exceptionally high, lighted 134 Shore line (urreliable) 20 Exceptionally high, lighted 131 Shore line (urreliable) 20 Exceptionally high, lighted 133 Shore line (urreliable) 20 Fixed group 131 Small river (perennial) 24 Height 130 Spot elevation (of doubtful accuracy) 14 Obstacle 129 Spring (perennial or intermittent) 37 Obstacle 129 Spring (perennial or intermittent) 37 Other broundaries 64 Stopway — SWY (on Aerodrome/Heliport Charts) 155 Other trees 16 Stopway — SWY (on Aerodrome/Heliport Charts) 164 Verbead cable (on Aerodrome/ Beliport Charts) 151 Pagoda Swamp 35 Picagoda 82 TACAN (UHF tactical air navigation aid) 166.1 Picagoda 185 Take farms 71 <	Non-directional radio beacon — NDB	100	Scale-break (on ATS route)	120
Obstacles light (on Acrodrome/Heliport Charts) 129.135 Sheltered anchorage 92 Obstacles of top 1.29.135 Shore line (reliable) 1.9 Exceptionally high 1.33 Shore line (reliable) 1.9 Exceptionally high, lighted 1.34 Shrub (on Acrodrome Obstacle Charts) 1.57 Group 1.31 Sprice (on Acrodrome Obstacle Charts) 1.58 Lighted group 1.32 Spot elevation (of doubtful accuracy) 1.4 Obstacle 1.29 Spring (perennial or intermitten) 3.7 Occan station vessel 1.38 Stadium 7.7 Oli field 70 Stop bar 1.55 Other boundaries 6.4 Stopway — SWY (on Acrodrome/Heliport Charts) 1.44 Obert creased sele (on Acrodrome Obstacle Charts) 1.61 Swamp 3.5 Pagoda 8.2 TACAN (UHF tactical air navigation aid) 106.11 Point light (on Acrodrome/Heliport Charts) 1.51 Tank farms 7.1 Primary road 3.8 Topography 1.18 Probabited area	Nuclear power station	72	Secondary road	59
Obstacles 129-135 Shoals 41 Elevation of top 135 Shore line (reliable) 19 Exceptionally high 133 Shore line (unreliable) 20 Exceptionally high, lighted 134 Shrub (on Aerodrome Obstacle Charts) 157 Group 131 Small river (perennial) 24 Height 135 Spire (on Aerodrome Obstacle Charts) 158 Lighted group 132 Spot elevation (of doubtful accuracy) 14 Obstacle 129 Sport elevation (of doubtful accuracy) 14 Olfer obstacle Charts 138 Stadium 77 Other trees 16 Stop bar Stop bar 155 Other trees 16 Stopway — SWY (on Aerodrome/Heliport Charts) 144 Other trees 16 Stopway — SWY (on Aerodrome/Heliport Charts) 164 Pagoda 22 Stopway — SWY (on Aerodrome/Heliport Charts) 150 Palms 17 Taxik arms 71 Parking areas (on Aerodrome/Heliport Charts) 151 Taxik arms		152	Sheltered anchorage	92
Exceptionally high 133 Shore line (unreliable) 20		129-135		41
Exceptionally high 133 Shore line (unreliable) 20	Elevation of top	135	Shore line (reliable)	19
Skrub (on Aerodrome Obstacle Charts)			, ,	
Group				
Height 135				
Lighted group				
132 Spot elevation (of doubtful accuracy) 14 14 15 15 15 16 16 17 17 18 18 18 18 19 19 19 19				
Obstacle 129 Spring (perennial or intermittent) 37 Ocean station vessel 138 Stadium 77 Oil field 70 Stop bar 155 Other boundaries 64 Stopway — SWY (on Aerodrome/Heliport Charts) 144 Other trees 16 Stopway — SWY (on Aerodrome/Beliport Charts) 164 Overhead cable (on Aerodrome Obstacle Charts) 161 Swamp 35 Pagoda 82 TACAN (UHF tactical air navigation aid) 106,110 Palms 17 Tank farms 71 Parking areas (on Aerodrome/Heliport Charts) 150 Telegraph or telephone line (when a landmark) 66 (on Aerodrome/Heliport Charts) 150 Temple Temple 83 Pipeline 69 Terrain penetrating obstacle plane (on Aerodrome 162 162 Pole (on Aerodrome/Heliport Charts) 151 Obstacle Charts) 162 162 Polinit light (on Aerodrome Obstacle Charts) 158 Tidal flats 21 17 Primary road 58 Toover (on Aerodrome Obstacle Charts)			*	
Ocean station vessel 138 Stadium 77 Oil field 70 Stop bar 155 Other boundaries 64 Stopway — SWY (on Aerodrome/Heliport Charts) 144 Overhead cable (on Aerodrome Obstacle Charts) 161 Stopway — SWY (on Aerodrome Obstacle Charts) 164 Overhead cable (on Aerodrome Obstacle Charts) 161 Swamp 318 161 Stopway — SWY (on Aerodrome Obstacle Charts) 164 164 164 Stopway — SWY (on Aerodrome Obstacle Charts) 164 164 164 Stopway — SWY (on Aerodrome Obstacle Charts) 164 162 164 164 164 162 <				
Oil field 70 Stop bar 155 Other boundaries 64 Stopway — SWY (on Aerodrome/Heliport Charts) 164 Overhead cable (on Aerodrome Obstacle Charts) 161 Stopway — SWY (on Aerodrome/Heliport Charts) 164 Overhead cable (on Aerodrome Obstacle Charts) 161 Swamp 35 Pagoda 82 TACAN (UHF tactical air navigation aid) 106,110 Palms 17 Tank farms 71 Parking areas (on Aerodrome/Heliport Charts) 150 Tank farms 71 Pireced steel plank or steel mesh runway 160 Tank farms 66 Gon Aerodrome/Heliport Charts) 151 Takiways (on Aerodrome/Heliport Charts) 165 Pipeline 69 Terrain penetrating obstacle plane (on Aerodrome Pole (on Aerodrome Obstacle Charts) 162 Pole (on Aerodrome Obstacle Charts) 158 Tidal flats 21 Primary road 58 Topography 1-18 Probibited are 127 Tower (on Aerodrome Obstacle Charts) 161 Radio navigation aid — basic 99,170 Train <td< td=""><td></td><td></td><td></td><td></td></td<>				
Other boundaries 64 Other trees Stopway — SWY (on Aerodrome/Heliport Charts) 144 Other trees Overhead cable (on Aerodrome Obstacle Charts) 161 Stopway — SWY (on Aerodrome Obstacle Charts) 164 Stopway — SWY (on Aerodrome/Heliport Charts) 150 Stopway — SWY (on Aerodrome/Heliport Charts) 35 Stopway — SWY (on Aerodrome Obstacle Charts) 165 Stopway — SWY (on Aerodrome/Heliport Charts) 165 Stopway — SWY (on Aerodrome Obstacle Charts) 165 Stopway — SWY (on Aerodrome/Heliport Charts) 161 Stopway — SWY (on Aerodrome/Heliport Charts) 161 Stopway — SWY (on Aerodrome/Heliport Charts) 161 Stopway — SWY (on Aerodrome Obstacle Charts) 161 Taxiways (on				
Other trees 16 Stopway — SWY (on Aerodrome Obstacle Charts) 164 Overhead cable (on Aerodrome Obstacle Charts) 161 Swamp 35 Pagoda 82 TACAN (UHF tactical air navigation aid) 106,110 Palms 17 Tank farms 71 Parking areas (on Aerodrome/Heliport Charts) 155 Taxiways (on Aerodrome/Heliport Charts) 166 Oo Aerodrome/Heliport Charts) 150 Telegraph or telephone line (when a landmark) 66 Ooint light (on Aerodrome/Heliport Charts) 151 Obstacle Charts) 162 Pole (on Aerodrome Obstacle Charts) 158 Tidal flats 21 Primary road 58 Topography 1-18 Prominent transmission line 136 Town Amalian 48 Race track 77 Trail 60 60 Radio navigation aid basic 99,170 71 72 72 72 72 73 73 73 74 74 74 74 74 74 74 74 74 <t< td=""><td></td><td></td><td></td><td></td></t<>				
Overhead cable (on Aerodrome Obstacle Charts) 161 Swamp 35 Pagoda 82 TACAN (UHF tactical air navigation aid) 106,110 Palms 17 Tank farms 71 Parking areas (on Aerodrome/Heliport Charts) 145 Taxiways (on Aerodrome/Heliport Charts) 145 Pierced steel plank or steel mesh runway 150 Telegraph or telephone line (when a landmark) 66 (on Aerodrome/Heliport Charts) 151 Temple 83 Pipeline 69 Terrain penetrating obstacle plane (on Aerodrome 66 Poli (on Aerodrome Obstacle Charts) 158 Tidal flats 21 Primary road 58 Topography 1-18 Prominent transmission line 136 Town (on Aerodrome Obstacle Charts) 158 Race track 77 Trail Train mission line (on Aerodrome Obstacle Charts) 160 Radio navigation aid — basic 99,170 Train prometrating obstacle Charts) 161 Railroads 910,170-173 Tree (on Aerodrome Obstacle Charts) 15 Railroad 160 Uncon				
Pagoda Palms 82 Palms TACAÑ (UHF tactical air navigation aid) 106,110 Palms 17 Tank farms 71 Parking areas (on Aerodrome/Heliport Charts) 145 Taxiways (on Aerodrome/Heliport Charts) 145 Pierced steel plank or steel mesh runway (on Aerodrome/Heliport Charts) 150 Telegraph or telephone line (when a landmark) 66 Pipeline 69 Terrain penetrating obstacle plane (on Aerodrome 162 Point light (on Aerodrome/Heliport Charts) 158 Terrain penetrating obstacle plane (on Aerodrome Point light (on Aerodrome Obstacle Charts) 158 Tidal flats 21 Primary road 58 Tooyer (on Aerodrome Obstacle Charts) 118 Primary road 136 Town 48 Race track 127 Tower (on Aerodrome Obstacle Charts) 158 Prominent transmission line 136 Town 48 Race track 77 Trail 60 Radio navigation aid — basic 99-110,170-173 17 17 Railroad (on Aerodrome Obstacle Charts) 15 16 16				
Palms 17 Tank farms 71 Parking areas (on Aerodrome/Heliport Charts) 145 Taxiways (on Aerodrome/Heliport Charts) 145 Pieced steel plank or steel mesh runway relegraph or telephone line (when a landmark) 66 (on Aerodrome/Heliport Charts) 150 Temple 83 Pipeline 69 Terrain penetrating obstacle plane (on Aerodrome Point light (on Aerodrome Obstacle Charts) 151 Pole (on Aerodrome Obstacle Charts) 158 Topography 1-18 Primary road 58 Topography 1-18 Prominent transmission line 136 Town (on Aerodrome Obstacle Charts) 158 Prominent transmission line 136 Town (on Aerodrome Obstacle Charts) 158 Race track 77 Trail 60 Radio marker beacon 109,171,172,174 Transmission line (on Aerodrome Obstacle Charts) 161 Railroad on avigation aid — basic 99-110,170-173 Tree, coniferous 15 Railroad (on Aerodrome Obstacle Charts) 160 UHF tactical air navigation aid — TACAN 100,110 Railroad (on Aerodrome Obstacle Charts)	· · · · · · · · · · · · · · · · · · ·			
Parking areas (on Aerodrome/Heliport Charts) Pierced steel plank or steel mesh runway (on Aerodrome/Heliport Charts) Pipeline Point light (on Aerodrome Obstacle Charts) Primary road Primary road Primary road Primary road Prominent transmission line Promone (on Aerodrome Obstacle Charts) Prominent transmission line Promone (on Aerodrome Obstacle Charts) Prominent transmission line Promone (on Aerodrome Obstacle Charts) Promonent evactacle Promonent Promone Obstacle Charts Promonent				,
Pierced steel plank or steel mesh runway (on Aerodrome/Heliport Charts) 150 Pipelime 669 Point light (on Aerodrome/Heliport Charts) 151 Pole (on Aerodrome Obstacle Charts) 158 Primary road 158 Promibited area 127 Prominent transmission line 136 Radio navigation aid — basic 99,170 Radio navigation aids 99-110,170-173 Railroads 83 Station 85		17		71
Con Aerodrome/Heliport Charts 150		145		145
Pipeline69 Point light (on Aerodrome/Heliport Charts)Terrain penetrating obstacle plane (on AerodromePole (on Aerodrome Obstacle Charts)158 TopographyTidal flats21Primary road58 Prohibited area127 TopographyTopography1-18Prominent transmission line136 Race track77 Town48Race track77 Trail60Radio marker beacon109,171,172,174 Transmission line (on Aerodrome Obstacle Charts)161Radio navigation aid — basic99,170 Transmission line (on Aerodrome Obstacle Charts)157Railroads51-56Tree, coniferous15Bridge54 UHF tactical air navigation aid — TACAN106,110 Uncontrolled route114Single track51 StationUnusual land features, appropriately labelled10Tunnel55 Unusual water features, appropriately labelled46Two or more tracks52 VHF omnidirectional radio range — VOR101,110Under construction53 Visual aids139-141Relief data incomplete18 Visual flight path119Relief shown by hachures3 VOR (VHF omnidirectional radio range)101,110Reservoir38 Restricted area127 VOR radialVOR check-point (on Aerodrome/Heliport Charts)148 VOR/DME (collocated VOR and DME radio			Telegraph or telephone line (when a landmark)	66
Point light (on Aerodrome/Heliport Charts) 151 Obstacle Charts) 152 Tidal flats 21	(on Aerodrome/Heliport Charts)	150		83
Pole (on Aerodrome Obstacle Charts) Primary road Primary road Prohibited area Prominent transmission line Race track Race track Race track Radio marker beacon Radio navigation aid — basic Radio navigation aids Railroads Railroad (on Aerodrome Obstacle Charts) Right track Station Single track Station Tunnel Tunnel Tunnel Tunnel Tunnel Two or more tracks Station Sta	Pipeline	69	Terrain penetrating obstacle plane (on Aerodrome	
Primary road 58 Topography 1-18 Probibited area 127 Tower (on Aerodrome Obstacle Charts) 158 Prominent transmission line 136 Town 48 Race track 77 Trail 60 Radio marker beacon 109,171,172,174 Transmission line (on Aerodrome Obstacle Charts) 161 Radio navigation aid — basic 99,170 Tree (on Aerodrome Obstacle Charts) 157 Railroads 99-110,170-173 Tree, onlerous 15 Railroad (on Aerodrome Obstacle Charts) 160 Uncontrolled route 114 Single track 51 Unpaved runway (on Aerodrome/Heliport Charts) 143 Station 56 Unusual land features, appropriately labelled 16 Two or more tracks 52 VHF omnidirectional radio range — VOR 101,110 Under construction 53 Visual aids 139-141 Relief data incomplete 18 Visual flight path 119 Relief shown by hachures 3 VOR (VHF omnidirectional radio range) 101,110 Reservice darea<	Point light (on Aerodrome/Heliport Charts)	151	Obstacle Charts)	162
Prohibited area 127 Tower (on Aerodrome Obstacle Charts) 158 Prominent transmission line 136 Town 488 Race track 77 Trail 60 Radio marker beacon 109,171,172,174 Transmission line (on Aerodrome Obstacle Charts) 161 Radio navigation aid — basic 99,170 Radio navigation aids 99-110,170-173 Tree (on Aerodrome Obstacle Charts) 157 Radio navigation aids 99-110,170-173 Tree, coniferous 15 Railroads 51-56 UHF tactical air navigation aid — TACAN 106,110 Railroad (on Aerodrome Obstacle Charts) 160 Uncontrolled route 114 Single track 51 Unpaved runway (on Aerodrome/Heliport Charts) 143 Station 56 Unusual land features, appropriately labelled 10 Tunnel 55 Unusual water features, appropriately labelled 46 Two or more tracks 52 VHF omnidirectional radio range — VOR 101,110 Rapids 27 Visual aids 139-141 Relief data incomplete 18 Visual flight path 119 Relief shown by hachures 3 VOR (VHF omnidirectional radio range) 101,110 Reporting point — REP (compulsory, on request) 121 Reservoir 38 (on Aerodrome/Heliport Charts) 148 Restricted area 127 VOR radial 105 VOR/DME (collocated VOR and DME radio	Pole (on Aerodrome Obstacle Charts)	158	Tidal flats	21
Prominent transmission line Race track Race	Primary road	58	Topography	1-18
Race track Radio marker beacon Radio marker beacon Radio navigation aid — basic Radio navigation aids Railroads Railroads Railroads Railroad (on Aerodrome Obstacle Charts) Restricted area Railroad (on Aerodrome Obstacle Charts) Restricted airspace (prohibited, restricted or danger Tree (on Aerodrome Obstacle Charts) 106 Tree (on Aerodrome Obstacle Charts) Total Charts Tree (on Aerodrome Obstacle Charts) Total Charts Tree (on Aerodrome Obstacle Charts) Tree (on Aerodrome Obstacle Charts) Tree (on Aerodrome Obstacle Charts) Total Charts Tree (on Aerodrome Obstacle Charts) Total Charts Tree (on Aerodrome Obstacle Charts) Total Charts Total	Prohibited area	127	Tower (on Aerodrome Obstacle Charts)	158
Race track Radio marker beacon Radio marker beacon Radio navigation aid — basic Radio navigation aids Railroads Railroads Railroads Railroad (on Aerodrome Obstacle Charts) Restricted area Railroad (on Aerodrome Obstacle Charts) Restricted airspace (prohibited, restricted or danger Tree (on Aerodrome Obstacle Charts) 106 Tree (on Aerodrome Obstacle Charts) Total Charts Tree (on Aerodrome Obstacle Charts) Total Charts Tree (on Aerodrome Obstacle Charts) Tree (on Aerodrome Obstacle Charts) Tree (on Aerodrome Obstacle Charts) Total Charts Tree (on Aerodrome Obstacle Charts) Total Charts Tree (on Aerodrome Obstacle Charts) Total Charts Total	Prominent transmission line	136	Town	48
Radio navigation aid — basic 99,170 Radio navigation aids 99-110,170-173 Railroads 99-110,170-173 Railroads 51-56 Bridge 54 Railroad (on Aerodrome Obstacle Charts) 160 Railroad (on Aerodrome Obstacle Charts) 160 Single track 51 Unpaved runway (on Aerodrome/Heliport Charts) 143 Station 56 Unusual land features, appropriately labelled 10 Tunnel 55 Unusual water features, appropriately labelled 46 Two or more tracks 52 Under construction 53 Village 49 Rapids 27 Rapids 27 Relief data incomplete 18 Relief data incomplete 18 Relief shown by hachures 8 Reporting point — REP (compulsory, on request) 121 Restricted area 127 Restricted airspace (prohibited, restricted or danger Tree (on Aerodrome Obstacle Charts) 15 Tree, other 16 Under construction aid — TACAN 106,110 Uncontrolled route 10 Uncontrolled route 110 Uncontrolled route 110 Unpaved runway (on Aerodrome/Heliport Charts) 143 Visual aids 100 VOR (VHF omnidirectional radio range) 101,110 VOR check-point (on Aerodrome/Heliport Charts) 148 Restricted airspace (prohibited, restricted or danger 105 VOR/DME (collocated VOR and DME radio			Trail	
Radio navigation aid — basic 99,170 Radio navigation aids 99-110,170-173 Railroads 99-110,170-173 Railroads 51-56 Bridge 54 Railroad (on Aerodrome Obstacle Charts) 160 Railroad (on Aerodrome Obstacle Charts) 160 Single track 51 Unpaved runway (on Aerodrome/Heliport Charts) 143 Station 56 Unusual land features, appropriately labelled 10 Tunnel 55 Unusual water features, appropriately labelled 46 Two or more tracks 52 Under construction 53 Village 49 Rapids 27 Rapids 27 Relief data incomplete 18 Relief data incomplete 18 Relief shown by hachures 29 Reporting point — REP (compulsory, on request) 121 Reservoir Reservoir 38 Restricted area 127 Restricted airspace (prohibited, restricted or danger Tree (on Aerodrome Obstacle Charts) 15 Tree, onfierous 1 Tree, coniferous 1 These, coniferous 1 These, coniferous 1 These, cheer - particular - TACAN 106,110 Tree, other 1 Tree, coher - particular - TACAN 106,110 Tree, other 1 Tree, coher - particular - TACAN 106,110 Tree, other - particular -	Radio marker beacon	109,171,172,174	Transmission line (on Aerodrome Obstacle Charts)	161
Radio navigation aids 99-110,170-173 Tree, coniferous 15 Railroads 51-56 Tree, other 16 Bridge 54 UHF tactical air navigation aid — TACAN 106,110 Railroad (on Aerodrome Obstacle Charts) 160 Uncontrolled route 114 Single track 51 Unpaved runway (on Aerodrome/Heliport Charts) 143 Station 56 Unusual land features, appropriately labelled 10 Tunnel 55 Unusual water features, appropriately labelled 46 Two or more tracks 52 VHF omnidirectional radio range — VOR 101,110 Under construction 53 Village 49 Rapids 27 Visual aids 139-141 Relief shown by hachures 3 VOR (VHF omnidirectional radio range) 101,110 Reporting point — REP (compulsory, on request) 121 VOR check-point Reservoir 38 (on Aerodrome/Heliport Charts) 148 Restricted area 127 VOR radial 105 Restricted airspace (prohibited, restricted or danger	Radio navigation aid — basic		· · · · · · · · · · · · · · · · · · ·	
Railroads51-56Tree, other16Bridge54UHF tactical air navigation aid — TACAN106,110Railroad (on Aerodrome Obstacle Charts)160Uncontrolled route114Single track51Unpaved runway (on Aerodrome/Heliport Charts)143Station56Unusual land features, appropriately labelled10Tunnel55Unusual water features, appropriately labelled46Two or more tracks52VHF omnidirectional radio range — VOR101,110Under construction53Village49Rapids27Visual aids139-141Relief data incomplete18Visual flight path119Relief shown by hachures3VOR (VHF omnidirectional radio range)101,110Reporting point — REP (compulsory, on request)121VOR check-pointReservoir38(on Aerodrome/Heliport Charts)148Restricted area127VOR radial105Restricted airspace (prohibited, restricted or dangerVOR/DME (collocated VOR and DME radio)				
Bridge 54 UHF tactical air navigation aid — TACAN 106,110 Railroad (on Aerodrome Obstacle Charts) 160 Uncontrolled route 114 Single track 51 Unpaved runway (on Aerodrome/Heliport Charts) 143 Station 56 Unusual land features, appropriately labelled 10 Tunnel 55 Unusual water features, appropriately labelled 46 Two or more tracks 52 VHF omnidirectional radio range — VOR 101,110 Under construction 53 Village 49 Rapids 27 Visual aids 139-141 Relief data incomplete 18 Visual flight path 119 Relief shown by hachures 3 VOR (VHF omnidirectional radio range) 101,110 Reporting point — REP (compulsory, on request) 121 VOR check-point Reservoir 38 (on Aerodrome/Heliport Charts) 148 Restricted area 127 VOR radial 105 Restricted airspace (prohibited, restricted or danger				
Railroad (on Aerodrome Obstacle Charts) Single track Single track Station Tunnel Tunnel Two or more tracks Under construction Sapids Relief data incomplete Relief shown by hachures Reporting point — REP (compulsory, on request) Reservoir Reservoir Reservoir Restricted area Restricted airspace (prohibited, restricted or danger 110 Uncontrolled route Uncontrolled route Uncontrolled route Unpaved runway (on Aerodrome/Heliport Charts) 143 Unpaved runway (on Aerodrome/Heliport Charts) 144 Unusual land features, appropriately labelled 46 Unusual water features, appropriately labelled 46 Vinusual water features, appropriately labelled 47 Village Village Village Village Visual aids Village Visual flight path 119 Vor (VHF omnidirectional radio range) 101,110 VOR (VHF omnidirectional radio range) 101,110 VOR check-point Reservoir Reservoir 101,110 VOR check-point VOR radial VOR radial VOR radial VOR and DME radio				
Single track 51 Unpaved runway (on Aerodrome/Heliport Charts) 143 Station 56 Unusual land features, appropriately labelled 10 Tunnel 55 Unusual water features, appropriately labelled 46 Two or more tracks 52 VHF omnidirectional radio range — VOR 101,110 Under construction 53 Village 49 Rapids 27 Visual aids 139-141 Relief data incomplete 18 Visual flight path 119 Relief shown by hachures 3 VOR (VHF omnidirectional radio range) 101,110 Reporting point — REP (compulsory, on request) 121 VOR check-point Reservoir 38 (on Aerodrome/Heliport Charts) 148 Restricted area 127 VOR radial 105 Restricted airspace (prohibited, restricted or danger VOR/DME (collocated VOR and DME radio	<u> </u>			
Station 56 Unusual land features, appropriately labelled 10 Tunnel 55 Unusual water features, appropriately labelled 46 Two or more tracks 52 VHF omnidirectional radio range — VOR 101,110 Under construction 53 Village 49 Rapids 27 Visual aids 139-141 Relief data incomplete 18 Visual flight path 119 Relief shown by hachures 3 VOR (VHF omnidirectional radio range) 101,110 Reporting point — REP (compulsory, on request) 121 VOR check-point Reservoir 38 (on Aerodrome/Heliport Charts) 148 Restricted area 127 VOR radial 105 Restricted airspace (prohibited, restricted or danger VOR/DME (collocated VOR and DME radio	,			
Tunnel 55 Unusual water features, appropriately labelled 46 Two or more tracks 52 VHF omnidirectional radio range — VOR 101,110 Under construction 53 Village 49 Rapids 27 Visual aids 139-141 Relief data incomplete 18 Visual flight path 119 Relief shown by hachures 3 VOR (VHF omnidirectional radio range) 101,110 Reporting point — REP (compulsory, on request) 121 VOR check-point Reservoir 38 (on Aerodrome/Heliport Charts) 148 Restricted area 127 VOR radial 105 Restricted airspace (prohibited, restricted or danger VOR/DME (collocated VOR and DME radio	•			
Two or more tracks Under construction 52 VHF omnidirectional radio range — VOR Village 49 Rapids 27 Visual aids 139-141 Relief data incomplete 18 Visual flight path 119 Relief shown by hachures 3 VOR (VHF omnidirectional radio range) 101,110 Reporting point — REP (compulsory, on request) 121 VOR check-point Reservoir Reservoir 38 (on Aerodrome/Heliport Charts) 148 Restricted area 127 VOR radial 105 Restricted airspace (prohibited, restricted or danger VOR/DME (collocated VOR and DME radio				
Under construction53Village49Rapids27Visual aids139-141Relief data incomplete18Visual flight path119Relief shown by hachures3VOR (VHF omnidirectional radio range)101,110Reporting point — REP (compulsory, on request)121VOR check-pointReservoir38(on Aerodrome/Heliport Charts)148Restricted area127VOR radial105Restricted airspace (prohibited, restricted or dangerVOR/DME (collocated VOR and DME radio)				
Rapids 27 Visual aids 139-141 Relief data incomplete 18 Visual flight path 119 Relief shown by hachures 3 VOR (VHF omnidirectional radio range) 101,110 Reporting point — REP (compulsory, on request) 121 VOR check-point Reservoir 38 (on Aerodrome/Heliport Charts) 148 Restricted area 127 VOR radial 105 Restricted airspace (prohibited, restricted or danger VOR/DME (collocated VOR and DME radio			<u> </u>	
Relief data incomplete Relief shown by hachures Reporting point — REP (compulsory, on request) Reservoir Reservoir Restricted area Restricted airspace (prohibited, restricted or danger 18 Visual flight path VOR (VHF omnidirectional radio range) 101,110 VOR check-point (on Aerodrome/Heliport Charts) 148 VOR radial 105 VOR/DME (collocated VOR and DME radio			~	
Relief shown by hachures 3 VOR (VHF omnidirectional radio range) 101,110 Reporting point — REP (compulsory, on request) 121 VOR check-point Reservoir 38 (on Aerodrome/Heliport Charts) 148 Restricted area 127 VOR radial 105 Restricted airspace (prohibited, restricted or danger VOR/DME (collocated VOR and DME radio				
Reporting point — REP (compulsory, on request) Reservoir Restricted area Restricted airspace (prohibited, restricted or danger 121 VOR check-point (on Aerodrome/Heliport Charts) 148 VOR radial 105 VOR/DME (collocated VOR and DME radio				
Reservoir38(on Aerodrome/Heliport Charts)148Restricted area127VOR radial105Restricted airspace (prohibited, restricted or dangerVOR/DME (collocated VOR and DME radio				101,110
Restricted area 127 VOR radial 105 Restricted airspace (prohibited, restricted or danger VOR/DME (collocated VOR and DME radio				1.40
Restricted airspace (prohibited, restricted or danger VOR/DME (collocated VOR and DME radio			*	
		127		105
area) and common boundary of two areas 127 navigation aids) 103,110			· ·	100 11-
	area) and common boundary of two areas	127	navigation aids)	103,110

1/11/01 APP 2-2

Index	No.	Index	No.
VORTAC (collocated VOR and TACAN radio	İ		
navigation aids)	107,110		
Wash	40		
Water hole (perennial or intermittent)	37	I	
Waypoint — WPT	124	I	
Well (perennial or intermittent)	37		

APP 2-3 1/11/01

THIS PAGE INTENTIONALLY LEFT BLANK

1/11/01 APP 2-4

TOPOGRAPHY

1	Contours	5000
2	Approximate contours	1 25500-
3	Relief shown by hachures	William William
4		
4	Bluff, cliff or escarpment	, manual transfer of the same
5	Bluff, cliff or escarpment Lava flow	

			•
8	Gravel		
٥	ative		444444666644444 PYYYYYY
9	9 Levee or esker	Alternative	PPFFFFFF
10	Unusual land features appropriately labelled		
	Active volcano	ı	<u> </u>
11	Mountain pass).(5395

12	Highest elevation on		17456
12	chart	Alternative	.17456
13	Spot elevation		.6397 .8975
14	Spot elevation (of doubtful accuracy)		.6370±
15	Coniferous trees		_ *
16	Other trees		
17	Palms		7 7 7 7 7 7

18 Areas not surveyed for contour information or relief data incomplete

Caution

HYDROGRAPHY

19	Shore line (reliable)		~~
20	Shore line (unreliable)	Shore line (unreliable)	
21	Tidal flats		e de la companya de
22	Coral reefs and ledges	Coral reefs and ledges	
23	Large river (perennial)		AND
24	Small river (perennial)		~~
25	Rivers and streams (non-perennial)	Alternative	
26	Rivers and streams (unsurveyed)		
27	Rapids		
28	Falls		
29	Canal		

30	Abandoned canal Note.— Dry canal having landmark value.			
31	Lakes (perennial)			
32	Lakes (non-perennial)			
			Alte	
33	Salt lake			
34	Salt pans (evaporator)			
35	Swamp		- 717	
36	Rice field Alternative			
37	perennia Spring, well or		nial	•
31	water hole	intermitter		0

38	38 Reservoir		Reservoir
39	Dry lake bed	Alternative	0
40	Wash	Alternative	
41	41 Shoals		
42	Glaciers and ice caps		
43	Danger line (2 m or one fathom line)		•
44	44 Charted isolated rock		+
45	45 Rock awash		:
46	46 Unusual water features appropriately labelled		(Covered Reef)

APP 2-5 1/11/01

CULTURE

BUILT-UP AREAS

47	City or large town	
48	Town	0
49	Village	0
50	Buildings	= I

HIGHWAYS AND ROADS

57	Dual highway	=====
58	Primary road	
59	Secondary road	
60	Trail	
61	Road bridge	
62	Road tunnel	→←

MISCELLANEOUS (Cont.)

69	Pipeline	Pipeline
70	Oil or gas field	lack
71	Tank farms	••••
72	Nuclear power station	*
73	Coast guard station	*
74	Lookout tower	(A)
75	Mine	*
76	Forest ranger station	±
77	Race track or stadium	
78	Ruins	••
79	Fort	Д
80	Church	t
81	Mosque	ð
82	Pagoda	\$
83	Temple	血

RAILROADS

51	Railroad (single track)	
52	Railroad (two or more tracks)	###
53	Railroad (under construction)	
54	Railroad bridge	
55	Railroad tunnel) (
56	Railroad station	+ = + +

MISCELLANEOUS

63	Boundaries (international)	
64	Outer boundaries	
65	Fence	x-x-x
66	Telegraph or telephone line (when a landmark)	-тт-
67	Dam	
68	Ferry	J0/


AERODROMES

0.4	Civil		\triangle
84	CIVII	Land	Y
85	Civil	Water	4
86	Military	Land	
87	Military	Water	

88	Joint civil and military Land	\rightarrow
89	Joint civil and military Water	
90	Emergency aerodrome or aerodrome with no facilities	0
91	Abandoned or closed aerodrome	\otimes

92	Sheltered anchorage	Ĵ
93	Aerodrome for use on charts on which aerodrome classification is not required e.g. Enroute Charts	Φ
94	Heliport Note.— Aerodrome for the exclusive use of helicopters	H


Note.— Where required by the function of the chart, the runway pattern of the aerodrome may be shown in lieu of the aerodrome symbol, for example:



1/11/01 APP 2-6

AERODROMES (Cont.) AERODROME DATA IN ABBREVIATED FORM WHICH MAY BE IN ASSOCIATION WITH AERODROME SYMBOLS

(Reference: 16.9.2.2 and 17.9.2.2)



AERODROME SYMBOLS FOR APPROACH CHARTS

Aerodromes affecting the traffic pattern on 97 the aerodrome on which the procedure is based




The aerodrome on which the 98 procedure is based



RADIO NAVIGATION AIDS*

99	Basic radio navigation aid symbol Note.— This symbol may be used with or without a box to enclose the data.		o		
100	Non-directional radio bea	acon	NDB	0	Electronic
101	VHF omnidirectional radi	io range	VOR	\odot	
102	Distance measuring equi	pment	DME	·	
103	Collocated VOR and DM radio navigation aids	collocated VOR and DME VOR/DME radio navigation aids		\bigcirc	
104	DME distance		Distance in kilometre (nautical miles) to DMi Identification o radio navigation ai		15 km K A V
105	VOR radial	Radial bearing from, and identification of, VOR R_090_KAV_		00_KAV	
106	UHF tactical air navigatio	navigation aid TACAN		7	?



Compass rose To be orientated on the chart in 110 accordance with the alignment of the station (normally Magnetic North)




Compass rose to be used as appropriate in combination with the following symbols:


 \odot VOR VOR/DME $\langle \cdot \rangle$ $\langle \gamma \rangle$ TACAN VORTAC \Diamond

* Note.— Guidance material on the presentation of radio navigation aid data is given in the Aeronautical Chart Manual (Doc 8697).

AIR TRAFFIC SERVICES



AIRSPACE CLASSIFICATIONS



AIRSPACE RESTRICTIONS

127			Common boundary of two areas	
	Note.— The angle and density of rulings may be varied according to the second s	ording to scale and the size, shape and orientation of the a	area.	
128	International boundary closed to passage of aircraft	except through air corridor		

1/11/01 APP 2-8

OBSTACLES


129	Obstacle	\wedge	1	133	Ex
130	Lighted obstacle	**	1	134	Ex
131	Group obstacles	\\(\lambda\)	-		No
132	Lighted group obstacles	<u></u>	1	35	

133	Exceptionally high obstacle (optional symbol)	<u>k</u>
134	Exceptionally high obstacle — lighted (optional symbol) Note.— For obstacles having a height of the order of 300 m (1 000 ft) above terrain	*
135	Elevation of top (italics) Height above specified datum (upright type in parentheses)	

MISCELLANEOUS

136	Prominent transmission line	~~~T~~~~T~~~	137	Isogonic line or isogonal	3° E	138	Ocean station vessel (normal position)	
-----	-----------------------------	--------------	-----	---------------------------	------	-----	--	--

VISUAL AIDS



SYMBOLS FOR AERODROME/HELIPORT CHARTS

142	Hard surface runway	
143	Unpaved runway	
144	Stopway SWY	
145	Taxiways and parking areas	
146	Helicopter alighting area on an aerodrome	H
147	Aerodrome reference point	+
148	VOR check-point	< ⊕
149	Runway visual range (RVR) observation site	\triangleright

150	Pierced steel plank or steel mesh run	way	
151	Point light		•
	· ·		0
152	Obstacle light		岩
153	Landing direction indicator (lighted)		T
154	Landing direction indicator (unlighted)	Т
155	Stop bar		•••
	Runway-holding	Pattern A	===
156	position	Pattern B	IIII
	Note.— For application, see Annex 14, Vol.	ume I, paragraph 5.2.9	

SYMBOLS FOR AERODROME OBSTACLE CHARTS — TYPE A, B AND C

		Plan	Profile
157	Tree or shrub	*	Identification
158	Pole, tower, spire, antenna, etc.	0	number
159	Building or large structure	-	1
160	Railroad	+	'
161	Transmission line or overhead cable	-тт-	

			Plan	Profile
162	Terrain penetrating ob	stacle plane		
163	Escarpment		*******	******
164	Stopway	SWY]	- :
165	Clearway	CWY	J	

APP 2-9 1/11/01

ADDITIONAL SYMBOLS FOR USE ON ELECTRONIC CHARTS

	PLAN VIEW	Electronic
166	Minimum sector altitude Note.— This symbol may be modified to reflect particular sector shapes MSA	090° 10,500′ 8100′ 2270 MSA OED VOR
167	Holding pattern	
168	Missed approach track	>
	PROFILE	Electronic
169	Runway	
170	Radio navigation aid (type of aid and its use in the procedure to be annotated on top of the symbol)	
171	Radio marker beacon (type of beacon to be annotated on top of the symbol)	
172	Collocated radio navigation aid and marker beacon (type of aid to be annotated on top of the symbol)	
173	DME fix (distance from DME and the fix use in the procedure to be annotated on top of the symbol)	
174	Collocated DME fix and marker beacon (distance from DME and the type of beacon to be annotated on top of the symbol)	

1/11/01 APP 2-10

APPENDIX 3. COLOUR GUIDE

(Ref. 2.11.1)


CHART SYMBOLS

CHART SY	IVIDOLO		
Culture, except highways and roads; outlines of large cities, grids and graticul spot elevations; danger lines and off-shore rocks; names and lettering excepaeronautical and hydrographic features	es; ot for	BLACK	
Built-up areas of cities		BLACK Stipple	
Highways and roads	Optional	BLACK Half-tone	
riigiiways anu ioaus	colours	RED	
Built-up areas for cities (alternative to black stipple)		YELLOW	
Contours and topographic features: Items 1 through 10 of Appendix 2. Hydrographic features: Items 39 through 41 of Appendix 2		BROWN	
Shore lines, drainage, rivers, lakes, bathymetric contours and other hydrograph including their names or description	ic features	BLUE	
Open water areas		BLUE Half-tone	
Salt lakes and salt pans		BLUE Stipple	
Large non-perennial rivers and non-perennial lakes		BLUE Stipple	
Aeronautical data, except for Enroute and Area Charts - ICAO, where different colours may be required. Both colours may be used on the same sheet	Optional	MAGENTA	
but, where only one colour is used, dark blue is preferred	colours	DARK BLUE	

CHART SYMBOLS (Cont.)


Woods	2	GREEN	
	,	GOLDEN BUFF	
Areas which have not been surveyed for contour information or relief data are incomplete	Optional colours	WHITE	

HYPSOMETRIC TINTS




APPENDIX 4. HYPSOMETRIC TINT GUIDE

(Alternative systems, reference 2.12.2)



Note 2.— Elevations have not been associated with tints of either system in order to allow for flexibility in their selection.



APPENDIX 6. AERONAUTICAL DATA QUALITY REQUIREMENTS

Table 1. Latitude and longitude

Latitude and longitude	Chart Resolution	Integrity Classification
Flight information region boundary points	as plotted	1×10^{-3} routine
P, R, D areas boundary points (outside CTA/CTZ boundaries)	as plotted	1×10^{-3} routine
P, R, D areas boundary points (inside CTA/CTZ boundary)	as plotted	1×10^{-5} essential
CTA/CTZ boundary points	as plotted	1×10^{-5} essential
En-route navaids and fixes, holding, STAR/SID points	1 sec	1×10^{-5} essential
Obstacles en-route	as plotted	1×10^{-3} routine
Aerodrome/heliport reference point	1 sec	1×10^{-3} routine
Navaids located at the aerodrome/heliport	as plotted	1×10^{-5} essential
Obstacles in the circling area and at the aerodrome/heliport	1/10 sec (AOC Type C)	1×10^{-5} essential
Significant obstacles in the approach and take-off area	1/10 sec (AOC Type C)	1×10^{-5} essential
Final approach fixes/points and other essential fixes/points comprising instrument approach procedure	1 sec	1×10^{-5} essential
Runway thresholds	1 sec	1×10^{-8} critical
Taxiway centre line points	1/100 sec	1×10^{-5} essential
Aircraft stand points/INS checkpoints	1/100 sec	1×10^{-3} routine
Geometric centre of TLOF or FATO thresholds, heliports	1 sec	1×10^{-8} critical

Annex 4 — Aeronautical Charts

Appendix 6

Table 2. Elevation/altitude/height

Elevation/altitude/height	Chart Resolution	Integrity Classification
Aerodrome/heliport elevation	1 m or 1 ft	1 × 10 ⁻⁵ essential
WGS-84 geoid undulation at aerodrome/heliport elevation position	1 m or 1 ft	1×10^{-5} essential
Runway or FATO threshold, non-precision approaches	1 m or 1 ft	1 × 10 ⁻⁵ essential
WGS-84 geoid undulation at runway or FATO threshold, TLOF geometric centre, non-precision approaches	1 m or 1 ft	1×10^{-5} essential
Runway or FATO threshold, precision approaches	0.5 m or 1 ft	1 × 10 ⁻⁸ critical
WGS-84 geoid undulation at runway or FATO threshold, TLOF geometric centre, precision approaches	0.5 m or 1 ft	1×10^{-8} critical
Threshold crossing height, precision approaches	0.5 m or 1 ft	1×10^{-8} critical
Obstacle Clearance Altitude/Height (OCA/H)	as specified in PANS-OPS (Doc 8168)	1×10^{-5} essential
Obstacles en-route	3 m (10 ft)	1×10^{-3} routine
Obstacles in the approach and take-off areas	1 m or 1 ft	1×10^{-5} essential
Obstacles in the circling areas and at the aerodrome/heliport	1 m or 1 ft	1×10^{-5} essential
Distance measuring equipment (DME)	30 m (100 ft)	1×10^{-5} essential
Instrument approach procedures altitude	as specified in PANS-OPS (Doc 8168)	1×10^{-5} essential
Minimum altitudes	50 m or 100 ft	1×10^{-3} routine

1/11/01 APP 6-2

Table 3. Magnetic variation

Magnetic variation	Chart Resolution	Integrity Classification
Aerodrome/heliport magnetic variation	1 degree	1×10^{-5} essential

Table 4. Bearing

Bearing	Chart Resolution	Integrity Classification
Airway segments	1 degree	1 × 10 ⁻³ routine
En-route and terminal fix formations	1/10 degree	1×10^{-3} routine
Terminal arrival/departure route segments	1 degree	1×10^{-3} routine
Instrument approach procedure fix formations	1/10 degree	1×10^{-5} essential
ILS localizer alignment	1 degree	1×10^{-5} essential
MLS zero azimuth alignment	1 degree	1×10^{-5} essential
Runway and FATO bearing	1 degree	1×10^{-3} routine

APP 6-3 1/11/01

Table 5. Length/distance/dimension

Length/distance/dimension	Chart Resolution	Integrity Classification
Airway segments length	1 km or 1 NM	1×10^{-3} routine
En-route fix formations distance	2/10 km (1/10 NM)	1×10^{-3} routine
Terminal arrival/departure route segments length	1 km or 1 NM	1×10^{-5} essential
Terminal and instrument approach procedure fix formations distance	2/10 km (1/10 NM)	1×10^{-5} essential
Runway and FATO length, TLOF dimensions	1 m (AD chart) 0.5 m (AOC chart)	1×10^{-8} critical
Stopway length	0.5 m (AOC chart)	1×10^{-8} critical
Landing distance available	1 m (AD chart) 0.5 m (AOC chart)	1×10^{-8} critical
ILS localizer antenna-runway end, distance	as plotted	1×10^{-3} routine
ILS glide slope antenna-threshold, distance along centre line	as plotted	1×10^{-3} routine
ILS markers-threshold distance	2/10 km (1/10 NM)	1×10^{-5} essential
ILS DME antenna-threshold, distance along centre line	as plotted	1×10^{-5} essential
MLS azimuth antenna-runway end, distance	as plotted	1×10^{-3} routine
MLS elevation antenna-threshold, distance along centre line.	as plotted	1×10^{-3} routine
MLS DME/P antenna-threshold, distance along centre line.	as plotted	1×10^{-5} essential

— END —

1/11/01 APP 6-4